

2022

Statewide Airfield Pavement Management Program



Airport Pavement Evaluation Report

SPG - Albert Whitted Airport | *District 7*



AVIATION



Florida Department of Transportation

Statewide Airfield Pavement Management Program

Airport Pavement Evaluation Report

Prepared by:

*FDOT Aviation Office
605 Suwannee Street
Tallahassee, Florida 32399-0450*

Website: [FDOT Aviation Office](#)

Interactive Web Application: [FDOT SAPMP Interactive Web Application](#)

TABLE OF CONTENTS

EXECUTIVE SUMMARY	1
<i>Program Background.....</i>	<i>1</i>
<i>Current Pavement Conditions</i>	<i>2</i>
<i>Forecasted Pavement Conditions</i>	<i>4</i>
<i>Major Rehabilitation Planning 2023-2032</i>	<i>5</i>
CHAPTER 1 – INTRODUCTION.....	9
1.1 Background	9
1.2 Stakeholders	11
1.3 General Scope of Work	11
1.4 FDOT SAPMP Objectives	12
CHAPTER 2 – METHODOLOGY.....	15
2.1 Airfield Pavement Database.....	15
2.2 Airfield Pavement Record Keeping (Historical Records Research).....	16
2.3 Airfield Pavement Structure.....	16
2.3.1 Asphalt Concrete.....	17
2.3.2 Portland Cement Concrete	17
2.3.3 Composite Structure – Whitetopping Pavement	17
2.4 Airfield Pavement Traffic	18
2.5 Pavement Management Program Network Definition Terminology	18
2.5.1 Pavement Network Identification	18
2.5.2 Pavement Branch Identification	18
2.5.3 Pavement Section Identification	19
2.5.4 Pavement Sample Unit Identification	19
2.5.5 Terminology Summary	19
2.6 Airfield PCI Survey Methodology	19
2.6.1 Pavement Distress Types.....	20
2.6.2 PCI Survey Procedures.....	21
CHAPTER 3 – AIRFIELD PAVEMENT SYSTEM INVENTORY.....	24
3.1 Airfield Pavement Network Information.....	24
3.1.1 Previous and/or Anticipated Airfield Pavement Construction	24
3.1.2 Estimated Pavement Age	27
3.1.3 Functional Use	29
3.1.4 Pavement Surface Type.....	29
3.1.5 Pavement System Inventory Details.....	30
CHAPTER 4 – AIRFIELD PAVEMENT CONDITION ANALYSIS	34
4.1 Airfield Pavement Condition Index.....	34
4.1.1 Network-Level Analysis.....	34
4.1.2 Branch-Level Analysis.....	34
4.1.3 Section-Level Analysis	37
4.2 Summary of Pavement Condition Evaluation Results	41

4.2.1 Network-Level Observations	41
4.2.2 Branch-Level Observations	41
CHAPTER 5 – SAPMP CUSTOMIZATION.....	48
5.1 Network-Level Customization.....	48
5.2 Pavement Condition Forecasts	48
5.2.1 Forecasting PCI Considerations.....	49
5.2.2 Performance Models	49
5.2.3 Branch-Level Pavement Condition Forecast.....	49
5.2.4 Section-Level Pavement Condition Forecast.....	50
5.3 Critical PCI Value.....	52
5.4 Localized Maintenance and Repair	55
5.4.1 Localized Maintenance and Repair Approach	55
5.4.2 Localized Work Types.....	56
5.4.3 Localized Maintenance Planning-Level Unit Costs	58
5.4.4 Localized Maintenance and Repair Policy	58
5.5 Major Rehabilitation	61
5.5.1 Major Rehabilitation Pavement Section Development	61
5.5.2 Major Rehabilitation Planning-Level Unit Costs	63
CHAPTER 6 – M&R PLANNING AND BUDGET SCENARIO ANALYSIS	65
6.1 Localized Maintenance and Repair Analysis and Recommendations	65
6.2 Major Rehabilitation Needs.....	67
6.2.1 10-Year Unconstrained Budget Major Rehabilitation Needs	68
CHAPTER 7 – CONCLUSION.....	72
7.1 Recommendations	72
7.1.1 Continued PCI Surveys.....	72
7.1.2 Localized Maintenance and Repair	72
7.1.3 Major Rehabilitation.....	72
7.1.4 Pavement Management System.....	72
7.2 Supporting Documents	73
Airfield Pavement Network Definition Exhibit.....	73
Airfield Pavement System Inventory Exhibit	73
Airfield Pavement Estimated Age Exhibit	73
Airfield Pavement Condition Index Exhibit.....	73
Airfield Pavement Major Rehabilitation Exhibit	73
Inspection Photograph Documentation.....	73
7.3 Conclusion.....	74
7.4 References.....	74

APPENDIX


Appendix A: Airfield Pavement Analysis

Appendix B: Maintenance and Rehabilitation Planning Needs

Appendix C: Technical Exhibits

Appendix D: Inspection Photograph Documentation

Appendix E: Inspection Distress Details



LIST OF TABLES

Table E.1: Pavement Condition Index Summary (Current PCI Survey) – Section Level.....	2
Table E.2: Forecasted PCI Values 2023-2032 – Section-Level.....	4
Table E.3: Major Rehabilitation Planning 2023-2032.....	6
Table 1.2: FDOT SAPMP Stakeholders	11
Table 2.5.5: SAPMP Terminology	19
Table 2.6.1 (a): Pavement Distress Types – Asphalt Concrete	20
Table 2.6.1 (b): Pavement Distress Types – Portland Cement Concrete.....	21
Table 2.6.2 (a): Recommended Sampling Rates for Asphalt Concrete.....	21
Table 2.6.2 (b): Recommended Sampling Rates for Portland Cement Concrete	22
Table 3.1.1: Summary of Previous and/or Anticipated Airfield Pavement Construction	24
Table 3.1.5: Pavement System Inventory Details	30
Table 4.1.2: Current Condition Summary – Branch-Level	37
Table 4.1.3: Latest Pavement Condition Index Summary – Section-Level.....	38
Table 5.2.4: Forecasted PCI Values 2023-2032 – Section-Level	50
Table 5.3 (a): AIP Handbook PCI Requirements for Airfield Pavement Projects.....	53
Table 5.3 (b): Critical PCI Values by Branch Use	53
Table 5.4.3 (a): Localized M&R Planning-Level Unit Costs – Asphalt Concrete	58
Table 5.4.3 (b): Localized M&R Planning-Level Unit Costs – Portland Cement Concrete.....	58
Table 5.4.4: AC Pavement Localized Preventive& Stopgap Maintenance & Repair Policy	59
Table 5.4.5: PCC Pavement Localized Preventive& Stopgap Maintenance & Repair Policy	60
Table 5.5.1: Conceptual Pavement Sections for Major Rehabilitation	62
Table 5.5.2: RL Major Rehabilitation Planning-Level Unit Cost by Pavement Type	63
Table 6.1 (a): Year 1 Summary of Localized Maintenance	65
Table 6.1 (b): Year 1 Localized Maintenance by Work Type Summary	66
Table 6.1 (c): Section-Level Year 1 Localized M&R Planning Cost Summary	66
Table 6.2.1 (a): Section-Level 10-Year Major Rehabilitation Needs	68

LIST OF FIGURES

Figure E.1: PCI Rating	1
Figure E.2: Current Condition Summary – Branch-Level	2
Figure E.3: 10-Year Major Rehabilitation Needs by Program Year	7
Figure 1.1: Florida Aviation System (Facilities with Pavement) and FDOT Districts	10
Figure 1.4: Pavement Life and the Effect of Treatments	13
Figure 2: FDOT SAPMP General Process	15
Figure 3.1.1 (a): Airfield Pavement Network Definition Exhibit	25
Figure 3.1.1 (b): Airfield Pavement System Inventory Exhibit	26
Figure 3.1.2 (a): Age of Pavements at PCI Survey	27
Figure 3.1.2 (b): Airfield Pavement Estimated Age Exhibit	28
Figure 3.1.3: Airfield Pavement Branch Use by Area (SF)	29
Figure 3.1.4: Airfield Pavement Surface Type by Area (SF)	30
Figure 4.1.1: Current Condition – Overall Network	34
Figure 4.1.2 (a): Current Condition Summary – Branch-Level	34
Figure 4.1.2 (b): Current Condition – Runway	35
Figure 4.1.2 (c): Current Condition – Taxiway	35
Figure 4.1.2 (d): Current Condition – Apron	36
Figure 4.1.3: Airfield Pavement Condition Index Exhibit	40
Figure 5.2.3: Forecasted Branch-Level Pavement Performance	49
Figure 5.3 (a): Pavement Life and the Effect of Treatments	52
Figure 5.3 (b): Major Rehabilitation Planning Decision Diagram, $PCI < \text{Critical PCI}$	54
Figure 5.3 (c): Major Rehabilitation Planning Decision Diagram, $PCI \geq \text{Critical PCI}$	54
Figure 6.2.1 (a): 10-Year Major Rehabilitation Needs by Program Year	69
Figure 6.2.1 (b): Airfield Pavement Major Rehabilitation Exhibit	70



Executive Summary



Executive Summary

Program Background

The FDOT Aviation Office (AO) has a mission to provide a safe and secure air transportation system that ensures the mobility of people and goods, enhances economic prosperity, and preserves the quality of our environment and communities. As part of ongoing efforts in fulfilling this mission, the Aviation Office is executing a System Update to the Statewide Airfield Pavement Management Program (SAPMP). The scope of the SAPMP encompasses 95 public-use airport facilities distributed throughout the seven (7) participating FDOT Districts. Albert Whitted Airport's System Update results are presented in this report and can be utilized by FDOT and the Federal Aviation Administration (FAA) to identify, prioritize, and schedule pavement maintenance, repair, and major rehabilitation projects.

Pavement condition was assessed utilizing the pavement condition index (PCI) methodology as defined in FAA Advisory Circular 150/5380-7B "Airport Pavement Management Program (PMP)" using the procedures documented in ASTM D5340-20 "Standard Test Method for Airport Pavement Condition Index Surveys".

The PCI methodology provides a means for systematically assessing pavement condition and provides an indication of the degree of maintenance, repair, rehabilitation, or reconstruction efforts required to sustain functional pavement conditions. Pavement deterioration, in accordance with ASTM D5340-20, is characterized in terms of distinct distress types, distress severity levels, and quantity of distress. This information is utilized to calculate a PCI value ranging from 0 to 100, which provides an indication of the overall condition of the pavement, with "100" indicating a pavement in new condition and "0" indicating a failed pavement section. This is graphically depicted in **Figure E.1**.

Figure E.1: PCI Rating

Color	Range	Condition Rating
	86-100	Good
	71-85	Satisfactory
	56-70	Fair
	41-55	Poor
	26-40	Very Poor
	11-25	Serious
	0-10	Failed

Current Pavement Conditions

In April 2022, approximately 1.6 million square feet of pavement was assessed as part of the airside pavement network PCI survey at Albert Whitted Airport (SPG). In general, airfield pavements at SPG are in Satisfactory condition with an area-weighted PCI of 77. The area-weighted average PCI values of the runways, taxiways, and aprons are 90, 69, and 73, respectively. **Figure E.2** and **Table E.1** summarize the current PCI values for SPG.

Figure E.2: Current Condition Summary – Branch-Level




Table E.1: Pavement Condition Index Summary (Current PCI Survey) – Section Level

Network ID	Branch ID	Branch Use	Section ID	Area (SF)	PCI	Condition Rating
SPG	RW 7-25	Runway	6205	18,375	88	Good
SPG	RW 7-25	Runway	6207	22,950	79	Satisfactory
SPG	RW 7-25	Runway	6208	21,525	80	Satisfactory
SPG	RW 7-25	Runway	6210	147,650	79	Satisfactory
SPG	RW 7-25	Runway	6213	19,590	84	Satisfactory
SPG	RW 7-25	Runway	6215	30,125	91	Good
SPG	RW 7-25	Runway	6220	2,875	100	Good
SPG	RW 7-25	Runway	6225	5,285	100	Good
SPG	RW 18-36	Runway	6105	217,732	100	Good
SPG	TW A	Taxiway	103	17,162	50	Poor
SPG	TW A	Taxiway	105	15,000	38	Very Poor
SPG	TW A	Taxiway	110	21,000	44	Poor
SPG	TW A	Taxiway	115	65,457	57	Fair
SPG	TW A	Taxiway	125	1,540	100	Good
SPG	TW A	Taxiway	130	3,523	100	Good
SPG	TW A1	Taxiway	120	4,672	86	Good
SPG	TW A2	Taxiway	410	5,577	90	Good

Airport Pavement Evaluation Report

Statewide Airfield Pavement Management Program

2022

Network ID	Branch ID	Branch Use	Section ID	Area (SF)	PCI	Condition Rating
SPG	TW A3	Taxiway	310	5,518	89	Good
SPG	TW A4	Taxiway	610	5,518	89	Good
SPG	TW A4	Taxiway	620	11,150	87	Good
SPG	TW B	Taxiway	205	87,871	60	Fair
SPG	TW B	Taxiway	210	18,217	48	Poor
SPG	TW B	Taxiway	215	6,420	75	Satisfactory
SPG	TW B1	Taxiway	250	1,246	100	Good
SPG	TW B1	Taxiway	255	2,142	100	Good
SPG	TW B2	Taxiway	260	3,445	100	Good
SPG	TW B2	Taxiway	265	2,731	100	Good
SPG	TW B3	Taxiway	270	3,445	100	Good
SPG	TW B3	Taxiway	275	2,731	100	Good
SPG	TW B4	Taxiway	280	4,813	100	Good
SPG	TW B4	Taxiway	285	2,142	100	Good
SPG	TW C	Taxiway	305	75,170	94	Good
SPG	TW C	Taxiway	307	29,730	50	Poor
SPG	TW C	Taxiway	308	33,474	51	Poor
SPG	TW D	Taxiway	155	8,835	100	Good
SPG	TW D	Taxiway	157	3,327	100	Good
SPG	TW D	Taxiway	160	1,353	100	Good
SPG	TW D	Taxiway	510	33,920	64	Fair
SPG	TW D	Taxiway	515	23,608	82	Satisfactory
SPG	TW D1	Taxiway	450	6,159	65	Fair
SPG	TW D2	Taxiway	740	29,398	86	Good
SPG	TW D3	Taxiway	470	3,795	61	Fair
SPG	TW D3	Taxiway	475	1,901	68	Fair
SPG	TW D5	Taxiway	150	5,816	90	Good
SPG	AP	Apron	4110	126,574	42	Poor
SPG	AP	Apron	4120	33,335	50	Poor
SPG	AP	Apron	4135	42,820	64	Fair
SPG	AP	Apron	4145	9,084	51	Poor
SPG	AP	Apron	4150	5,101	100	Good
SPG	AP	Apron	4155	41,633	100	Good
SPG	AP	Apron	4160	37,874	100	Good
SPG	AP	Apron	4165	36,941	100	Good
SPG	AP FUEL	Apron	4510	6,767	85	Satisfactory
SPG	AP HELI	Apron	4610	21,255	63	Fair
SPG	AP MID	Apron	4405	85,370	90	Good
SPG	AP MID	Apron	4410	15,414	85	Satisfactory
SPG	AP NW	Apron	4310	76,197	68	Fair
SPG	AP NW	Apron	4315	35,173	83	Satisfactory
SPG	AP NW	Apron	4320	4,732	73	Satisfactory
SPG	AP NW	Apron	4325	14,232	90	Good

Forecasted Pavement Conditions

Table E.2 provides section-level details for PCI forecasts. Pavement condition forecasts should be used for planning purposes only, as the actual condition of sections is subject to sensitivities in changes of traffic and maintenance frequency.

The estimation of forecasted PCI values gives no assurance of future pavement conditions as PCI values represent an engineering estimation to be used as a planning tool. Forecasted PCI data should not be the sole metric for determining the year in which a project should be planned. Design-level planning should be undertaken by the responsible engineer prior to the development of airfield design plans.

Table E.2: Forecasted PCI Values 2023-2032 – Section-Level

Network ID	Branch ID	Section ID	Current PCI	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032
SPG	RW 7-25	6205	88	86	84	82	81	79	77	75	74	72	70
SPG	RW 7-25	6207	79	77	75	73	72	70	68	66	65	63	61
SPG	RW 7-25	6208	80	78	76	74	73	71	69	67	66	64	62
SPG	RW 7-25	6210	79	77	75	73	72	70	68	66	65	63	61
SPG	RW 7-25	6213	84	82	80	79	77	76	75	74	73	72	71
SPG	RW 7-25	6215	91	89	87	85	84	82	80	78	77	75	73
SPG	RW 7-25	6220	100	98	96	94	93	91	89	87	86	84	82
SPG	RW 7-25	6225	100	98	96	94	93	91	89	87	86	84	82
SPG	RW 18-36	6105	100	98	96	94	93	91	89	87	86	84	82
SPG	TW A	103	50	49	49	48	47	46	45	44	44	43	41
SPG	TW A	105	38	36	34	32	30	28	26	24	22	20	18
SPG	TW A	110	44	42	41	39	37	35	33	31	29	27	25
SPG	TW A	115	57	56	55	55	54	53	52	52	51	50	49
SPG	TW A	125	100	97	95	92	90	88	86	84	82	80	79
SPG	TW A	130	100	97	95	92	90	88	86	84	82	80	79
SPG	TW A1	120	86	84	82	80	79	77	76	75	74	72	71
SPG	TW A2	410	90	88	86	84	82	81	79	78	76	75	74
SPG	TW A3	310	89	87	85	83	81	80	78	77	76	74	73
SPG	TW A4	610	89	87	85	83	81	80	78	77	76	74	73
SPG	TW A4	620	87	85	83	81	80	78	77	75	74	73	72
SPG	TW B	205	60	59	58	58	57	56	56	55	54	53	53
SPG	TW B	210	48	47	45	44	43	41	39	38	36	34	32
SPG	TW B	215	75	73	72	71	70	69	68	67	66	66	65
SPG	TW B1	250	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B1	255	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B2	260	100	97	95	93	90	88	87	85	83	81	80
SPG	TW B2	265	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B3	270	100	97	95	93	90	88	87	85	83	81	80
SPG	TW B3	275	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B4	280	100	97	95	93	90	88	87	85	83	81	80
SPG	TW B4	285	100	97	95	92	90	88	86	84	82	80	79
SPG	TW C	305	94	91	89	87	86	84	82	80	79	77	76

Network ID	Branch ID	Section ID	Current PCI	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032
SPG	TW C	307	50	49	48	47	45	44	43	41	39	38	36
SPG	TW C	308	51	50	49	48	47	45	44	43	41	39	38
SPG	TW D	155	100	96	94	91	89	87	85	83	81	80	78
SPG	TW D	157	100	97	95	92	90	88	86	84	82	80	79
SPG	TW D	160	100	97	95	92	90	88	86	84	82	80	79
SPG	TW D	510	64	63	63	62	61	61	60	60	59	59	58
SPG	TW D	515	82	80	79	77	76	74	73	72	71	70	69
SPG	TW D1	450	65	64	63	63	62	62	61	60	60	59	59
SPG	TW D2	740	86	84	82	80	78	77	75	74	72	71	70
SPG	TW D3	470	61	60	60	59	59	58	58	58	57	57	56
SPG	TW D3	475	68	67	66	65	65	64	63	62	62	61	61
SPG	TW D5	150	90	87	85	83	82	80	78	77	75	74	72
SPG	AP	4110	42	40	38	36	34	32	29	26	23	20	17
SPG	AP	4120	50	47	45	43	41	39	36	34	32	30	28
SPG	AP	4135	64	61	59	57	55	53	50	48	46	44	42
SPG	AP	4145	51	48	46	44	42	40	37	35	33	31	29
SPG	AP	4150	100	96	93	91	89	87	85	82	80	78	76
SPG	AP	4155	100	96	93	91	89	87	85	82	80	78	76
SPG	AP	4160	100	94	91	89	87	85	83	81	79	77	75
SPG	AP	4165	100	96	93	91	89	87	85	82	80	78	76
SPG	AP FUEL	4510	85	82	81	79	77	75	73	71	70	68	67
SPG	AP HELI	4610	63	62	61	60	59	58	57	56	56	55	54
SPG	AP MID	4405	90	87	85	83	81	79	77	76	74	72	70
SPG	AP MID	4410	85	82	81	79	77	75	73	71	70	68	67
SPG	AP NW	4310	68	66	65	64	62	61	60	59	58	58	57
SPG	AP NW	4315	83	81	79	77	75	73	72	70	68	67	66
SPG	AP NW	4320	73	71	69	68	66	65	64	63	62	60	60
SPG	AP NW	4325	90	87	85	83	81	79	76	74	72	70	68

Major Rehabilitation Planning 2023-2032

Localized maintenance and repair policies identified within this report are categorized as preventive or stopgap based on FDOT SAPMP and FAA maintenance policies and recommendations. Major rehabilitation is identified within the FDOT SAPMP as a major construction activity that results in a reset of a pavement section's PCI to a value of 100. Major rehabilitation activities can include mill and Asphalt Concrete (AC) overlay, Portland cement concrete (PCC) pavement repair and slab replacement, and full-depth reconstruction. It is recommended that the Airport use this report as a planning tool for future project development and prioritization. Localized maintenance, repair, and major rehabilitation recommendations should be considered as planning-level only. Final localized maintenance, repair, and major rehabilitation recommendations are subject to change based on Airport prioritization and further design-level evaluations.

Due to FAA Order 5100.38D Change 1 Airport Improvement Program (AIP) Handbook (February 26, 2019), a substantial update to the FDOT SAPMP policy on identifying major rehabilitation

work has been incorporated in this System Update. In previous System Updates, major rehabilitation had been identified for pavement sections below a PCI Value of 65; however, based on the thresholds identified by the FAA in the AIP Handbook, major rehabilitation will now be identified for pavement sections below a PCI value of 70.


The results of the maintenance, repair, and major rehabilitation analysis identified approximately \$13.68M in major rehabilitation needs for the 10-year forecast period. Year 1 major needs are \$9.19M and localized maintenance needs for Year 1 are \$0.01M.

Table E.3: Major Rehabilitation Planning 2023-2032

Program Year	Network ID	Branch ID	Section ID	Surface	Area (SF)	PCI Before	Rehabilitation Type	Planning Cost Estimate
2023	SPG	AP NW	4310	AC	76,197	66	AC Rehabilitation	\$ 801,000
2023	SPG	TW A	103	AC	17,162	49	AC Reconstruction	\$ 318,000
2023	SPG	TW A	105	AAC	15,000	36	AC Reconstruction	\$ 278,000
2023	SPG	TW A	110	AAC	21,000	42	AC Reconstruction	\$ 389,000
2023	SPG	TW A	115	AAC	65,457	56	AC Rehabilitation	\$ 688,000
2023	SPG	TW B	205	AAC	87,871	59	AC Rehabilitation	\$ 923,000
2023	SPG	TW B	210	AAC	18,217	47	AC Reconstruction	\$ 338,000
2023	SPG	TW C	307	AAC	29,730	49	AC Reconstruction	\$ 550,000
2023	SPG	TW C	308	AAC	33,474	50	AC Reconstruction	\$ 620,000
2023	SPG	TW D	510	AC	33,920	63	AC Rehabilitation	\$ 357,000
2023	SPG	TW D1	450	AC	6,159	64	AC Rehabilitation	\$ 65,000
2023	SPG	TW D3	470	AC	3,795	60	AC Rehabilitation	\$ 40,000
2023	SPG	TW D3	475	AC	1,901	67	AC Rehabilitation	\$ 20,000
2023	SPG	AP	4110	AC	126,574	40	AC Reconstruction	\$ 2,342,000
2023	SPG	AP	4120	AAC	33,335	47	AC Reconstruction	\$ 617,000
2023	SPG	AP	4135	AAC	42,820	61	AC Rehabilitation	\$ 450,000
2023	SPG	AP	4145	AAC	9,084	48	AC Reconstruction	\$ 169,000
2023	SPG	AP HELI	4610	AC	21,255	62	AC Rehabilitation	\$ 224,000
2024	SPG	AP NW	4320	AC	4,732	69	AC Rehabilitation	\$ 53,000
2027	SPG	RW 7-25	6207	AAC	22,950	70	AC Rehabilitation	\$ 293,000
2027	SPG	RW 7-25	6210	AAC	147,650	70	AC Rehabilitation	\$ 1,885,000
2027	SPG	TW B	215	AC	6,420	69	AC Rehabilitation	\$ 82,000
2028	SPG	RW 7-25	6208	AAC	21,525	69	AC Rehabilitation	\$ 289,000
2029	SPG	AP NW	4315	AC	35,173	70	AC Rehabilitation	\$ 495,000
2030	SPG	AP MID	4410	AC	15,414	70	AC Rehabilitation	\$ 228,000
2030	SPG	AP FUEL	4510	AC	6,767	70	AC Rehabilitation	\$ 100,000
2031	SPG	AP NW	4325	AAC	14,232	70	AC Rehabilitation	\$ 221,000
2031	SPG	TW D	515	AC	23,608	70	AC Rehabilitation	\$ 367,000
2032	SPG	TW D2	740	AAC	29,398	70	AC Rehabilitation	\$ 479,000

**All planning cost values have been rounded up to the nearest thousand dollars.*

Figure E.3: 10-Year Major Rehabilitation Needs by Program Year





Chapter 1: Introduction



Chapter 1 – Introduction

The State of Florida has 128 public airports, 100 of which are recognized as part of the Federal Aviation Administration's (FAA) National Plan of Integrated Airport Systems (NPIAS). These public-use airports are vital to Florida's economy as well as the economy of the United States. The Florida Airport System (FAS) provides opportunities for the State to capitalize on an increasingly global marketplace. Florida's system of commercial service and general aviation airports are important to businesses throughout the State as air travel is essential to tourism, Florida's most prominent industry.

1.1 Background

In 1992, the Florida Department of Transportation (FDOT) established the Statewide Airfield Pavement Management Program (SAPMP) to provide program managers, District Aviation Offices, and Airport operators with a system to proactively manage airfield pavement infrastructure within the FAS. The SAPMP includes network-level Pavement Condition Index (PCI) surveys for Airport facilities that are categorized as General Aviation (GA), Reliever (RL), and Primary/Commercial (PR). Currently, the SAPMP includes 95 participating public-use airports with pavement facilities and provides its users with comprehensive data to better manage their pavement assets.

There are millions of square feet of pavement infrastructure at airports across a network of runways, taxiways, aprons, and other areas. This pavement infrastructure is vital to the support and safety of aircraft operations. Timely maintenance, repair, and major rehabilitation of pavement infrastructure allows the Airport to operate safely, efficiently, and economically without excessive down time.

Airports participating in the Airport Improvement Program (AIP) Grant Program are required by the FAA to develop and implement a pavement maintenance program in order to be eligible for funding, per FAA Advisory Circulars 150/5380-6C "Guidelines and Procedures for Maintenance of Airport Pavements" and 150/5380-7B "Airport Pavement Management Program (PMP)". The AIP program requires detailed assessments of airfield pavements at least once a year for a pavement management program. The frequency of the detailed inspections may be extended to every three years if the pavement is assessed according to the PCI survey procedure described in ASTM D5340-20 "Standard Test Method for Airport Pavement Condition Index Surveys".

In general, adherence to the FAA Advisory Circulars is mandatory for projects funded with federal grant monies through the AIP program and with revenue from the Passenger Facilities Charges (PFC) Program. Further information is detailed in FAA Grant Assurance No. 11 "Pavement Maintenance," No. 34 "Policies, Standards, and Specifications," and PFC Assurance No. 9 "Standards and Specifications." The FDOT performs the SAPMP System Updates for the benefit of participating public-use and publicly-owned airports through the Aviation Office (AO).


The SAPMP addresses the requirements of maintaining an effective pavement management program for participating airports at the network level. Network-level management of pavement assets provides insight for short-term and long-term budget needs, understanding of the overall condition of the network (current and future), and knowledge of the pavement facilities that are

Airport Pavement Evaluation Report

Statewide Airfield Pavement Management Program

under consideration for projects. A network-level evaluation can support the identification of maintenance, repair, and major rehabilitation needs and budgetary planning-level opinions of probable construction costs.

Figure 1.1: Florida Aviation System (Facilities with Pavement) and FDOT Districts



1.2 Stakeholders

The SAPMP is performed for the benefit of the stakeholders. The table below outlines the primary stakeholders of the FDOT SAPMP and their role in the program.

Table 1.2: FDOT SAPMP Stakeholders

Role	Description
FAA Orlando Airports District Office (Orlando ADO)	Key Stakeholder: local ADO Program Manager personnel that oversees the grant administration of AIP grant with Planning Agency Sponsor (Florida Department of Transportation).
Florida Department of Transportation (FDOT)	Key Stakeholder: the FDOT is the "Sponsor" for the AIP grant agreement. Specifically, the Aviation Office (AO) provides development and operations support for the Florida Airport System.
FDOT District Offices	The seven (7) FDOT District Offices, specifically the Aviation representatives, provide essential support to the SAPMP System Update and the AO Program Manager (AO-PM). Each District supports the SAPMP's ongoing efforts by providing local construction cost information throughout the State, which is used as the basis of development for maintenance, repair, and major rehabilitation opinions of probable construction costs for planning purposes.
Participating Public-Use and Publicly-Owned Airports	The airports are the end-user and primary beneficiary of the SAPMP. The SAPMP provides a specific Airport Pavement Evaluation Report that meets the requirements of the FAA AC 150/5380-7B. Individual participating airports are provided a final Airport Pavement Evaluation Report by the Consultant that is specific to each airport's airfield PCI assessment.
Aviation Office Program Manager (AO-PM)	FDOT AO Airport Engineering Manager: oversees and manages the overall Program System Update.

1.3 General Scope of Work

The SAPMP is limited to performing tasks in adherence to the key elements of an effective pavement management program on a statewide level. The primary tasks undertaken to update the FDOT SAPMP include, but are not limited to:

- » Research and evaluation of existing record documentation;
- » Establishment of a pavement system inventory;
- » Development of a pavement network definition map and supplemental GIS model;
- » Functional pavement evaluations via the PCI assessment method;
- » Customization of PAVER™ software including prioritization, policies, and performance models;
- » Analysis of condition data; and
- » Maintenance, repair, and rehabilitation planning.

1.4 FDOT SAPMP Objectives

The SAPMP enables the FDOT AO and FAA to monitor pavement conditions at airports in the Florida Airport System. The SAPMP provides objective condition information needed to make informed decisions regarding the significant capital investment that the public-use airport pavement infrastructure represents.

Airport staff are responsible for making decisions regarding the timing and type of maintenance and rehabilitation activities that should be completed in order to maintain an acceptable operational condition and adequate load-carrying capacity. Utilizing the SAPMP will help Airport staff better understand the relative condition of their pavement facilities and when those facilities should be rehabilitated. The data collected from the SAPMP can be used for project programming for the next 10 years. This report summarizes the data collection, analysis, program update, and implementation of the FDOT SAPMP.


A comprehensive SAPMP provides information that assists with the project programming process. The primary objectives of the FDOT SAPMP consist of the following:

- » Assist airports in meeting the requirements of Public Law 103-305;
- » Assist airports in complying with FAA Grant Assurances 11 and 19;
- » Provide airports with functional pavement condition in accordance with ASTM D5340-20 (current) and with the FAA AC 150/5380-7B (current) based on visual assessment efforts;
- » Provide airports with planning-level guidance on maintenance, repair, and rehabilitation in accordance with the FAA AC 150/5380-6C (current) based on pavement conditions and distress data in terms of type, severity, and extent; and
- » Provide airports, FDOT Districts, FDOT AO, and the FAA Airports District Office with long-term, planning-level forecasts of pavement performance and rehabilitation budgetary needs (e.g., maintenance, repair, and major reconstruction) through reports.

From a pavement management perspective, one of the most valuable aspects of the PCI methodology is the ability to save money by effectively prioritizing the rehabilitation of pavement assets before they reach critical condition. Critical PCI values are assigned to deterioration models for pavement assets based on their respective use and rank. The concept of critical PCI will be further discussed in **Chapter 5**, but it is used as a benchmark to help identify pavement assets that should receive rehabilitation. In doing so, the PCI methodology can help create a proactive maintenance and rehabilitation (M&R) strategy to effectively address pavement projects before the cost of these projects increases significantly.

With M&R costs escalating over time, the consequences of inadequate maintenance practices can result in an inefficient allocation of funding. If maintenance is conducted before a significant decline in pavement condition occurs, substantial repair and/or rehabilitation costs may be avoided or delayed. **Figure 1.4** illustrates how the cost of pavement repairs can significantly increase if M&R activities are delayed.

Figure 1.4: Pavement Life and the Effect of Treatments



FAA Eligibility Thresholds: ☐ >70: Routine Maintenance ☐ 55-70: Rehabilitation Eligible ☐ <55: Reconstruction Eligible

*Figure is for conceptual purposes only – unit costs are not specific to airfield pavements




Chapter 2: Methodology



Chapter 2 – Methodology

An effective pavement management program incorporates both the regular collection of pavement condition information and communication of information to appropriate sponsors. This chapter of the report defines the specific methods utilized as part of the SAPMP System Update to meet the requirements of an effective pavement management system as defined by the FAA AC 150/5380-7B. **Figure 2** summarizes the overall process for the FDOT SAPMP.

Figure 2: FDOT SAPMP General Process



2.1 Airfield Pavement Database

This SAPMP utilizes PAVERTM 7.0 software as its airfield pavement database. The PAVERTM software application was developed by the U.S. Army Construction Engineering Research Laboratory and sponsored by the FAA, Federal Highway Administration, U.S. Army, U.S. Air Force, and U.S. Navy to meet the objectives of an effective pavement management system. The PAVERTM database includes a network-level inventory of the participating airport's eligible airfield pavement facilities. PAVERTM can achieve the following pavement management objectives:

- » Create a manageable inventory system;
- » Analyze the current condition of pavements in accordance with ASTM D5340-20;
- » Develop pavement performance models to forecast conditions; and
- » Generate maintenance, repair, and major rehabilitation recommendations based on budgetary scenarios.

PAVERTM inventory management is based on a tiered organizational structure consisting of networks, branches, sections, and samples, with the sample being the smallest unit of management. Critical elements of an effective pavement management program are maintained within the network-level PAVERTM database and typically consist of pavement inventory

characteristics, pavement structure, work history, historic condition records, and analytical customization.

2.2 Airfield Pavement Record Keeping (Historical Records Research)

In accordance with the FAA AC 150/5380-7B, it is a best practice that airports maintain records of all airfield construction and maintenance (routine, emergency, and proactive) related to the pavement facilities. These records should consist of:

- » Location and limits of work;
- » Types and severities of repaired distresses;
- » Work type and cost; and
- » Supporting documents (e.g., contract documents, construction drawings, specifications, bid tabulations, repair products, and photograph records).

As part of the SAPMP, participating airport's staff was asked to provide documentation regarding the historical work performed at the Airport, including construction drawings and bid tabulations. This information is used to identify location, limits, type of work, pavement cross-sections, and representative material costs.

Updated historical data collected during this task was entered into the PAVER™ database. This database includes the following fields for historical information:

- » Date of last construction/rehabilitation
- » Work type performed
- » Comments for documenting pavement cross-section
- » Pavement surface type
- » Section area (limits of work)

The SAPMP PAVER™ database accuracy is limited to the record documentation provided by the participating airports. Airport Sponsors should rely on this information as a planning tool and defer to final as-built plans, record drawings, and/or engineer's construction report for pavement construction records.

2.3 Airfield Pavement Structure

A pavement is a prepared surface designed to provide a continuous, smooth ride at a certain speed and to support an estimated amount of traffic for a certain number of years. A pavement structure is composed of constructed layers consisting of subgrade, subbase, base, structural, and surface courses. For the FDOT SAPMP, two (2) predominant pavement types are classified for evaluation and analysis: Asphalt Concrete (AC) and Portland cement concrete (PCC). Composite Structures, known as Whitetopping Pavements consisting of PCC on AC, are also present at limited airports in Florida and are evaluated separately.

2.3.1 Asphalt Concrete

Asphalt concrete is a pavement comprised of aggregate mixture with an asphalt cement binder. The FDOT SAPMP categorizes three (3) Asphalt Concrete surface types: Asphalt Concrete (AC), Asphalt Concrete overlaid on Asphalt Concrete (AAC), and Asphalt Concrete overlaid on Portland cement concrete (APC).

Asphalt Concrete (AC)

A flexible pavement section consisting of aggregate mixture with asphalt cement binder layered on engineered base course material that is layered on subbase and subgrade soil material.

Asphalt Concrete Overlaid on Asphalt Concrete (AAC)

A flexible pavement section consisting of aggregate mixture with asphalt cement binder layered on an existing flexible AC pavement section. Airfield pavement sections are considered to be AAC when a pavement rehabilitation includes a pavement milling and resurfacing operation or a direct overlay of Asphalt Concrete without surface preparation.

Asphalt Concrete Overlaid on Portland Cement Concrete (APC)

A flexible pavement section consisting of aggregate mixture with asphalt cement binder layered on an existing PCC pavement section. This unique pavement composition may result in distinct pavement distress manifestations known as reflective joint cracking.

2.3.2 Portland Cement Concrete

Portland cement concrete is a pavement comprised of aggregate mixture with a Portland cement binder. The FDOT SAPMP categorizes Portland cement concrete (PCC) as the primary rigid pavement section.

Portland Cement Concrete (PCC)

A rigid pavement section composed of Portland cement concrete placed on a granular or treated base course that is supported on a compacted subgrade. The concrete surface provides a texture of nonskid qualities, prevents the infiltration of surface water into the subgrade, and provides structural support for airplane loading. Rigid pavement construction requires the layout of appropriately designed joints. Concrete overlays built in accordance with the FAA Advisory Circular 150/5320-6F "Airport Pavement Design and Evaluation" are recognized as PCC pavement.

2.3.3 Composite Structure – Whitetopping Pavement

Whitetopping pavement is a composite pavement comprised of relatively thin PCC overlaid on an existing AC pavement structure. There are three (3) types of Whitetopping Pavements: Conventional (WT), Thin (TWT), and Ultra-Thin (UWT).

Conventional Whitetopping (WT)

A composite pavement structure consisting of a modified PCC overlaid on an existing AC pavement section. The modified PCC layer is typically greater than 6 inches in thickness.

Thin Whitetopping (TWT)

A composite pavement structure consisting of modified PCC overlaid on an existing AC pavement section. The modified PCC layer is typically between 4 and 6 inches in thickness.

Ultra-Thin Whitetopping (UWT)

A composite pavement structure consisting of a modified PCC overlaid on an existing AC pavement section. The modified PCC layer is typically between 2 and 4 inches in thickness.

2.4 Airfield Pavement Traffic

A pavement section is typically designed to meet the needs of the user (airlines, air cargo, general aviation, and/or military) in providing a safe, smooth, operational surface. Pavement deterioration generally occurs gradually from aircraft loading and environmental conditions.

This System Update does not involve a study or analysis of SPG's aircraft fleet mix or traffic operations. However, it is strongly recommended that the Airport incorporate the requirements of the FAA AC 150/5320-6F when developing design-level rehabilitation activities; this AC provides guidance on incorporation of aircraft traffic fleet mix data.

2.5 Pavement Management Program Network Definition Terminology

To facilitate an effective pavement management program, a pavement network must be established and subdivided into smaller, manageable working units. Sectioning of the pavement network was established in a prior System Update and was revised during this SAPMP to account for work that has been performed on the airfield since the previous Update. Information from historic records is used to help define the limits of the smaller working units. A critical input for a pavement inventory and network definition is the date of last major construction or rehabilitation, as this type of work will reset the section PCI to a value of 100.

The following sections define the common terms used in pavement management systems and cover their application for this SAPMP System Update.

2.5.1 Pavement Network Identification

Establishing the pavement network is the first step in organizing pavements into a structure for pavement management. The network is the starting point of the hierarchy of pavement management organization. A network typically consists of one or more pavement *branches*, which have one or more pavement *sections*. For example, a network can be all the pavements within an Airport's airfield or all the pavements in a statewide program. For the FDOT SAPMP, a network represents an individual Airport's airfield pavement facilities maintained by the Airport.

2.5.2 Pavement Branch Identification

A pavement branch, also known as a facility, is a logical unit of generally identifiable pavement within a network that has a distinct functional classification. For example, within an airfield, each runway, taxiway, or apron is considered a branch. Each branch contains at least one section but may contain more if pavement feature characteristics are distinct throughout the branch.

2.5.3 Pavement Section Identification

A pavement section, or feature, is a subdivision of a branch and has consistent characteristics throughout its length or area. These characteristics include structural composition (pavement layer material type and thickness), construction history, age, traffic type, traffic frequency, and pavement condition. A section is the basic management unit of a pavement network and is the level at which maintenance, repair, or major rehabilitation treatments are considered.

2.5.4 Pavement Sample Unit Identification

A pavement sample unit is an arbitrarily defined subdivision of a pavement section that has a standard size range of 20 contiguous slabs (± 8 slabs) for PCC pavement and 5,000 contiguous square feet ($\pm 2,000$ SF) for AC. A sample unit is the smallest subdivision of a pavement network and is analyzed during field assessments to establish condition ratings.

2.5.5 Terminology Summary

Below is a summary table, **Table 2.5.5**, with definitions and examples of common SAPMP terminology.

Table 2.5.5: SAPMP Terminology

SAPMP Terminology	Common Definition	Airport Example
Network	Totality of pavement assets maintained by the Airport.	"Tallahassee International Airport – Airfield Pavements"
Branch Name	Commonly defined asset name as established by Airport and by use.	"Runway 18-36"
Branch ID	Codified shorthand name for commonly defined asset established for database identification.	"RW 18-36" RW, Branch Use, "Runway" "Runway 18-36", Runway Facility
Section ID	Codified identification for pavement asset that is distinct by pavement composition, work history, aircraft loading, or condition.	"6105"
Sample Unit	A numeric identification of an area of pavement (5,000 \pm 2,000 SF of AC or 20 \pm 8 slabs of PCC) that has been inspected in accordance with ASTM D5340-20.	"300"

2.6 Airfield PCI Survey Methodology

In adherence to the FAA AC 150/5380-7B, the FDOT SAPMP utilizes the PCI survey method to collect pavement distress data and analyze the condition. The PCI survey procedure is a visual statistical sampling of pavements for recording primary distress types (e.g., cracking and deformation), associated severities, and quantities as defined by the ASTM D5340-20. This effort is the primary means of obtaining and recording pavement distress data. The PCI survey consists primarily of visual assessments of pavement surfaces for signs of distress and deterioration resulting from loading (aircraft) and environmental influences.

Overall, a visual pavement condition survey provides an indication of the cause and rate of deterioration of a pavement section from a functional point of view and can help identify if any underlying structural deficiencies are present. Although a visual PCI survey does not predict the remaining structural life of a pavement section or its ability to support loads, it does assess the rating of the operational surface. Functional condition, determined by the PCI method, can provide a cost-effective means to plan for pavement rehabilitation projects. Timely application of pavement rehabilitation may lead to the extension of functional life of individual pavement sections. This method varies from structural evaluation; functional condition is limited to visually observed distresses and indicative modes of pavement deterioration. A formal structural evaluation analyzes subsurface conditions, material characteristics, and qualitative pavement structure attributes. A structural evaluation may consist of subsurface geotechnical exploration, falling weight deflectometer testing, petrographic testing, material coring, and/or flexural testing.

2.6.1 Pavement Distress Types

For each sample, the severity and quantity of defined distresses are recorded and then analyzed in accordance with the ASTM D5340-20 standard, which identifies 17 AC distress types and 16 PCC distress types. **Tables 2.6.1 (a)** and **2.6.1 (b)** identify these distresses and their common causes or mechanisms.

Table 2.6.1 (a): Pavement Distress Types – Asphalt Concrete

Distress Mechanism	Distress Type
Load	Alligator Cracking Rutting
Climate/Durability	Block Cracking Joint Reflection Cracking Longitudinal and Transverse Cracking (LT) Raveling Shoving Weathering
Construction/Material	Bleeding Corrugation Depression Polished Aggregate Slippage Cracking Swelling
Other	Jet Blast Erosion Oil Spillage Patching and Utility Cut Patching

Table 2.6.1 (b): Pavement Distress Types – Portland Cement Concrete

Distress Mechanism	Distress Type
Load	Corner Break Longitudinal, Transverse, and Diagonal Cracking (LTD) Pumping Shattered Slab/Intersecting Cracks
Climate/Durability	Blowup Durability "D" Cracking Joint Seal Damage Popouts
Construction/Material	Alkali Silica Reaction (ASR) Scaling Shrinkage Cracking
Other	Corner Spalling Joint Spalling Large Patching and Utility Cut Settlement or Faulting Small Patching

2.6.2 PCI Survey Procedures

PCI surveys are conducted on sample units defined in previous System Updates. Sample units are subject to change at the discretion of field personnel and/or to major pavement rehabilitation treatments. Furthermore, access to sample units based on accessibility or operational impacts may affect the overall sampling rate effort at each airport. **Tables 2.6.2 (a) and (b)** define the sampling criteria used by the FDOT SAPMP. A higher sampling rate may be utilized to achieve greater statistical confidence, should the Airport have the available resources to perform PCI survey independent of the FDOT SAPMP.


Table 2.6.2 (a): Recommended Sampling Rates for Asphalt Concrete

Number of Total Sample Units in Section	Runway Sampling Rate	Taxiways, Aprons, and Others Sampling Rate
1 - 4	1	1
5 - 10	2	1
11 - 15	3	2
16 - 30	5	3
31 - 40	7	4
41 - 50	8	5
51 or more	20% but ≤ 20	10% but ≤ 10


Table 2.6.2 (b): Recommended Sampling Rates for Portland Cement Concrete

Number of Total Sample Units in Section	Runway Sampling Rate	Taxiways, Aprons, and Others Sampling Rate
1 - 3	1	1
4 - 6	2	1
7 - 10	3	2
11 - 15	4	2
16 - 20	5	3
21 - 30	7	3
31 - 40	8	4
41 - 50	10	5
51 or more	20% but ≤ 20	10% but ≤ 10

The FDOT SAPMP is limited to select sample units for each section identified in each airport's Airfield Pavement Network Definition. The intent is to perform a limited amount of sample unit PCI surveys to reasonably reflect the functional condition. Due to the limited sampling criteria, there may be instances of pavement distress and deterioration outside of the inspected sample units that were not observed.



Chapter 3: Airfield Pavement System Inventory



Chapter 3 – Airfield Pavement System Inventory

This chapter discusses the inventory data collected from the Airport and summarizes network-level characteristics of the Airport's airfield pavements. At the start of each FDOT SAPMP System Update, all airports are asked to review the existing Airfield Pavement Network Definition Exhibit for accuracy. Furthermore, participating airports are asked to provide documentation of any recent or anticipated construction related to their airfield pavements.

3.1 Airfield Pavement Network Information

3.1.1 Previous and/or Anticipated Airfield Pavement Construction



Based on information provided by the Airport, **Table 3.1.1** summarizes recent or anticipated airfield pavement construction projects since 2017.

Table 3.1.1: Summary of Previous and/or Anticipated Airfield Pavement Construction

Construction Year	Location	Work Type / Pavement Section
2018	AP NW	Mill and Overlay
	TW C	Complete Reconstruction - AC 3" P-403, 6-10" Reclaimed Base
2019	TW D2	Mill and Overlay
2020	AP	New Construction - AC 2" P-402, 5" P-219
2021	AP	Mill and Overlay Variable depth mill, Variable depth P-403 overlay
	TW D	Mill and Overlay
2022	RW 7-25, RW 18-36, TW A, TW B1, TW B2, TW B3, TW B4, TW D	Mill and Overlay 1.5" Variable cold milling, 2" P-403 Overlay
	TW B2, TW B3, TW B4	New Construction - AC 4" P-403, 6" P-211, 12" P-152

The Airport provided a combination of record drawings, reports, and staff input, which aided in developing the construction history of the Airport's pavements since inception. Major rehabilitation and construction activities performed in the last 24 months, or anticipated in the next 24 months, are assumed to restore the PCI to 100. These activities include pavement overlay, mill and overlay, new construction, and/or complete reconstruction. These pavements were not formally subject to a PCI assessment and actual conditions may vary. Furthermore, any localized maintenance or repair performed in the assessment areas that would improve the PCI are considered in the condition analysis.

Figure 3.1.1 (a), the Airfield Pavement Network Definition Exhibit, provides details of the PCI assessment efforts. The Exhibit identifies pavement facilities, surface types, section definitions, and sample unit delineations. **Figure 3.1.1 (b)**, the Airfield Pavement System Inventory Exhibit, provides details of the work history updates communicated by the Airport. The Exhibit provides the approximate limits of recent and/or anticipated construction on the airfield pavement facilities. The limits are based on documentation provided by the Airport and, if constructed, are confirmed during field surveys.




AAC RW 7-25 6205 2 5	AAC RW 7-25 6207 2 6	AAC RW 7-25 6208 2 6	AAC RW 7-25 6210 8 39	AC RW 7-25 6213 2 5	AAC RW 7-25 6220 0 1	AAC RW 7-25 6225 0 1	AC TW A 103 1 4	AAC TW A 105 1 4
AAC TW A 110 2 5	AAC TW A 125 0 1	AAC TW A 130 0 1	AC TW A2 410 1 1	AC TW A3 310 1 1	AC TW A4 610 1 1	AC TW A4 620 1 3	AC TW B2 260 0 1	
AAC TW B2 265 0 1	AC TW B3 270 0 1	AAC TW B3 275 0 1	AAC TW C 308 1 7	AAC TW D 157 0 1	AAC TW D 160 0 1	AC AP MID 4405 3 18	AC AP MID 4410 1 4	

LEGEND

- TYPICAL RUNWAY BRANCH ID
- TYPICAL TAXIWAY BRANCH ID
- TYPICAL APRON BRANCH ID
- PAVEMENT SURFACE TYPE
- PAVEMENT BRANCH ID
- SECTION NUMBER
- NUMBER OF SAMPLE UNITS IN SECTION
NUMBER OF SAMPLE UNITS TO BE INSPECTED
- SECTION NOT INSPECTED DUE TO RECENT CONSTRUCTION. SEE SYSTEM INVENTORY MAP FOR CONSTRUCTION DATES.
- INSPECTED SAMPLE UNITS.

TOTAL SAMPLES INSPECTED = 65
AC: 65 PCC: 0

RUNWAY LENGTHS DEPICTED IN THIS DRAWING ARE FOR PAVEMENT MANAGEMENT PURPOSES ONLY AND MAY NOT MATCH PUBLISHED RUNWAY LENGTHS. DRAWING NOT TO SCALE.



RECENT & ANTICIPATED CONSTRUCTION ACTIVITY		
CONSTRUCTION YEAR	LOCATION	WORK TYPE / PAVEMENT SECTION
2018	AP NW	Mill and Overlay
	TW C	Complete Reconstruction - AC 3" P-403, 6-10" Reclaimed Base
2019	TW D2	Mill and Overlay
2020	AP	New Construction - AC 2" P-402, 5" P-219
2021	AP, TW D	Mill and Overlay Variable depth mill, Variable depth P-403 overlay
2022	RW 18-36, RW 7-25, TW A, TW B1, TW B2, TW B3, TW B4, TW D	Mill and Overlay 1.5" Variable cold milling, 2" P-403 Overlay
	TW B2, TW B3, TW B4	New Construction - AC 4" P-403, 6" P-211, 12" P-152

LEGEND

RW 13-31 — TYPICAL RUNWAY BRANCH ID

TW A — TYPICAL TAXIWAY BRANCH ID

AP S — TYPICAL APRON BRANCH ID

PROJECT YEAR


2017	2022
2018	2023
2019	2024
2020	2025
2021	2026


RUNWAY LENGTHS DEPICTED IN THIS DRAWING ARE FOR PAVEMENT MANAGEMENT PURPOSES ONLY AND MAY NOT MATCH PUBLISHED RUNWAY LENGTHS. DRAWING NOT TO SCALE.

3.1.2 Estimated Pavement Age

Standard pavement design practice considers a design life of 20 years. Design inputs typically require subgrade soil conditions, pavement layer material characteristics, and anticipated loading (aircraft fleet mix) for the design-life period. Based on the review of historic airfield pavement construction activities, **Figure 3.1.2 (a)** summarizes the age of the pavement sections since the last major construction activity has occurred. **Figure 3.1.2 (b)** provides the approximate limits of those age ranges on the airfield pavement facilities. This is intended to be a rough estimate based on interpretation of the limited data available at the time of report. The estimation of pavement age is based on information requested from the Airport.

Figure 3.1.2 (a): Age of Pavements at PCI Survey





LEGEND

TYPICAL RUNWAY BRANCH ID

TYPICAL TAXIWAY BRANCH ID

TYPICAL APRON BRANCH ID

AGE AT INSPECTION


	0-5 Years
	6-10 Years
	11-15 Years
	16-20 Years
	> 20 Years

RUNWAY LENGTHS DEPICTED IN THIS DRAWING ARE FOR PAVEMENT MANAGEMENT PURPOSES ONLY AND MAY NOT MATCH PUBLISHED RUNWAY LENGTHS. DRAWING NOT TO SCALE.

3.1.3 Functional Use

Pavements are subject to variations in aircraft loading patterns based on use and overall operations. This is termed “functional use” or “branch use.” For this SAPMP System Update, the following categories of pavement functional use are identified: runway, taxiway, taxilane, and apron. **Figure 3.1.3** summarizes pavement functional use by area and excludes paved shoulders.

Figure 3.1.3: Airfield Pavement Branch Use by Area (SF)




3.1.4 Pavement Surface Type

The airfield pavement facility surface types within the SAPMP include four (4) common types of pavement: Asphalt Concrete (AC), Asphalt Concrete overlaid on Asphalt Concrete (AAC), Asphalt Concrete overlaid on Portland cement concrete (APC), and Portland cement concrete (PCC).

Based on the record documentation incorporated within the SAPMP database and as observed during airfield pavement field assessments, pavement surface types have been assigned to the various pavement sections. **Figure 3.1.4** summarizes the applicable pavement types observed at SPG.

Figure 3.1.4: Airfield Pavement Surface Type by Area (SF)



3.1.5 Pavement System Inventory Details

The pavement inventory scope includes updates to existing pavement geometry and the development of an AutoCAD model with spatial projection for use within GIS. **Appendix C** includes the Airfield Pavement Network Definition Exhibit and the Airfield Pavement System Inventory Exhibit, which visually summarize the results of the airfield pavement system inventory analysis.

Table 3.1.5 displays the section-level pavement inventory data, which is based on record documentation provided by the airports and from previous System Updates. The information presented relies on the accuracy and the adequacy of data provided. In some cases, characteristics such as pavement area may be estimated based on aerial interpretation of spatially-projected imagery. Additionally, if the last construction date is unknown, a date of January 1 of the estimated year was assigned to the section. The accuracy of data is appropriate for this network-level planning document. Should the Airport perform rehabilitation work, it is recommended that project-level investigations be performed to support the data accuracy needed for design and construction.

Table 3.1.5: Pavement System Inventory Details

Network ID	Branch ID	Branch Use	Section ID	Area (SF)	Surface Type	Estimate of Last Construction Date
SPG	RW 7-25	Runway	6205	18,375	AAC	6/1/2016
SPG	RW 7-25	Runway	6207	22,950	AAC	6/1/2016
SPG	RW 7-25	Runway	6208	21,525	AAC	6/1/2016
SPG	RW 7-25	Runway	6210	147,650	AAC	6/1/2016
SPG	RW 7-25	Runway	6213	19,590	AC	6/1/2016
SPG	RW 7-25	Runway	6215	30,125	AAC	6/1/2016
SPG	RW 7-25	Runway	6220	2,875	AAC	4/1/2022
SPG	RW 7-25	Runway	6225	5,285	AAC	4/1/2022

Network ID	Branch ID	Branch Use	Section ID	Area (SF)	Surface Type	Estimate of Last Construction Date
SPG	RW 18-36	Runway	6105	217,732	AAC	4/1/2022
SPG	TW A	Taxiway	103	17,162	AC	1/1/1991
SPG	TW A	Taxiway	105	15,000	AAC	1/1/1987
SPG	TW A	Taxiway	110	21,000	AAC	1/1/1987
SPG	TW A	Taxiway	115	65,457	AAC	1/1/1987
SPG	TW A	Taxiway	125	1,540	AAC	4/1/2022
SPG	TW A	Taxiway	130	3,523	AAC	4/1/2022
SPG	TW A1	Taxiway	120	4,672	AC	6/1/2016
SPG	TW A2	Taxiway	410	5,577	AC	6/1/2016
SPG	TW A3	Taxiway	310	5,518	AC	6/1/2016
SPG	TW A4	Taxiway	610	5,518	AC	6/1/2016
SPG	TW A4	Taxiway	620	11,150	AC	1/1/2013
SPG	TW B	Taxiway	205	87,871	AAC	1/1/1988
SPG	TW B	Taxiway	210	18,217	AAC	1/1/1988
SPG	TW B	Taxiway	215	6,420	AC	6/1/2016
SPG	TW B1	Taxiway	250	1,246	AAC	4/1/2022
SPG	TW B1	Taxiway	255	2,142	AAC	4/1/2022
SPG	TW B2	Taxiway	260	3,445	AC	4/1/2022
SPG	TW B2	Taxiway	265	2,731	AAC	4/1/2022
SPG	TW B3	Taxiway	270	3,445	AC	4/1/2022
SPG	TW B3	Taxiway	275	2,731	AAC	4/1/2022
SPG	TW B4	Taxiway	280	4,813	AC	4/1/2022
SPG	TW B4	Taxiway	285	2,142	AAC	4/1/2022
SPG	TW C	Taxiway	305	75,170	AC	5/25/2018
SPG	TW C	Taxiway	307	29,730	AAC	1/1/1991
SPG	TW C	Taxiway	308	33,474	AAC	1/1/1991
SPG	TW D	Taxiway	155	8,835	AAC	11/1/2021
SPG	TW D	Taxiway	157	3,327	AAC	4/1/2022
SPG	TW D	Taxiway	160	1,353	AAC	4/1/2022
SPG	TW D	Taxiway	510	33,920	AC	1/1/2002
SPG	TW D	Taxiway	515	23,608	AC	1/1/2011
SPG	TW D1	Taxiway	450	6,159	AC	1/1/2006
SPG	TW D2	Taxiway	740	29,398	AAC	7/1/2019
SPG	TW D3	Taxiway	470	3,795	AC	1/1/2011
SPG	TW D3	Taxiway	475	1,901	AC	1/1/2006
SPG	TW D5	Taxiway	150	5,816	AAC	6/1/2016
SPG	AP	Apron	4110	126,574	AC	1/1/1993
SPG	AP	Apron	4120	33,335	AAC	1/1/2002
SPG	AP	Apron	4135	42,820	AAC	1/1/2002
SPG	AP	Apron	4145	9,084	AAC	1/1/2002
SPG	AP	Apron	4150	5,101	AAC	7/1/2021
SPG	AP	Apron	4155	41,633	AAC	7/1/2021
SPG	AP	Apron	4160	37,874	AC	7/1/2020
SPG	AP	Apron	4165	36,941	AAC	7/1/2021
SPG	AP FUEL	Apron	4510	6,767	AC	1/1/2013
SPG	AP HELI	Apron	4610	21,255	AC	1/1/2006

Airport Pavement Evaluation Report

Statewide Airfield Pavement Management Program

Network ID	Branch ID	Branch Use	Section ID	Area (SF)	Surface Type	Estimate of Last Construction Date
SPG	AP MID	Apron	4405	85,370	AC	1/1/2013
SPG	AP MID	Apron	4410	15,414	AC	1/1/2013
SPG	AP NW	Apron	4310	76,197	AC	1/1/2006
SPG	AP NW	Apron	4315	35,173	AC	1/1/2011
SPG	AP NW	Apron	4320	4,732	AC	1/1/2002
SPG	AP NW	Apron	4325	14,232	AAC	1/1/2018



Chapter 4: Airfield Pavement Condition Analysis



Chapter 4 – Airfield Pavement Condition Analysis


The Pavement Condition Index (PCI) provides insight to possible causes of deterioration to help support pavement maintenance and rehabilitation planning. Distress type, severity, and extent are required in the computation of a PCI value. The PCI method of pavement condition evaluation is strictly a visual review of surface condition, also referred to as a functional evaluation. Further evaluation of pavement conditions may be necessary, such as structural evaluation, for design-and/or project-level determination of pavement rehabilitation needs.

4.1 Airfield Pavement Condition Index

4.1.1 Network-Level Analysis

The following figure, **Figure 4.1.1**, summarizes the network-level pavement condition analysis based on the most recent survey results. On a network level, approximately 60% of inspected pavements are in Good or Satisfactory condition. Presently, roughly 21% of inspected pavements are in Fair condition and the remaining 19% of inspected pavements are in Poor or worse condition.

Figure 4.1.1: Current Condition – Overall Network



4.1.2 Branch-Level Analysis

The following **Figures 4.1.2 (a)-(d)** summarize branch-level pavement conditions according to the most recent PCI assessment results.

Figure 4.1.2 (a): Current Condition Summary – Branch-Level




Figure 4.1.2 (b): Current Condition – Runway




Figure 4.1.2 (c): Current Condition – Taxiway




Figure 4.1.2 (d): Current Condition – Apron




Table 4.1.2 details the branch-level condition for each airfield pavement branch.

Table 4.1.2: Current Condition Summary – Branch-Level

Branch ID	Branch Use	Number of Sections	Branch Area (SF)	Area-Weighted Avg PCI	Condition Rating
RW 7-25	Runway	8	268,375	82	Satisfactory
RW 18-36	Runway	1	217,732	100	Good
TW A	Taxiway	6	123,682	53	Poor
TW A1	Taxiway	1	4,672	86	Good
TW A2	Taxiway	1	5,577	90	Good
TW A3	Taxiway	1	5,518	89	Good
TW A4	Taxiway	2	16,668	88	Good
TW B	Taxiway	3	112,508	59	Fair
TW B1	Taxiway	2	3,388	100	Good
TW B2	Taxiway	2	6,176	100	Good
TW B3	Taxiway	2	6,176	100	Good
TW B4	Taxiway	2	6,955	100	Good
TW C	Taxiway	3	138,374	74	Satisfactory
TW D	Taxiway	5	71,043	77	Satisfactory
TW D1	Taxiway	1	6,159	65	Fair
TW D2	Taxiway	1	29,398	86	Good
TW D3	Taxiway	2	5,696	63	Fair
TW D5	Taxiway	1	5,816	90	Good
AP	Apron	8	333,362	67	Fair
AP FUEL	Apron	1	6,767	85	Satisfactory
AP HELI	Apron	1	21,255	63	Fair
AP MID	Apron	2	100,784	89	Good
AP NW	Apron	4	130,334	75	Satisfactory

4.1.3 Section-Level Analysis

Table 4.1.3 provides each pavement section's area-weighted average PCI and the percent of distress related to load, climate, and other factors. The causes of condition deterioration help inform maintenance, repair, and rehabilitation decisions. For example, load-related distress can indicate that the pavement is reaching the end of its structural design life and the selected rehabilitation treatment should include either strengthening or reconstruction. **Figure 4.1.3** provides a technical exhibit that graphically depicts PCI values and ratings determined from this SAPMP System Update.


Pavement facilities that have been reconstructed within the past 24 months, or are anticipated for reconstruction within the next 24 months, may have been omitted from this assessment. Pavement that has received major rehabilitation will be set to a PCI of 100 for this analysis.

Table 4.1.3: Latest Pavement Condition Index Summary – Section-Level

Network ID	Branch ID	Branch Use	Section ID	Area (SF)	Surface	PCI	Condition Rating	PCI % Climate	PCI % Load	PCI % Other	Sample Units Inspected	Total Sample Units in Section
SPG	RW 7-25	Runway	6205	18,375	AAC	88	Good	100	0	0	2	5
SPG	RW 7-25	Runway	6207	22,950	AAC	79	Satisfactory	100	0	0	2	6
SPG	RW 7-25	Runway	6208	21,525	AAC	80	Satisfactory	100	0	0	2	6
SPG	RW 7-25	Runway	6210	147,650	AAC	79	Satisfactory	96	0	4	8	39
SPG	RW 7-25	Runway	6213	19,590	AC	84	Satisfactory	100	0	0	2	5
SPG	RW 7-25	Runway	6215	30,125	AAC	91	Good	100	0	0	2	8
SPG	RW 7-25	Runway	6220	2,875	AAC	100	Good	0	0	0	0	0
SPG	RW 7-25	Runway	6225	5,285	AAC	100	Good	0	0	0	0	0
SPG	RW 18-36	Runway	6105	217,732	AAC	100	Good	0	0	0	0	0
SPG	TW A	Taxiway	103	17,162	AC	50	Poor	100	0	0	1	4
SPG	TW A	Taxiway	105	15,000	AAC	38	Very Poor	89	0	11	1	4
SPG	TW A	Taxiway	110	21,000	AAC	44	Poor	90	0	10	2	5
SPG	TW A	Taxiway	115	65,457	AAC	57	Fair	100	0	0	3	16
SPG	TW A	Taxiway	125	1,540	AAC	100	Good	0	0	0	0	0
SPG	TW A	Taxiway	130	3,523	AAC	100	Good	0	0	0	0	0
SPG	TW A1	Taxiway	120	4,672	AC	86	Good	100	0	0	1	1
SPG	TW A2	Taxiway	410	5,577	AC	90	Good	100	0	0	1	1
SPG	TW A3	Taxiway	310	5,518	AC	89	Good	100	0	0	1	1
SPG	TW A4	Taxiway	610	5,518	AC	89	Good	100	0	0	1	1
SPG	TW A4	Taxiway	620	11,150	AC	87	Good	100	0	0	1	3
SPG	TW B	Taxiway	205	87,871	AAC	60	Fair	100	0	0	3	21
SPG	TW B	Taxiway	210	18,217	AAC	48	Poor	100	0	0	1	4
SPG	TW B	Taxiway	215	6,420	AC	75	Satisfactory	100	0	0	1	1
SPG	TW B1	Taxiway	250	1,246	AAC	100	Good	0	0	0	0	0
SPG	TW B1	Taxiway	255	2,142	AAC	100	Good	0	0	0	0	0
SPG	TW B2	Taxiway	260	3,445	AC	100	Good	0	0	0	0	0
SPG	TW B2	Taxiway	265	2,731	AAC	100	Good	0	0	0	0	0
SPG	TW B3	Taxiway	270	3,445	AC	100	Good	0	0	0	0	0
SPG	TW B3	Taxiway	275	2,731	AAC	100	Good	0	0	0	0	0
SPG	TW B4	Taxiway	280	4,813	AC	100	Good	0	0	0	0	0
SPG	TW B4	Taxiway	285	2,142	AAC	100	Good	0	0	0	0	0
SPG	TW C	Taxiway	305	75,170	AC	94	Good	100	0	0	3	17
SPG	TW C	Taxiway	307	29,730	AAC	50	Poor	79	0	21	1	7
SPG	TW C	Taxiway	308	33,474	AAC	51	Poor	89	0	11	1	7
SPG	TW D	Taxiway	155	8,835	AAC	100	Good	0	0	0	0	0
SPG	TW D	Taxiway	157	3,327	AAC	100	Good	0	0	0	0	0
SPG	TW D	Taxiway	160	1,353	AAC	100	Good	0	0	0	0	0
SPG	TW D	Taxiway	510	33,920	AC	64	Fair	100	0	0	1	7
SPG	TW D	Taxiway	515	23,608	AC	82	Satisfactory	100	0	0	1	5
SPG	TW D1	Taxiway	450	6,159	AC	65	Fair	79	0	21	1	1
SPG	TW D2	Taxiway	740	29,398	AAC	86	Good	100	0	0	1	6
SPG	TW D3	Taxiway	470	3,795	AC	61	Fair	95	0	5	1	1
SPG	TW D3	Taxiway	475	1,901	AC	68	Fair	100	0	0	1	1

Network ID	Branch ID	Branch Use	Section ID	Area (SF)	Surface	PCI	Condition Rating	PCI % Climate	PCI % Load	PCI % Other	Sample Units Inspected	Total Sample Units in Section
SPG	TW D5	Taxiway	150	5,816	AAC	90	Good	100	0	0	1	1
SPG	AP	Apron	4110	126,574	AC	42	Poor	97	0	3	3	23
SPG	AP	Apron	4120	33,335	AAC	50	Poor	90	0	10	1	6
SPG	AP	Apron	4135	42,820	AAC	64	Fair	100	0	0	1	10
SPG	AP	Apron	4145	9,084	AAC	51	Poor	88	0	12	1	2
SPG	AP	Apron	4150	5,101	AAC	100	Good	0	0	0	0	0
SPG	AP	Apron	4155	41,633	AAC	100	Good	0	0	0	0	0
SPG	AP	Apron	4160	37,874	AC	100	Good	0	0	0	0	0
SPG	AP	Apron	4165	36,941	AAC	100	Good	0	0	0	0	0
SPG	AP FUEL	Apron	4510	6,767	AC	85	Satisfactory	100	0	0	1	2
SPG	AP HELI	Apron	4610	21,255	AC	63	Fair	84	0	16	1	5
SPG	AP MID	Apron	4405	85,370	AC	90	Good	76	0	24	3	18
SPG	AP MID	Apron	4410	15,414	AC	85	Satisfactory	89	0	11	1	4
SPG	AP NW	Apron	4310	76,197	AC	68	Fair	91	0	9	3	16
SPG	AP NW	Apron	4315	35,173	AC	83	Satisfactory	100	0	0	1	8
SPG	AP NW	Apron	4320	4,732	AC	73	Satisfactory	90	0	10	1	1
SPG	AP NW	Apron	4325	14,232	AAC	90	Good	100	0	0	1	3

* Zero (0) Sample Units Inspected signifies that the pavement section was not inspected during this SAPMP System Update due to recent construction projects. These sections correlate with the gray sections on the Network Definition Exhibit.



4.2 Summary of Pavement Condition Evaluation Results

4.2.1 Network-Level Observations

The PCI assessment for Albert Whitted Airport (SPG) was performed in April 2022. The overall area-weighted average PCI value of the network was 77, representing a condition rating of Satisfactory. A large portion of the airfield pavement was not inspected due to recent construction in 2021 and 2022. These areas include Runway 18-36 and the Taxiway B connectors as well as portions of the Apron.

Based on the FAA 5010 Report as of 10/27/2022, the Airport has reported 93,812 operations for 12 months ending 12/14/2017.

4.2.2 Branch-Level Observations


The following branch-level observations are a summary of select pavement facilities identified during the PCI assessment, including a discussion of general conditions and branch characteristics. The summary may not include all branches and/or sections within the Airport's airfield pavement network. Representative distress photographs of airfield pavements are presented in **Appendix D**. "Vicinity" photos refer to the approximate boundaries of an inspected sample unit within the section and provide an overview of the section condition but are not focused on a specific distress. The Re-inspection Report found in **Appendix E** provides listings of each sample unit and distress.

Runways

RW 7-25

Branch ID	Branch Use	Number of Sections	Branch Area (SF)	Branch Area-Weighted Avg PCI	Branch Condition Rating
RW 7-25	RUNWAY	8	268,375	82	Satisfactory

The following bar graph shows proportional distribution (as % of area within branch) of condition categories among sections within the branch. Given the individual section data shown in the subsequent table, the distribution is as follows: 21% Good (86-100 PCI), 79% Satisfactory (71-85 PCI).



Section ID	Surface Type	Section Area (SF)	PCI	Condition Rating
6205	AAC	18,375	88	Good
6207	AAC	22,950	79	Satisfactory
6208	AAC	21,525	80	Satisfactory
6210	AAC	147,650	79	Satisfactory
6213	AC	19,590	84	Satisfactory


Section ID	Surface Type	Section Area (SF)	PCI	Condition Rating
6215	AAC	30,125	91	Good
6220	AAC	2,875	100	Good
6225	AAC	5,285	100	Good

RW 7-25 consists of 8 flexible pavement sections, totaling 268,375 sf. The last major construction dates range from 2016 to 2022, resulting in an area-weighted average age at inspection of 6 years old. Overall, RW 7-25 is in Satisfactory condition with an area-weighted average PCI of 82.

RW 18-36

Branch ID	Branch Use	Number of Sections	Branch Area (SF)	Branch Area-Weighted Avg PCI	Branch Condition Rating
RW 18-36	RUNWAY	1	217,732	100	Good

The following bar graph shows proportional distribution (as % of area within branch) of condition categories among sections within the branch. Given the individual section data shown in the subsequent table, the distribution is as follows: 100% Good (86-100 PCI).



Section ID	Surface Type	Section Area (SF)	PCI	Condition Rating
6105	AAC	217,732	100	Good

RW 18-36 consists of 1 flexible pavement section, totaling 217,732 sf. The last major construction date for the branch was 2022. Overall, RW 18-36 is in Good condition with an area-weighted average PCI of 100.

Taxiways

TW A

Branch ID	Branch Use	Number of Sections	Branch Area (SF)	Branch Area-Weighted Avg PCI	Branch Condition Rating
TW A	TAXIWAY	6	123,682	53	Poor

The following bar graph shows proportional distribution (as % of area within branch) of condition categories among sections within the branch. Given the individual section data shown in the subsequent table, the distribution is as follows: 4% Good (86-100 PCI), 53% Fair (56-70 PCI), 31% Poor (41-55 PCI), 12% Very Poor (26-40 PCI).




Section ID	Surface Type	Section Area (SF)	PCI	Condition Rating
103	AC	17,162	50	Poor
105	AAC	15,000	38	Very Poor
110	AAC	21,000	44	Poor
115	AAC	65,457	57	Fair
125	AAC	1,540	100	Good
130	AAC	3,523	100	Good

TW A consists of 6 flexible pavement sections, totaling 123,682 sf. The last major construction dates range from 1987 to 2022, resulting in an area-weighted average age at inspection of 33 years old. Overall, TW A is in Poor condition with an area-weighted average PCI of 53.

TW B

Branch ID	Branch Use	Number of Sections	Branch Area (SF)	Branch Area-Weighted Avg PCI	Branch Condition Rating
TW B	TAXIWAY	3	112,508	59	Fair

The following bar graph shows proportional distribution (as % of area within branch) of condition categories among sections within the branch. Given the individual section data shown in the subsequent table, the distribution is as follows: 6% Satisfactory (71-85 PCI), 78% Fair (56-70 PCI), 16% Poor (41-55 PCI).




Section ID	Surface Type	Section Area (SF)	PCI	Condition Rating
205	AAC	87,871	60	Fair
210	AAC	18,217	48	Poor
215	AC	6,420	75	Satisfactory

TW B consists of 3 flexible pavement sections, totaling 112,508 sf. The last major construction dates range from 1988 to 2016, resulting in an area-weighted average age at inspection of 33 years old. Overall, TW B is in Fair condition with an area-weighted average PCI of 59.

TW C

Branch ID	Branch Use	Number of Sections	Branch Area (SF)	Branch Area-Weighted Avg PCI	Branch Condition Rating
TW C	TAXIWAY	3	138,374	74	Satisfactory

The following bar graph shows proportional distribution (as % of area within branch) of condition categories among sections within the branch. Given the individual section data shown in the subsequent table, the distribution is as follows: 54% Good (86-100 PCI), 46% Poor (41-55 PCI).




Section ID	Surface Type	Section Area (SF)	PCI	Condition Rating
305	AC	75,170	94	Good
307	AAC	29,730	50	Poor
308	AAC	33,474	51	Poor

TW C consists of 3 flexible pavement sections, totaling 138,374 sf. The last major construction dates range from 1991 to 2018, resulting in an area-weighted average age at inspection of 16 years old. Overall, TW C is in Satisfactory condition with an area-weighted average PCI of 74.

TW D

Branch ID	Branch Use	Number of Sections	Branch Area (SF)	Branch Area-Weighted Avg PCI	Branch Condition Rating
TW D	TAXIWAY	5	71,043	77	Satisfactory

The following bar graph shows proportional distribution (as % of area within branch) of condition categories among sections within the branch. Given the individual section data shown in the subsequent table, the distribution is as follows: 19% Good (86-100 PCI), 33% Satisfactory (71-85 PCI), 48% Fair (56-70 PCI).



Section ID	Surface Type	Section Area (SF)	PCI	Condition Rating
155	AAC	8,835	100	Good
157	AAC	3,327	100	Good
160	AAC	1,353	100	Good

Section ID	Surface Type	Section Area (SF)	PCI	Condition Rating
510	AC	33,920	64	Fair
515	AC	23,608	82	Satisfactory


TW D consists of 5 flexible pavement sections, totaling 71,043 sf. The last major construction dates range from 2002 to 2022, resulting in an area-weighted average age at inspection of 13 years old. Overall, TW D is in Satisfactory condition with an area-weighted average PCI of 77.

Aprons

AP

Branch ID	Branch Use	Number of Sections	Branch Area (SF)	Branch Area-Weighted Avg PCI	Branch Condition Rating
AP	APRON	8	333,362	67	Fair

The following bar graph shows proportional distribution (as % of area within branch) of condition categories among sections within the branch. Given the individual section data shown in the subsequent table, the distribution is as follows: 36% Good (86-100 PCI), 13% Fair (56-70 PCI), 51% Poor (41-55 PCI).




Section ID	Surface Type	Section Area (SF)	PCI	Condition Rating
4110	AC	126,574	42	Poor
4120	AAC	33,335	50	Poor
4135	AAC	42,820	64	Fair
4145	AAC	9,084	51	Poor
4150	AAC	5,101	100	Good
4155	AAC	41,633	100	Good
4160	AC	37,874	100	Good
4165	AAC	36,941	100	Good

AP consists of 8 flexible pavement sections, totaling 333,362 sf. The last major construction dates range from 1993 to 2021, resulting in an area-weighted average age at inspection of 16 years old. Overall, AP is in Fair condition with an area-weighted average PCI of 67.

AP NW

Branch ID	Branch Use	Number of Sections	Branch Area (SF)	Branch Area-Weighted Avg PCI	Branch Condition Rating
AP NW	APRON	4	130,334	75	Satisfactory

The following bar graph shows proportional distribution (as % of area within branch) of condition categories among sections within the branch. Given the individual section data shown in the subsequent table, the distribution is as follows: 11% Good (86-100 PCI), 31% Satisfactory (71-85 PCI), 58% Fair (56-70 PCI).



Section ID	Surface Type	Section Area (SF)	PCI	Condition Rating
4310	AC	76,197	68	Fair
4315	AC	35,173	83	Satisfactory
4320	AC	4,732	73	Satisfactory
4325	AAC	14,232	90	Good

AP NW consists of 4 flexible pavement sections, totaling 130,334 sf. The last major construction dates range from 2002 to 2018, resulting in an area-weighted average age at inspection of 14 years old. Overall, AP NW is in Satisfactory condition with an area-weighted average PCI of 75.



Chapter 5: SAPMP Customization



Chapter 5 – SAPMP Customization

Once the PAVER™ database is populated with inventory and condition data (including PCI and rank), it is further customized with key elements such as network-level attributes, performance models, critical PCI, maintenance policies, and unit costs that are specific to the FDOT SAPMP. Each of these factors play a role in the development of rehabilitation strategies as they help to identify maintenance and rehabilitation needs for long-term management.

The FDOT SAPMP is organized to provide airports with planning-level data and does not intend to preclude the responsible engineer from performing the appropriate level of investigation and analysis in determining the appropriate design details of a pavement rehabilitation. It would not be advisable to solely base design-level rehabilitation without the appropriate level of investigation and determination of pavement deterioration beyond that of a visual functional condition assessment.

5.1 Network-Level Customization

The network-level attribute fields used in the FDOT SAPMP PAVER™ database consist of the Network, Airport Classification, District, FAA ADO Area, Inspection Phase, and Continuing Florida Aviation System Planning Process (CFASPP) Center. Each of these elements are briefly defined below.

- » The “Network” field identifies the airport being analyzed;
- » The “Airport Classification” field classifies the Airport according to the type and volume of aircraft traffic;
 - “GA” for General Aviation, community airports
 - “RL” for Regional Relievers
 - “PR” for Primary/Commercial airports
- » The “District” field identifies the FDOT District to which the Airport belongs;
- » The “FAA ADO Area” is an area used by the Orlando ADO to assign airports within those areas to the responsible FAA ADO personnel (planners, engineers, and environmentalists);
- » The “Inspection Phase” denotes which phase of the SAPMP the Airport is surveyed (Phase 1 or Phase 2); and
- » The “CFASPP Center” identifies which Region or Metropolitan Area of the Continuing Florida Aviation Systems Planning Process an Airport falls within.

5.2 Pavement Condition Forecasts

Pavement performance models, alternatively known as forecast models, prediction curves, or family curves, are developed from past and current distress data, as well as age data. These prediction curves are used to develop forecasts of PCI values that then help determine optimum timing for pavement maintenance and rehabilitation.

5.2.1 Forecasting PCI Considerations

Performance models will continue to be refined as the FDOT updates the SAPMP with subsequent PCI surveys. With the refinement of additional PCI and age data points, the forecasting of pavement conditions will continue to better reflect the performance trends of airfield pavements in the FAS. As a reminder, forecasting of pavement condition for the Airport is intended for planning purposes only. **The estimation of forecasted PCI values gives no assurance of future pavement conditions as PCI values represent an engineering estimation to be used as a planning tool. Forecasted PCI data should not be the sole metric for determining the year in which a project should be planned. Design-level planning should be undertaken by the responsible engineer prior to the development of airfield design plans.** Design-level recommendations for pavement rehabilitation and/or reconstruction will require the appropriate application of the procedures defined in the FAA AC 150/5320-6F.


5.2.2 Performance Models

To develop pavement performance models, data for each section is combined into “groups” or “families” according to pavement type, traffic, and functional use. For the FDOT SAPMP, the models were defined for both PCC- and AC-surfaced pavements and further divided according to functional use. Based on average deterioration rates for different pavement types, each pavement section is assigned to a specific deterioration family to forecast the condition over a 10-year period.

5.2.3 Branch-Level Pavement Condition Forecast

Figure 5.2.3 depicts the branch-level pavement condition forecast for each branch use (Runway, Taxiway, Taxilane, and/or Apron) as well as the overall network. The condition forecasts are for a 10-year duration, starting in 2023 through 2032.

Figure 5.2.3: Forecasted Branch-Level Pavement Performance



5.2.4 Section-Level Pavement Condition Forecast

Table 5.2.4 provides section-level details for PCI forecasts. Pavement condition forecasts should be used for planning purposes only, as actual condition of sections is subject to the sensitivities in changes of traffic and maintenance frequency.

Table 5.2.4: Forecasted PCI Values 2023-2032 – Section-Level


Network ID	Branch ID	Section ID	Current PCI	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032
SPG	RW 7-25	6205	88	86	84	82	81	79	77	75	74	72	70
SPG	RW 7-25	6207	79	77	75	73	72	70	68	66	65	63	61
SPG	RW 7-25	6208	80	78	76	74	73	71	69	67	66	64	62
SPG	RW 7-25	6210	79	77	75	73	72	70	68	66	65	63	61
SPG	RW 7-25	6213	84	82	80	79	77	76	75	74	73	72	71
SPG	RW 7-25	6215	91	89	87	85	84	82	80	78	77	75	73
SPG	RW 7-25	6220	100	98	96	94	93	91	89	87	86	84	82
SPG	RW 7-25	6225	100	98	96	94	93	91	89	87	86	84	82
SPG	RW 18-36	6105	100	98	96	94	93	91	89	87	86	84	82
SPG	TW A	103	50	49	49	48	47	46	45	44	44	43	41
SPG	TW A	105	38	36	34	32	30	28	26	24	22	20	18
SPG	TW A	110	44	42	41	39	37	35	33	31	29	27	25
SPG	TW A	115	57	56	55	55	54	53	52	52	51	50	49
SPG	TW A	125	100	97	95	92	90	88	86	84	82	80	79
SPG	TW A	130	100	97	95	92	90	88	86	84	82	80	79
SPG	TW A1	120	86	84	82	80	79	77	76	75	74	72	71
SPG	TW A2	410	90	88	86	84	82	81	79	78	76	75	74
SPG	TW A3	310	89	87	85	83	81	80	78	77	76	74	73
SPG	TW A4	610	89	87	85	83	81	80	78	77	76	74	73
SPG	TW A4	620	87	85	83	81	80	78	77	75	74	73	72
SPG	TW B	205	60	59	58	58	57	56	56	55	54	53	53
SPG	TW B	210	48	47	45	44	43	41	39	38	36	34	32
SPG	TW B	215	75	73	72	71	70	69	68	67	66	66	65
SPG	TW B1	250	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B1	255	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B2	260	100	97	95	93	90	88	87	85	83	81	80
SPG	TW B2	265	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B3	270	100	97	95	93	90	88	87	85	83	81	80
SPG	TW B3	275	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B4	280	100	97	95	93	90	88	87	85	83	81	80
SPG	TW B4	285	100	97	95	92	90	88	86	84	82	80	79
SPG	TW C	305	94	91	89	87	86	84	82	80	79	77	76
SPG	TW C	307	50	49	48	47	45	44	43	41	39	38	36
SPG	TW C	308	51	50	49	48	47	45	44	43	41	39	38
SPG	TW D	155	100	96	94	91	89	87	85	83	81	80	78
SPG	TW D	157	100	97	95	92	90	88	86	84	82	80	79
SPG	TW D	160	100	97	95	92	90	88	86	84	82	80	79
SPG	TW D	510	64	63	63	62	61	61	60	60	59	59	58
SPG	TW D	515	82	80	79	77	76	74	73	72	71	70	69

Network ID	Branch ID	Section ID	Current PCI	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032
SPG	TW D1	450	65	64	63	63	62	62	61	60	60	59	59
SPG	TW D2	740	86	84	82	80	78	77	75	74	72	71	70
SPG	TW D3	470	61	60	60	59	59	58	58	58	57	57	56
SPG	TW D3	475	68	67	66	65	65	64	63	62	62	61	61
SPG	TW D5	150	90	87	85	83	82	80	78	77	75	74	72
SPG	AP	4110	42	40	38	36	34	32	29	26	23	20	17
SPG	AP	4120	50	47	45	43	41	39	36	34	32	30	28
SPG	AP	4135	64	61	59	57	55	53	50	48	46	44	42
SPG	AP	4145	51	48	46	44	42	40	37	35	33	31	29
SPG	AP	4150	100	96	93	91	89	87	85	82	80	78	76
SPG	AP	4155	100	96	93	91	89	87	85	82	80	78	76
SPG	AP	4160	100	94	91	89	87	85	83	81	79	77	75
SPG	AP	4165	100	96	93	91	89	87	85	82	80	78	76
SPG	AP FUEL	4510	85	82	81	79	77	75	73	71	70	68	67
SPG	AP HELI	4610	63	62	61	60	59	58	57	56	56	55	54
SPG	AP MID	4405	90	87	85	83	81	79	77	76	74	72	70
SPG	AP MID	4410	85	82	81	79	77	75	73	71	70	68	67
SPG	AP NW	4310	68	66	65	64	62	61	60	59	58	58	57
SPG	AP NW	4315	83	81	79	77	75	73	72	70	68	67	66
SPG	AP NW	4320	73	71	69	68	66	65	64	63	62	60	60
SPG	AP NW	4325	90	87	85	83	81	79	76	74	72	70	68

5.3 Critical PCI Value

An important concept in pavement management is the critical PCI value, a value that prompts major rehabilitation activities. It serves as a condition threshold that helps determine a section's suitability to receive major work. As soon as a section's PCI reaches the critical PCI value, the rate of PCI loss (deterioration) is expected to increase. The critical PCI concept assumes that once a pavement section deteriorates to this critical level, it is more cost-effective to complete a major rehabilitation project rather than continuing to apply preventive maintenance or deferring major work until more costly reconstruction activities are required. **Figure 5.3 (a)** illustrates the benefit of applying lower cost preventive maintenance to extend the life of the pavement.

Figure 5.3 (a): Pavement Life and the Effect of Treatments



FAA Eligibility Thresholds: >70: Routine Maintenance 55-70: Rehabilitation Eligible <55: Reconstruction Eligible

**Figure is for conceptual purposes only – unit costs are not specific to airfield pavements.*

Critical PCI values vary and are typically based on a pavement's surface type, functional use, and importance, or priority, in daily operations. Pavement priority is generally assigned based on the branch use of a pavement section. In previous System Updates, the critical PCI value was set to 65 for all functional uses. Now, based on FAA Order 5100.38D Change 1 Airport Improvement Handbook, issued February 26, 2019, the FAA has established pavement construction based on thresholds that distinguish Rehabilitation and Reconstruction. Pavement sections between PCI Values 55 and 70 will be considered for Rehabilitation and sections less than 55 will be considered for Reconstruction at the planning-level, as shown in **Table 5.3 (a)**. The FDOT SAPMP will integrate the PCI thresholds for airfield pavement projects to maintain alignment with the FAA AIP

and/or PFC eligibility for project planning. Moving forward, the critical PCI value will be defined at 70 for the FDOT SAPMP. Critical PCI values for this SAPMP System Update are shown in **Table 5.3 (b)**.

Table 5.3 (a): AIP Handbook PCI Requirements for Airfield Pavement Projects

Airfield Pavement Project Type	PCI Requirement
Reconstruction	PCI < 55 (Poor)
Rehabilitation	PCI < 70 (Fair)
Maintenance	N/A

*Source: AIP Handbook, in reference to Runways, Taxiways, and Aprons as seen in table G-2, H-1, and I-1 respectively

Table 5.3 (b): Critical PCI Values by Branch Use

Runway	Taxiway	Apron
70	70	70

Figures 5.3 (b) and 5.3 (c) depict the decision process for major rehabilitation project identification with the assumption of available funds (Shahin). Should funding be unavailable for pavement sections in need of major rehabilitation, the Airport may elect to apply appropriate localized stopgap repair strategies. As the figures show, once major rehabilitation has been applied, the PCI of the section is reset to 100.

Figure 5.3 (b): Major Rehabilitation Planning Decision Diagram, $PCI < \text{Critical PCI}$





Figure 5.3 (c): Major Rehabilitation Planning Decision Diagram, $PCI \geq \text{Critical PCI}$



5.4 Localized Maintenance and Repair

This section discusses both localized maintenance and major rehabilitation methods and how they may be most effectively applied to extend the life of the pavement network. General maintenance and rehabilitation (M&R) methods are characterized under two (2) broad categories: localized maintenance and major rehabilitation.

Localized maintenance is best applied as a conservation measure and is applied to slow the rate of pavement deterioration. It may, however, be applied as a temporary corrective measure in isolated areas. Proactive localized maintenance, and specifically preservation, is highly recommended to the Airport. However, it is recognized that once pavements have deteriorated below a certain condition threshold (the critical PCI value), the pavement benefits from more substantial rehabilitation in lieu of localized repairs.

Major rehabilitation is recommended when a pavement section falls below the critical PCI value or if a pavement section has a significant presence of load-related distress. Major rehabilitation efforts can correct or improve structural deficiencies and/or functional deterioration for pavement sections within a network.

M&R planning combines methods of repair to address the cause of the problem rather than just treating the symptom. For example, a PCC corner break may require slab under-sealing, full-depth patching, and joint sealing. While these repair methods apply to specific distress and pavement types, they also consider the impact of Foreign Object Debris (FOD) on aircraft operations. Untidy or improperly constructed repair activities may disintegrate and potentially create FOD at or near the repair site. Therefore, maintenance activities must include quality control monitoring to ensure that repairs are conducted properly and clean-up activities are undertaken to address this potential. The current version of the FAA Advisory Circular 150/5210-24 “Airport Foreign Object Debris (FOD) Management” provides additional guidance for developing and managing an airport FOD program.

5.4.1 Localized Maintenance and Repair Approach

Localized maintenance differs from major rehabilitation in that localized maintenance is applied based on the distresses observed and not an averaged or forecasted PCI value. Treatments are selected based on the appropriate corrective measure for a given distress type and severity level. Localized maintenance can be applied either as a preventive measure or a safety (“stopgap”) measure. The two (2) types of localized maintenance are described below in further detail.

- » Localized Preventive Maintenance and Repair
 - Distress maintenance activities performed with the primary objective of slowing the rate of deterioration. These activities typically include crack sealing and patching.
- » Localized Stopgap/Safety Maintenance and Repair
 - Defined as the localized distress repair needed to keep a pavement in a safe and operational condition. These activities are typically applied to high-severity distresses or distresses impacting operations.

5.4.2 Localized Work Types

The following sections provide detailed descriptions of the maintenance policy work types identified in the Localized Maintenance Policy.

AC Crack Sealing

Crack sealing is the process of cleaning and sealing (or resealing) cracks in AC pavements. This repair is used to fill longitudinal and transverse cracks, including reflective cracks and block cracks that are wider than 1/8-inch. The purpose of this treatment is to prevent water and incompressible materials from entering cracks and causing further deterioration of the pavement structure. Accumulation of incompressible materials in cracks may lead to spalling and is a source of FOD. Crack sealing is cost-effective when used as a preventive measure. Depending on the size of the crack, routing and cleaning the crack may be necessary to remove the loose material within the crack for better adherence of the crack sealant to the crack face. Measurement of this work type is typically in linear feet.

AC Full-Depth Patching

This technique involves replacing the full thickness of the AC layer and may include replacement of the base and subbase layers. Full-depth patching is used to repair structural and material-related distresses, such as alligator cracking, corrugation, depressions, rutting, slippage cracking, and swelling in AC pavements. This repair may be limited to the top AC layer (partial-depth patch) if the base and subbase layers exhibit no signs of deterioration. Measurement of this work type is typically in square feet or square yards.

AC Partial-Depth AC Patching

This technique involves the removal of a given thickness of the surface layer using a milling machine and adding back a layer of AC pavement. This technique removes the deteriorated layer and provides a good bond for an overlay. It can correct or improve the structural capacity or functional requirement, such as skid resistance and ride quality. This repair is used for surface distresses that can occur over a large area, such as raveling, shoving, and bleeding. While mill and replace can be a major rehabilitation M&R method when applied at a large scale, its application in a localized capacity to treat specific distress types also classifies it under localized maintenance for the purpose of this study. After milling operations are completed, any cracks still present should be cleaned and sealed prior to the placement of a tack coat and AC overlay layer(s). Measurement of this work type is typically in square feet or square yards.

Grinding

Grinding is the process of removing a thin layer of the existing concrete by grinding it with a series of closely spaced, rotating saw blades. This method is used to re-profile jointed concrete pavements with poor ride quality due to faulting or warping. Grinding is also used to restore transverse drainage and to provide a textured pavement surface. The concern with this type of maintenance is that if too much material is removed, the overall structural composition of the pavement section may change, potentially reducing the overall life of the pavement. Measurement of this work type is typically in square feet or square yards.

Monitor Pavement

Monitor pavement is recommended when the distresses do not interfere with ride quality, do not have FOD potential, and do not pose an immediate safety concern.

PCC Crack Sealing

Crack sealing is the process of routing, cleaning, and sealing (or resealing) cracks in PCC pavement to prevent water from infiltrating into the pavement foundation and to stop the accumulation of incompressible materials in the cracks. Water entering cracks can weaken the subgrade, potentially leading to pumping, corner breaks, and/or shattered slabs. Accumulation of incompressible materials in cracks may lead to spalling and is a source of FOD. Routing and cleaning of the crack is often necessary to adhere the crack sealant to both sides of the crack. Measurement of this work type is typically in linear feet.

PCC Full-Depth Patching

This type of M&R activity involves full-depth replacement of a portion of a PCC slab. This repair is used for medium- and high-severity corner breaks, medium-severity durability cracking, medium-severity blowups and buckling, and high-severity large patches. This repair requires restoring load transfer if near a joint or crack. Measurement of this work type is typically in square feet or square yards.

PCC Joint Seal

Joint sealing is the process of cleaning and sealing (or resealing) joints in PCC pavement to prevent water from infiltrating into the pavement foundation and to stop the accumulation of incompressible materials in the joints. Water entering joints can weaken the subgrade, potentially leading to pumping, corner breaks, and/or shattered slabs. Accumulation of incompressible materials in joints leads to spalling of the concrete and is a source of FOD. In some cases, it may be necessary to re-saw the pavement joints to remove old material prior to resealing. Measurement of this work type is typically in linear feet.

PCC Partial-Depth Patching

Partial-depth patching involves removing shallow, localized areas of deteriorated or spalled PCC pavement and replacing them with a suitable patch-like cement concrete or epoxy concrete. This method is used to repair distresses that are confined to the top few inches of the slab, such as joint and corner spalling. This repair would require restoring the joint sealant if near a joint. Measurement of this work type is typically in square feet or square yards.

PCC Slab Replacement

This type of M&R activity involves full-depth replacement of an entire PCC slab. This repair is used to repair high-severity blowups and buckling, high-severity durability cracking, medium- and high-severity shattered slabs, and medium- and high-severity ASR. This repair requires restoring load transfer with adjacent slabs through dowels or similar means. Measurement of this work type is typically in square feet or square yards.

Surface Seal

Application of a surface treatment provides AC-surfaced pavements with an unoxidized layer of bituminous material that can help extend the life of a pavement that is experiencing climate-related distresses such as weathering and raveling. The surface treatment can also serve as a repair that re-establishes a bond between aggregates, slowing pavement deterioration and reducing FOD potential. Measurement of this work type is typically in square feet or square yards.

5.4.3 Localized Maintenance Planning-Level Unit Costs

The activities identified here are based on research of practical pavement treatments in consideration of the FAA AC 150/5380-6C. The Localized Maintenance Policies and associated planning-level unit costs are developed in consideration of a network-level analysis.

The Localized Maintenance and Repair Policies and associated planning-level unit costs are based on a statewide consideration of pavement treatments and construction costs from both airfield pavements and the FDOT Historical Cost Information archives. Furthermore, a consideration of limited repair quantities is factored into the determination of conservative planning-level unit costs. Neither the FDOT nor the Consultant team have control over the cost of labor, materials, equipment, the Contractor's methods of determining prices, or over competitive bidding or market conditions. Opinions of probable construction costs provided herein are based on the information known to the FDOT at this time and represent only the Consultant team's judgment as a design professional familiar with the construction industry. This Report cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable construction costs.

Tables 5.4.3 (a) and (b) display the cost by maintenance activity for AC and PCC pavement types, respectively. Because the localized maintenance activities identified for both preventive and stopgap work types are based on a statewide network approach, project-specific evaluations and maintenance quantities should be developed prior to construction.

Table 5.4.3 (a): Localized M&R Planning-Level Unit Costs – Asphalt Concrete

Localized Work Type	Reliever Costs	Work Type Unit
AC Crack Sealing	\$ 4.00	LF
AC Full-Depth Patching	\$ 11.50	SF
AC Partial-Depth Patching	\$ 4.75	SF
Surface Seal	\$ 0.75	SF

Table 5.4.3 (b): Localized M&R Planning-Level Unit Costs – Portland Cement Concrete

Localized Work Type	Reliever Costs	Work Type Unit
Grinding	\$ 2.00	SF
PCC Crack Sealing	\$ 7.00	LF
PCC Joint Seal	\$ 4.25	LF
PCC Full-Depth Patching	\$ 65.00	SF
PCC Partial-Depth Patching	\$ 169.00	SF
PCC Slab Replacement	\$ 51.50	SF

* PCC Partial-Depth Patching considers high-early-strength and high-performing repair material.

5.4.4 Localized Maintenance and Repair Policy

Table 5.4.4 and **Table 5.4.5** depicts the Localized Preventive Maintenance Policy and the Localized Stopgap Maintenance Policy for AC and PCC pavements. The resulting Localized Maintenance recommendations for this program are identified based on this policy.

Table 5.4.4: AC Pavement Localized Preventive & Stopgap Maintenance & Repair Policy

Distress	Severity	Description	AC Preventive Work Type	AC Stopgap Work Type
41	Low	Alligator Cracking	Monitor Pavement	Monitor Pavement
41	Medium	Alligator Cracking	AC Full Depth Patching	AC Full Depth Patching
41	High	Alligator Cracking	AC Full Depth Patching	AC Full Depth Patching
42	N/A	Bleeding	Monitor Pavement	Monitor Pavement
43	Low	Block Cracking	Monitor Pavement	Monitor Pavement
43	Medium	Block Cracking	AC Crack Sealing	Monitor Pavement
43	High	Block Cracking	AC Crack Sealing	AC Crack Sealing
44	Low	Corrugation	Monitor Pavement	Monitor Pavement
44	Medium	Corrugation	AC Full Depth Patching	Monitor Pavement
44	High	Corrugation	AC Full Depth Patching	AC Full Depth Patching
45	Low	Depression	Monitor Pavement	Monitor Pavement
45	Medium	Depression	AC Full Depth Patching	Monitor Pavement
45	High	Depression	AC Full Depth Patching	AC Full Depth Patching
46	N/A	Jet Blast	Monitor Pavement	Monitor Pavement
47	Low	Jt. Reflective Cracking	Monitor Pavement	Monitor Pavement
47	Medium	Jt. Reflective Cracking	AC Crack Sealing	Monitor Pavement
47	High	Jt. Reflective Cracking	AC Full Depth Patching	AC Full Depth Patching
48	Low	L&T Cracking	Monitor Pavement	Monitor Pavement
48	Medium	L&T Cracking	AC Crack Sealing	Monitor Pavement
48	High	L&T Cracking	AC Full Depth Patching	AC Full Depth Patching
49	N/A	Oil Spillage	Monitor Pavement	Monitor Pavement
50	Low	Patching	Monitor Pavement	Monitor Pavement
50	Medium	Patching	AC Full Depth Patching	Monitor Pavement
50	High	Patching	AC Full Depth Patching	AC Full Depth Patching
51	N/A	Polished Aggregate	Monitor Pavement	Monitor Pavement
52	Low	Raveling	Surface Seal	Monitor Pavement
52	Medium	Raveling	Surface Seal	Monitor Pavement
52	High	Raveling	AC Partial Depth Patching	AC Partial Depth Patching
53	Low	Rutting	Monitor Pavement	Monitor Pavement
53	Medium	Rutting	AC Full Depth Patching	Monitor Pavement
53	High	Rutting	AC Full Depth Patching	AC Full Depth Patching
54	Low	Shoving	Monitor Pavement	Monitor Pavement
54	Medium	Shoving	AC Partial Depth Patching	Monitor Pavement
54	High	Shoving	AC Full Depth Patching	AC Full Depth Patching
55	N/A	Slippage Cracking	AC Full Depth Patching	AC Full Depth Patching
56	Low	Swelling	Monitor Pavement	Monitor Pavement
56	Medium	Swelling	AC Full Depth Patching	Monitor Pavement
56	High	Swelling	AC Full Depth Patching	AC Full Depth Patching

Distress	Severity	Description	AC Preventive Work Type	AC Stopgap Work Type
57	Low	Weathering	Monitor Pavement	Monitor Pavement
57	Medium	Weathering	Surface Seal	Monitor Pavement
57	High	Weathering	AC Partial Depth Patching	Surface Seal

Table 5.4.5: PCC Pavement Localized Preventive & Stopgap Maintenance & Repair Policy

Distress	Severity	Description	PCC Preventive Work Type	PCC Stopgap Work Type
61	Low	Blow-up	PCC Full Depth Patching	Monitor Pavement
61	Medium	Blow-up	PCC Full Depth Patching	PCC Full Depth Patching
61	High	Blow-up	PCC Slab Replacement	PCC Slab Replacement
62	Low	Corner Break	Monitor Pavement	Monitor Pavement
62	Medium	Corner Break	PCC Full Depth Patching	PCC Full Depth Patching
62	High	Corner Break	PCC Full Depth Patching	PCC Full Depth Patching
63	Low	Linear Cracking	Monitor Pavement	Monitor Pavement
63	Medium	Linear Cracking	PCC Crack Sealing	PCC Crack Sealing
63	High	Linear Cracking	PCC Full Depth Patching	PCC Crack Sealing
64	Low	Durability Cracking	Monitor Pavement	Monitor Pavement
64	Medium	Durability Cracking	PCC Full Depth Patching	PCC Full Depth Patching
64	High	Durability Cracking	PCC Slab Replacement	PCC Slab Replacement
65	Low	Jt. Seal Damage	PCC Joint Seal	Monitor Pavement
65	Medium	Jt. Seal Damage	PCC Joint Seal	Monitor Pavement
65	High	Jt. Seal Damage	PCC Joint Seal	PCC Joint Seal
66	Low	Small Patch	Monitor Pavement	Monitor Pavement
66	Medium	Small Patch	PCC Partial Depth Patching	Monitor Pavement
66	High	Small Patch	PCC Partial Depth Patching	PCC Partial Depth Patching
67	Low	Large Patch	Monitor Pavement	Monitor Pavement
67	Medium	Large Patch	PCC Full Depth Patching	Monitor Pavement
67	High	Large Patch	PCC Full Depth Patching	PCC Full Depth Patching
68	N/A	Popouts	Monitor Pavement	Monitor Pavement
69	N/A	Pumping	Monitor Pavement	Monitor Pavement
70	Low	Scaling	Monitor Pavement	Monitor Pavement
70	Medium	Scaling	PCC Slab Replacement	Monitor Pavement
70	High	Scaling	PCC Slab Replacement	PCC Slab Replacement
71	Low	Faulting	Monitor Pavement	Monitor Pavement
71	Medium	Faulting	Grinding	Monitor Pavement
71	High	Faulting	PCC Slab Replacement	PCC Slab Replacement
72	Low	Shattered Slab	PCC Crack Sealing	Monitor Pavement
72	Medium	Shattered Slab	PCC Slab Replacement	PCC Crack Sealing
72	High	Shattered Slab	PCC Slab Replacement	PCC Slab Replacement
73	N/A	Shrinkage Cracking	Monitor Pavement	Monitor Pavement

Distress	Severity	Description	PCC Preventive Work Type	PCC Stopgap Work Type
74	Low	Joint Spall	Monitor Pavement	Monitor Pavement
74	Medium	Joint Spall	PCC Partial Depth Patching	PCC Partial Depth Patching
74	High	Joint Spall	PCC Partial Depth Patching	PCC Partial Depth Patching
75	Low	Corner Spall	Monitor Pavement	Monitor Pavement
75	Medium	Corner Spall	PCC Partial Depth Patching	PCC Partial Depth Patching
75	High	Corner Spall	PCC Partial Depth Patching	PCC Partial Depth Patching
76	Low	ASR	Monitor Pavement	Monitor Pavement
76	Medium	ASR	PCC Slab Replacement	PCC Slab Replacement
76	High	ASR	PCC Slab Replacement	PCC Slab Replacement

5.5 Major Rehabilitation

Major rehabilitation is recommended to correct or improve structural deficiencies and/or functional deterioration. Often, when pavements are subject to significant changes in the aircraft fleet mix (frequency and type), major rehabilitation is required to provide a pavement section that can meet the structural demands of traffic loading. Major rehabilitation is generally described as a pavement construction that removes and replaces the pavement surface, thus resetting the PCI value to 100 and the pavement age to zero. Typical policies include full- and partial-depth reconstruction and mill and overlay.

5.5.1 Major Rehabilitation Pavement Section Development

Once the timing of the major rehabilitation activity is determined based on the PCI value, existing as-built record documentation is used to determine typical rehabilitation processes and pavement sections. Refinement of the pavement section layers is performed in consideration of the FAA AC 150/5320-6F. It should be noted that no subsurface geotechnical investigation, American Land Title Association (ALTA)/American Congress on Surveying and Mapping (ACSM) Survey, topographic survey, utilities survey, environmental, or site-specific air traffic study(s) have been utilized in the development of the design criteria. No warranty or assurance is implied in this document for final design nor construction for any airfield pavements discussed within this Report.

Major rehabilitation is divided into two (2) policy categories as part of this System Update: Full-Depth Reconstruction (Reconstruction) and Intermediate Major Rehabilitation (Rehabilitation). Based on the pavement type, the general categories are defined as AC Reconstruction and AC Rehabilitation for AC, AAC, and APC pavement types, and PCC Reconstruction and PCC Rehabilitation for PCC pavement types. The pavement sections are based on the average Reliever Airport Type requirements; no pavement design has been performed in accordance with the FAA AC 150/5320-6F for the determined conceptual sections. **Table 5.5.1** provide details on the conceptual pavement sections developed for this study.

Table 5.5.1: Conceptual Pavement Sections for Major Rehabilitation

Rehabilitation Type	Reliever Pavement Section
AC Reconstruction	
<i>Full-depth asphalt pavement section reconstruction. Removal of existing pavement section and construction of a new section.</i> PCI <55	Pavement Removal
	Unclassified Excavation
	Subgrade Stabilization (12")
	Limerock Base Course (8")
	Prime Coat
	Tack Coat
	P-401 Surface Course (4")
	<i>Excludes any paved shoulder features</i>
AC Rehabilitation	
<i>Combination of asphalt pavement milling and replacement overlay with 15% of the areas subject to full-depth reconstruction.</i> PCI = 55 to 70	15% AC Reconstruction
	Mill and Overlay
	AC Milling (3")
	Tack Coat
	P-401 Surface Course (3")
	<i>Excludes any paved shoulder features</i>
PCC Reconstruction	
<i>Full-depth rigid pavement section reconstruction.</i> PCI < 55	Pavement Removal
	Unclassified Excavation
	Subgrade Stabilization (12")
	Limerock Base Course (6")
	P-501 PCC Pavement (14")
	PCC Joint Seal
PCC Rehabilitation	
<i>Rehabilitation of PCC pavement with a combination of crack sealing, joint seal replacement, limited patching, and replacement of 15% of slab panels.</i> PCI = 55 to 70	15% Slab Replacement
	Joint and Crack Seal
	Limited Patching

The identification of rehabilitation needs and conceptual pavement sections have been determined at the planning level. Design-level investigation is recommended prior to developing construction-level design documents and budgets. This type of construction typically warrants consideration for non-pavement efforts that may include drainage, turfing, electrical lighting, pavement marking, construction contingency, mobilization costs, and project soft costs.

Reconstruction (AC or PCC)

Reconstruction is the removal and replacement of the existing AC or PCC pavement and base layer and includes preparation of the existing subgrade material. This technique is utilized when the pavement is badly deteriorated or a structural improvement is required. Reconstruction is used when the pavements are structurally deficient and an overlay is not possible due to adjacent pavement grades.

AC Rehabilitation

AC Rehabilitation, for the purposes of this SAPMP, is a removal of all or a portion of the asphalt surface through milling and replacing the milled depth with an overlay of asphalt. This rehabilitation activity is typically applied to pavement that does not require a structural improvement and does not display an extensive amount of load-related distresses. However, this work type conservatively accounts for 15% of the planned area to receive a full-depth replacement of the pavement structure. This is meant to capture any deficiencies that may not be apparent from a visual evaluation of the surface of the pavement. This work type occurs on pavement sections with a PCI value between 55 and 70. As a general rule of thumb, intermediate rehabilitation activities have a shorter pavement life compared to a full-depth reconstruction, but AC Rehabilitation will still reset the pavement to a PCI of 100.

PCC Rehabilitation

PCC Rehabilitation, for the purposes of this SAPMP, is a planning-level estimate of several concurrent PCC maintenance activities intended to raise the PCI above Critical without reconstructing the entire area. This work type accounts for the replacement of 15% of the slabs as well as a PCC patching, crack sealing, and joint sealing for areas outside of the panel replacement. This work type occurs on pavement sections with a PCI value between 55 and 70.


5.5.2 Major Rehabilitation Planning-Level Unit Costs

Planning-level opinions of probable construction cost developed for this System Update are based on archived bid tabulations and records from airfield pavement projects provided by participating airports. A review of cost trends and cost factors have been incorporated to assist airports in planning for project budgets.


Neither the FDOT nor the Consultant team have control over the cost of labor, materials, equipment, Contractor's methods of determining prices, or over competitive bidding or market conditions. Opinions of probable construction costs provided herein are based on the information known to the FDOT at this time and represent only the Consultant team's judgment as a design professional familiar with the construction industry. This Report cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable construction costs. **Table 5.5.2** depicts the associated work type planning-level unit costs for Major Rehabilitation for each pavement type.

Table 5.5.2: RL Major Rehabilitation Planning-Level Unit Cost by Pavement Type

Rehabilitation Type	PCI Range	Asphalt Concrete Cost per SF	Portland Cement Concrete Cost Per SF
Rehabilitation	55 to 70	\$10.50	\$22.50
Reconstruction	0 to 55	\$18.50	\$45.00



Chapter 6: M&R Planning and Budget Scenario Analysis



Chapter 6 – M&R Planning and Budget Scenario Analysis

6.1 Localized Maintenance and Repair Analysis and Recommendations

This FDOT SAPMP System Update provides a planning-level estimation of Localized Maintenance and Repair costs based on the results of the latest PCI assessment performed at the Airport. Due to the limited sample units inspected in certain pavement sections, a statistical extrapolation of distresses is used to estimate the quantities of recommended repair activities at the section level, based the policies defined in **5.4.4 Localized Maintenance and Repair Policy**. These work quantities are limited to a near-term application since they were determined directly from the PCI assessment efforts. As pavements continue to deteriorate year-to-year, quantities and/or distress severities may increase, which will affect the amount and type of localized maintenance required. This analysis can be utilized as a planning tool to assist Airport staff in determining an annual budget allocation for maintenance activities that will help maintain Airport pavements above the critical PCI value and extend the life of the pavement.

Table 6.1 (a) provides a summary of the anticipated planning-level costs for Year 1 Localized Preventive Maintenance and Localized Stopgap Maintenance. The following table depicts planning-level costs rounded up to the next 10-dollar increment.

Table 6.1 (a): Year 1 Summary of Localized Maintenance

Work Category	Cost
Preventive	\$ 13,120
Stopgap	\$ 1,780
Planning-Level Localized M&R Needs =	\$ 14,900

Localized Preventive Maintenance is typically applied to pavements that are in a condition above the critical PCI value of the pavement section. Localized Stopgap Maintenance is typically applied to pavement sections that are at or below the critical PCI value. Application of localized maintenance and repair should be coordinated with the planning of major rehabilitation efforts identified through the Major Rehabilitation analysis. Pavements with stopgap recommendations that are subject to near-term major rehabilitation efforts may remove the need to perform localized (stopgap) maintenance efforts in subsequent years.

Table 6.1 (b) summarizes the anticipated Year 1 Localized Maintenance recommendations by work type, based on the PCI assessment efforts performed as part of this SAPMP System Update. The following table depicts planning-level costs rounded up to the next 10-dollar increment.

Table 6.1 (b): Year 1 Localized Maintenance by Work Type Summary

Localized Maintenance Category	Localized Work Type	Rough Estimate of Work Quantity	Work Units	Planning Material Cost
Localized Preventive Maintenance	Surface Seal	17,461	SF	\$ 13,120
Localized Stopgap Maintenance	AC Partial-Depth Patching	73	SF	\$ 360
	AC Full-Depth Patching	123	SF	\$ 1,420

Table 6.1 (c) provides a breakdown of the anticipated planning-level costs by section for those areas exhibiting distresses that would benefit from Year 1 Localized M&R. The table shows the approximate improved “End Condition” PCI value of the section after the application of Localized M&R. This approximation is intended to depict a planning-level estimate of the effect of the localized M&R on the section-level PCI; the performance of the work does not guarantee the pavement will not deteriorate in other ways outside of the described treatment. The following table depicts planning-level costs rounded up to the next 10-dollar increment.

Table 6.1 (c): Section-Level Year 1 Localized M&R Planning Cost Summary

Network ID	Branch ID	Section ID	Area (SF)	Start PCI	End PCI	Cost
SPG	RW 7-25	6205	18,375	88	88	\$ -
SPG	RW 7-25	6207	22,950	79	79	\$ -
SPG	RW 7-25	6208	21,525	80	80	\$ -
SPG	RW 7-25	6210	147,650	79	79	\$ -
SPG	RW 7-25	6213	19,590	84	84	\$ -
SPG	RW 7-25	6215	30,125	91	91	\$ -
SPG	RW 7-25	6220	2,875	100	100	\$ -
SPG	RW 7-25	6225	5,285	100	100	\$ -
SPG	RW 18-36	6105	217,732	100	100	\$ -
SPG	TW A	103	17,162	50	54	\$ 130
SPG	TW A	105	15,000	38	39	\$ 1,420
SPG	TW A	110	21,000	44	44	\$ -
SPG	TW A	115	65,457	57	57	\$ -
SPG	TW A	125	1,540	100	100	\$ -
SPG	TW A	130	3,523	100	100	\$ -
SPG	TW A1	120	4,672	86	86	\$ -
SPG	TW A2	410	5,577	90	90	\$ -
SPG	TW A3	310	5,518	89	89	\$ -
SPG	TW A4	610	5,518	89	89	\$ -
SPG	TW A4	620	11,150	87	90	\$ 420
SPG	TW B	205	87,871	60	60	\$ -
SPG	TW B	210	18,217	48	48	\$ -
SPG	TW B	215	6,420	75	75	\$ -
SPG	TW B1	250	1,246	100	100	\$ -
SPG	TW B1	255	2,142	100	100	\$ -
SPG	TW B2	260	3,445	100	100	\$ -
SPG	TW B2	265	2,731	100	100	\$ -
SPG	TW B3	270	3,445	100	100	\$ -
SPG	TW B3	275	2,731	100	100	\$ -

Network ID	Branch ID	Section ID	Area (SF)	Start PCI	End PCI	Cost
SPG	TW B4	280	4,813	100	100	\$ -
SPG	TW B4	285	2,142	100	100	\$ -
SPG	TW C	305	75,170	94	94	\$ -
SPG	TW C	307	29,730	50	50	\$ -
SPG	TW C	308	33,474	51	51	\$ -
SPG	TW D	155	8,835	100	100	\$ -
SPG	TW D	157	3,327	100	100	\$ -
SPG	TW D	160	1,353	100	100	\$ -
SPG	TW D	510	33,920	64	64	\$ -
SPG	TW D	515	23,608	82	85	\$ 890
SPG	TW D1	450	6,159	65	65	\$ -
SPG	TW D2	740	29,398	86	86	\$ -
SPG	TW D3	470	3,795	61	61	\$ -
SPG	TW D3	475	1,901	68	68	\$ -
SPG	TW D5	150	5,816	90	90	\$ -
SPG	AP	4110	126,574	42	42	\$ 230
SPG	AP	4120	33,335	50	50	\$ -
SPG	AP	4135	42,820	64	64	\$ -
SPG	AP	4145	9,084	51	51	\$ -
SPG	AP	4150	5,101	100	100	\$ -
SPG	AP	4155	41,633	100	100	\$ -
SPG	AP	4160	37,874	100	100	\$ -
SPG	AP	4165	36,941	100	100	\$ -
SPG	AP FUEL	4510	6,767	85	90	\$ 510
SPG	AP HELI	4610	21,255	63	63	\$ -
SPG	AP MID	4405	85,370	90	93	\$ 3,210
SPG	AP MID	4410	15,414	85	89	\$ 580
SPG	AP NW	4310	76,197	68	68	\$ -
SPG	AP NW	4315	35,173	83	89	\$ 3,960
SPG	AP NW	4320	4,732	73	94	\$ 3,550
SPG	AP NW	4325	14,232	90	90	\$ -

6.2 Major Rehabilitation Needs

Major rehabilitation is identified within the FDOT SAPMP as a major construction activity that results in a substantial improvement to the pavement condition and resets the pavement section's PCI value to 100. Major rehabilitation recommendations (AC Rehabilitation, AC Reconstruction, PCC Rehabilitation, and PCC Reconstruction) should be considered as planning-level only. Additional design-level investigation in accordance with FAA Advisory Circulars is required. Recommendations identified within this planning document do not imply final design.

The objective of the Major Pavement Rehabilitation Needs analysis is to develop planning-level projects within an Airport's airfield pavement network. As depicted in **Figures 5.3 (b) and (c)** in **Chapter 5**, major rehabilitation activities are recommended when a pavement section has deteriorated below the critical PCI value, a point at which localized maintenance and repair activities may not be a cost-effective solution. In addition, major rehabilitation is also recommended when the section's PCI value is above the critical PCI value with the section

exhibiting a significant amount of load-related distresses. Identification of rehabilitation needs is done at the section-level. This, however, does not limit the Airport from further refining limits of project planning areas.

6.2.1 10-Year Unconstrained Budget Major Rehabilitation Needs

Major rehabilitation needs are identified by analyzing the Airport's pavement condition in relationship to critical PCI values, major rehabilitation policies, and unit costs, assuming there are no budget constraints. This is done over a 10-year analysis period. While this is financially impractical, it does yield the unbiased pavement needs over a 10-year time frame at the Airport given current and forecasted pavement conditions. The FDOT recognizes that airports are constrained by budgets and does not intend to convey an unrealistic approach of addressing pavement rehabilitation. Each airport has a unique set of challenges and FDOT's goals are to provide it with the data needed to formulate a practical Capital Improvement Program and identify needs in the Joint Automated Capital Improvement Program (JACIP). This includes:

- » An estimation of current pavement condition;
- » Major pavement rehabilitation needs based on condition and policies; and
- » Planning-level cost estimates for the major rehabilitation needs.

Table 6.2.1 (a) summarizes section-level major rehabilitation needs forecasted for a 10-year period. It should be noted that the following table depicts planning-level costs and has been rounded up to the nearest \$1,000 for planning purposes.


Table 6.2.1 (a): Section-Level 10-Year Major Rehabilitation Needs


Program Year	Network ID	Branch ID	Section ID	Surface	Area (SF)	PCI Before	Rehabilitation Type	Planning Cost Estimate
2023	SPG	TW A	103	AC	17,162	49	AC Reconstruction	\$ 318,000
2023	SPG	TW A	105	AAC	15,000	36	AC Reconstruction	\$ 278,000
2023	SPG	TW A	110	AAC	21,000	42	AC Reconstruction	\$ 389,000
2023	SPG	TW A	115	AAC	65,457	56	AC Rehabilitation	\$ 688,000
2023	SPG	TW B	205	AAC	87,871	59	AC Rehabilitation	\$ 923,000
2023	SPG	TW B	210	AAC	18,217	47	AC Reconstruction	\$ 338,000
2023	SPG	TW C	307	AAC	29,730	49	AC Reconstruction	\$ 550,000
2023	SPG	TW C	308	AAC	33,474	50	AC Reconstruction	\$ 620,000
2023	SPG	TW D	510	AC	33,920	63	AC Rehabilitation	\$ 357,000
2023	SPG	TW D1	450	AC	6,159	64	AC Rehabilitation	\$ 65,000
2023	SPG	TW D3	470	AC	3,795	60	AC Rehabilitation	\$ 40,000
2023	SPG	TW D3	475	AC	1,901	67	AC Rehabilitation	\$ 20,000
2023	SPG	AP	4110	AC	126,574	40	AC Reconstruction	\$ 2,342,000
2023	SPG	AP	4120	AAC	33,335	47	AC Reconstruction	\$ 617,000
2023	SPG	AP	4135	AAC	42,820	61	AC Rehabilitation	\$ 450,000
2023	SPG	AP	4145	AAC	9,084	48	AC Reconstruction	\$ 169,000
2023	SPG	AP HELI	4610	AC	21,255	62	AC Rehabilitation	\$ 224,000
2023	SPG	AP NW	4310	AC	76,197	66	AC Rehabilitation	\$ 801,000
2024	SPG	AP NW	4320	AC	4,732	69	AC Rehabilitation	\$ 53,000
2027	SPG	RW 7-25	6207	AAC	22,950	70	AC Rehabilitation	\$ 293,000

Program Year	Network ID	Branch ID	Section ID	Surface	Area (SF)	PCI Before	Rehabilitation Type	Planning Cost Estimate
2027	SPG	RW 7-25	6210	AAC	147,650	70	AC Rehabilitation	\$ 1,885,000
2027	SPG	TW B	215	AC	6,420	69	AC Rehabilitation	\$ 82,000
2028	SPG	RW 7-25	6208	AAC	21,525	69	AC Rehabilitation	\$ 289,000
2029	SPG	AP NW	4315	AC	35,173	70	AC Rehabilitation	\$ 495,000
2030	SPG	AP FUEL	4510	AC	6,767	70	AC Rehabilitation	\$ 100,000
2030	SPG	AP MID	4410	AC	15,414	70	AC Rehabilitation	\$ 228,000
2031	SPG	TW D	515	AC	23,608	70	AC Rehabilitation	\$ 367,000
2031	SPG	AP NW	4325	AAC	14,232	70	AC Rehabilitation	\$ 221,000
2032	SPG	TW D2	740	AAC	29,398	70	AC Rehabilitation	\$ 479,000

Figure 6.2.1 (a) summarizes the section-level major rehabilitation needs for a 10-year period between 2023 and 2032. **Figure 6.2.1 (b)**, the Airfield Pavement Major Rehabilitation Exhibit, graphically depicts the major rehabilitation needs with rounded costs. As suggested previously, this is planning-level data that can be used by the Airport to support developing a practical CIP.

Figure 6.2.1 (a): 10-Year Major Rehabilitation Needs by Program Year





LEGEND

RW 13-31 — TYPICAL RUNWAY BRANCH ID
TW A — TYPICAL TAXIWAY BRANCH ID
AP S — TYPICAL APRON BRANCH ID

PROGRAM YEAR

2023	2028
2024	2029
2025	2030
2026	2031
2027	2032

"BRANCH"/"SECTION"
"YEAR"/"REHAB ACTIVITY"
"EST. COST"

RUNWAY LENGTHS DEPICTED IN THIS DRAWING ARE FOR PAVEMENT MANAGEMENT PURPOSES ONLY AND MAY NOT MATCH PUBLISHED RUNWAY LENGTHS. DRAWING NOT TO SCALE.



Chapter 7: Conclusion



Chapter 7 – Conclusion

7.1 Recommendations

7.1.1 Continued PCI Surveys

It is recommended that the Airport continue to perform regularly scheduled PCI surveys in accordance with the ASTM D5340-20 (or latest edition) to monitor the condition of airfield pavement facilities.

A high priority should be placed on maintaining good record keeping and re-inspecting the Airport's maintained pavement facilities to ensure continued safe aircraft operations. Per the FAA AC 150/5380-7B, a series of scheduled periodic inspections must be carried out for an effective maintenance program. Re-inspection of pavements should be scheduled in a timely manner to ensure that all areas, particularly those that may not come under day-to-day observation, are thoroughly evaluated and reported.

7.1.2 Localized Maintenance and Repair

While deterioration of the pavements due to usage and exposure to the environment cannot be prevented, applying timely and effective maintenance efforts can slow the anticipated rate of deterioration. Lack of adequate and timely maintenance is a significant factor in pavement deterioration. **Chapter 6** identified localized maintenance and repair needs. It is recommended that Airport sponsors coordinate with their respective Airport maintenance staff and Airport engineer when developing project-level maintenance and repair efforts.

7.1.3 Major Rehabilitation

Chapter 6 also identified major pavement rehabilitation project needs from 2023-2032. Identification of these rehabilitation needs are performed at the section level for manageable project areas and assume an unconstrained budget scenario. Given the uncertainty in Airport-specific budget information and prioritization goals, the unconstrained budget scenario represents a conservative scenario and identifies pavement needs over a 10-year period. Certainly, it is understood that most airports are faced with constrained budgets, thus further evaluation of projects based on prioritization, operational criticality, funding availability, and practicality is recommended.

7.1.4 Pavement Management System

The following recommendations are made to fully implement an effective pavement management program for the Airport:

- » Develop a detailed preventive maintenance program for the Airport based on the recommendations provided in **Section 6.1**;
- » Further refine and implement the identified 10-year major rehabilitation needs provided in **Section 6.2**;
- » Maintain detailed records on pavement maintenance, construction, and inspection; and
- » Maintain records on major pavement construction projects (year, scope, cost, and construction documents).

7.2 Supporting Documents

Airfield Pavement Network Definition Exhibit

The Airfield Pavement Network Definition Exhibit is located in **Chapter 3** and **Appendix C**. The Exhibit depicts the airfield layout in a manner that defines the airfield pavement infrastructure as branches, sections, and sample units in accordance with the ASTM D5340-20. The Exhibit is intended for planning purposes only. Further details can be found on the Airport's adopted Airport Layout Plan. Detailed characteristics are tabulated in **Appendix A**.

Airfield Pavement System Inventory Exhibit

The Airfield Pavement System Inventory Exhibit is located in **Chapter 3** and **Appendix C**. The Exhibit depicts recent and/or anticipated construction activity within the airfield pavement facilities reported by Airport staff. The Exhibit is intended to schematically identify the pavement limits of work and general work description. The information reported on the Airport Response Form provided by each participating airport was used as the basis of the changes. Furthermore, changes are confirmed at the Airport with Airport staff during the in-brief and debrief meeting.

Airfield Pavement Estimated Age Exhibit

The Airfield Pavement Estimated Age Exhibit is located in **Chapter 3** and **Appendix C**. Based on the review of historic airfield pavement construction activities, the Exhibit provides the approximate limits of the age of the pavement sections since the last major construction activity has occurred. This is intended to be a rough estimate based on interpretation of the limited data available at the time of report.

Airfield Pavement Condition Index Exhibit

The Airfield Pavement Condition Index Exhibit is located in **Chapter 4** and **Appendix C**. The Exhibit is a visual summary of the latest conditions reported from the PCI assessment performed at the Airport. Distress analysis occurred in accordance with ASTM D5340-20 (referenced in **Appendix E**), with results being analyzed using PAVER™ software to determine PCI values. The PCI values are identified in the Exhibit and graphically represented using the standard ASTM D5340-20 condition rating categories.

Airfield Pavement Major Rehabilitation Exhibit

The Airfield Pavement Major Rehabilitation Exhibit is located in **Chapter 6** and **Appendix C**. The Exhibit has been prepared based on the section condition analysis, pavement condition forecasts, and major rehabilitation needs analysis. The Exhibit graphically depicts the inventory with the associated rehabilitation type activity, program year, and the planning-level costs. Area limits, rehabilitation type, and planning-level costs should not be considered a design-level recommendation. A tabulation of the 10-Year Major Rehabilitation is located in **Appendix B**.

Inspection Photograph Documentation

Representative field conditions from the PCI assessment are documented with digital photographs located in **Appendix D**. Select photographs are provided with a limited caption on the distress(es) observed. "Vicinity" photos refer to the approximate boundaries of an inspected sample unit within the section and provide an overview of the section condition but are not focused on a specific distress. The Appendix does not contain photographs for every section and sample unit.

7.3 Conclusion

The FDOT SAPMP System Update Phase 2 2021-2023 was completed for the Airport on behalf of the FDOT AO in accordance with the FAA AC 150/5380-7B and 150/5380-6C. FDOT's implementation of the SAPMP has assisted public airports with this requirement in performing PCI survey inspections and analysis in accordance with the ASTM D5340-20.

7.4 References

The following documents are referenced as specific guidelines and procedures for maintaining Airport pavements, establishing an effective pavement maintenance program, and identifying specific pavement distresses, probable causes of distresses, survey guidelines, and recommended methods of repair.

- » ASTM D5340-20, Standard Test Method for Airport Pavement Condition Index Surveys, American Society for Testing and Materials, West Conshohocken, PA, 2018.
- » AC 150/5210-24 Airport Foreign Object Debris (FOD) Management, Federal Aviation Administration, Washington, D.C., 2010.
- » AC 150/5320-6F, Airport Pavement Design and Evaluation, Federal Aviation Administration, Washington, D.C., 2016.
- » AC 150/5380-7B, Airport Pavement Management Program (PMP), Federal Aviation Administration, Washington, D.C., 2014.
- » AC 150/5380-6C, Guidelines and Procedures for Maintenance of Airport Pavements, Federal Aviation Administration, Washington, D.C., 2014.
- » AC 150/5370-10H, Standard Specifications for Construction of Airports, Federal Aviation Administration, Washington, D.C., 2018.
- » Airport Improvement Program Handbook, Order 5100.38D, Change 1, Federal Aviation Administration, Washington, D.C., 2019.
- » Tri-Service Pavements Working Group (TSPWG) Manual 3-270-08. 14-03, Preventive Maintenance Plan (PMP) for Airfield Pavements, Department of Defense, Washington, D.C., 2019.
- » Unified Facilities Criteria (UFC) 3-260-16, O&M Manual: Standard Practice for Airfield Pavement Condition Surveys, Department of Defense, Washington, D.C., 2019.
- » Unified Facilities Criteria (UFC) 3-260-03, Airfield Pavement Evaluation, Department of Defense, Washington, D.C., 2001.
- » Shahin, Mohamed Y., Pavement Management for Airports, Roads, and Parking Lots, Springer, 2005.

A wide-angle photograph of an airfield runway stretching into the distance under a bright blue sky with scattered white clouds. The runway is dark asphalt with a central white dashed line and yellow edge lines. The image is framed by a red diagonal bar on the left and a blue diagonal bar on the right.

Appendix A: Airfield Pavement Analysis

A close-up, low-angle view of the runway pavement, showing a concrete strip with yellow chevron markings on the right side. The image is framed by a red diagonal bar on the left and a blue diagonal bar on the right.

Table A.1: Pavement System Inventory Details

Network ID	Branch ID	Branch Use	Section ID	Area (SF)	Surface Type	Estimate of Last Construction Date
SPG	RW 7-25	Runway	6205	18,375	AAC	6/1/2016
SPG	RW 7-25	Runway	6207	22,950	AAC	6/1/2016
SPG	RW 7-25	Runway	6208	21,525	AAC	6/1/2016
SPG	RW 7-25	Runway	6210	147,650	AAC	6/1/2016
SPG	RW 7-25	Runway	6213	19,590	AC	6/1/2016
SPG	RW 7-25	Runway	6215	30,125	AAC	6/1/2016
SPG	RW 7-25	Runway	6220	2,875	AAC	4/1/2022
SPG	RW 7-25	Runway	6225	5,285	AAC	4/1/2022
SPG	RW 18-36	Runway	6105	217,732	AAC	4/1/2022
SPG	TW A	Taxiway	103	17,162	AC	1/1/1991
SPG	TW A	Taxiway	105	15,000	AAC	1/1/1987
SPG	TW A	Taxiway	110	21,000	AAC	1/1/1987
SPG	TW A	Taxiway	115	65,457	AAC	1/1/1987
SPG	TW A	Taxiway	125	1,540	AAC	4/1/2022
SPG	TW A	Taxiway	130	3,523	AAC	4/1/2022
SPG	TW A1	Taxiway	120	4,672	AC	6/1/2016
SPG	TW A2	Taxiway	410	5,577	AC	6/1/2016
SPG	TW A3	Taxiway	310	5,518	AC	6/1/2016
SPG	TW A4	Taxiway	610	5,518	AC	6/1/2016
SPG	TW A4	Taxiway	620	11,150	AC	1/1/2013
SPG	TW B	Taxiway	205	87,871	AAC	1/1/1988
SPG	TW B	Taxiway	210	18,217	AAC	1/1/1988
SPG	TW B	Taxiway	215	6,420	AC	6/1/2016
SPG	TW B1	Taxiway	250	1,246	AAC	4/1/2022
SPG	TW B1	Taxiway	255	2,142	AAC	4/1/2022
SPG	TW B2	Taxiway	260	3,445	AC	4/1/2022
SPG	TW B2	Taxiway	265	2,731	AAC	4/1/2022
SPG	TW B3	Taxiway	270	3,445	AC	4/1/2022
SPG	TW B3	Taxiway	275	2,731	AAC	4/1/2022
SPG	TW B4	Taxiway	280	4,813	AC	4/1/2022
SPG	TW B4	Taxiway	285	2,142	AAC	4/1/2022
SPG	TW C	Taxiway	305	75,170	AC	5/25/2018
SPG	TW C	Taxiway	307	29,730	AAC	1/1/1991
SPG	TW C	Taxiway	308	33,474	AAC	1/1/1991
SPG	TW D	Taxiway	155	8,835	AAC	11/1/2021
SPG	TW D	Taxiway	157	3,327	AAC	4/1/2022
SPG	TW D	Taxiway	160	1,353	AAC	4/1/2022
SPG	TW D	Taxiway	510	33,920	AC	1/1/2002
SPG	TW D	Taxiway	515	23,608	AC	1/1/2011
SPG	TW D1	Taxiway	450	6,159	AC	1/1/2006
SPG	TW D2	Taxiway	740	29,398	AAC	7/1/2019
SPG	TW D3	Taxiway	470	3,795	AC	1/1/2011
SPG	TW D3	Taxiway	475	1,901	AC	1/1/2006
SPG	TW D5	Taxiway	150	5,816	AAC	6/1/2016

Network ID	Branch ID	Branch Use	Section ID	Area (SF)	Surface Type	Estimate of Last Construction Date
SPG	AP	Apron	4110	126,574	AC	1/1/1993
SPG	AP	Apron	4120	33,335	AAC	1/1/2002
SPG	AP	Apron	4135	42,820	AAC	1/1/2002
SPG	AP	Apron	4145	9,084	AAC	1/1/2002
SPG	AP	Apron	4150	5,101	AAC	7/1/2021
SPG	AP	Apron	4155	41,633	AAC	7/1/2021
SPG	AP	Apron	4160	37,874	AC	7/1/2020
SPG	AP	Apron	4165	36,941	AAC	7/1/2021
SPG	AP FUEL	Apron	4510	6,767	AC	1/1/2013
SPG	AP HELI	Apron	4610	21,255	AC	1/1/2006
SPG	AP MID	Apron	4405	85,370	AC	1/1/2013
SPG	AP MID	Apron	4410	15,414	AC	1/1/2013
SPG	AP NW	Apron	4310	76,197	AC	1/1/2006
SPG	AP NW	Apron	4315	35,173	AC	1/1/2011
SPG	AP NW	Apron	4320	4,732	AC	1/1/2002
SPG	AP NW	Apron	4325	14,232	AAC	1/1/2018

Table A.2: Pavement Condition Index Summary (Current PCI Survey) – Section Level

Network ID	Branch ID	Branch Use	Section ID	Area (SF)	PCI	Condition Rating
SPG	RW 7-25	Runway	6205	18,375	88	Good
SPG	RW 7-25	Runway	6207	22,950	79	Satisfactory
SPG	RW 7-25	Runway	6208	21,525	80	Satisfactory
SPG	RW 7-25	Runway	6210	147,650	79	Satisfactory
SPG	RW 7-25	Runway	6213	19,590	84	Satisfactory
SPG	RW 7-25	Runway	6215	30,125	91	Good
SPG	RW 7-25	Runway	6220	2,875	100	Good
SPG	RW 7-25	Runway	6225	5,285	100	Good
SPG	RW 18-36	Runway	6105	217,732	100	Good
SPG	TW A	Taxiway	103	17,162	50	Poor
SPG	TW A	Taxiway	105	15,000	38	Very Poor
SPG	TW A	Taxiway	110	21,000	44	Poor
SPG	TW A	Taxiway	115	65,457	57	Fair
SPG	TW A	Taxiway	125	1,540	100	Good
SPG	TW A	Taxiway	130	3,523	100	Good
SPG	TW A1	Taxiway	120	4,672	86	Good
SPG	TW A2	Taxiway	410	5,577	90	Good
SPG	TW A3	Taxiway	310	5,518	89	Good
SPG	TW A4	Taxiway	610	5,518	89	Good
SPG	TW A4	Taxiway	620	11,150	87	Good
SPG	TW B	Taxiway	205	87,871	60	Fair
SPG	TW B	Taxiway	210	18,217	48	Poor
SPG	TW B	Taxiway	215	6,420	75	Satisfactory
SPG	TW B1	Taxiway	250	1,246	100	Good
SPG	TW B1	Taxiway	255	2,142	100	Good
SPG	TW B2	Taxiway	260	3,445	100	Good
SPG	TW B2	Taxiway	265	2,731	100	Good
SPG	TW B3	Taxiway	270	3,445	100	Good
SPG	TW B3	Taxiway	275	2,731	100	Good
SPG	TW B4	Taxiway	280	4,813	100	Good
SPG	TW B4	Taxiway	285	2,142	100	Good
SPG	TW C	Taxiway	305	75,170	94	Good
SPG	TW C	Taxiway	307	29,730	50	Poor
SPG	TW C	Taxiway	308	33,474	51	Poor
SPG	TW D	Taxiway	155	8,835	100	Good
SPG	TW D	Taxiway	157	3,327	100	Good
SPG	TW D	Taxiway	160	1,353	100	Good
SPG	TW D	Taxiway	510	33,920	64	Fair
SPG	TW D	Taxiway	515	23,608	82	Satisfactory
SPG	TW D1	Taxiway	450	6,159	65	Fair
SPG	TW D2	Taxiway	740	29,398	86	Good
SPG	TW D3	Taxiway	470	3,795	61	Fair
SPG	TW D3	Taxiway	475	1,901	68	Fair
SPG	TW D5	Taxiway	150	5,816	90	Good
SPG	AP	Apron	4110	126,574	42	Poor

Network ID	Branch ID	Branch Use	Section ID	Area (SF)	PCI	Condition Rating
SPG	AP	Apron	4120	33,335	50	Poor
SPG	AP	Apron	4135	42,820	64	Fair
SPG	AP	Apron	4145	9,084	51	Poor
SPG	AP	Apron	4150	5,101	100	Good
SPG	AP	Apron	4155	41,633	100	Good
SPG	AP	Apron	4160	37,874	100	Good
SPG	AP	Apron	4165	36,941	100	Good
SPG	AP FUEL	Apron	4510	6,767	85	Satisfactory
SPG	AP HELI	Apron	4610	21,255	63	Fair
SPG	AP MID	Apron	4405	85,370	90	Good
SPG	AP MID	Apron	4410	15,414	85	Satisfactory
SPG	AP NW	Apron	4310	76,197	68	Fair
SPG	AP NW	Apron	4315	35,173	83	Satisfactory
SPG	AP NW	Apron	4320	4,732	73	Satisfactory
SPG	AP NW	Apron	4325	14,232	90	Good

Table A.3: Forecasted PCI Values 2023-2032 – Section-Level

Network ID	Branch ID	Section ID	Current PCI	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032
SPG	RW 7-25	6205	88	86	84	82	81	79	77	75	74	72	70
SPG	RW 7-25	6207	79	77	75	73	72	70	68	66	65	63	61
SPG	RW 7-25	6208	80	78	76	74	73	71	69	67	66	64	62
SPG	RW 7-25	6210	79	77	75	73	72	70	68	66	65	63	61
SPG	RW 7-25	6213	84	82	80	79	77	76	75	74	73	72	71
SPG	RW 7-25	6215	91	89	87	85	84	82	80	78	77	75	73
SPG	RW 7-25	6220	100	98	96	94	93	91	89	87	86	84	82
SPG	RW 7-25	6225	100	98	96	94	93	91	89	87	86	84	82
SPG	RW 18-36	6105	100	98	96	94	93	91	89	87	86	84	82
SPG	TW A	103	50	49	49	48	47	46	45	44	44	43	41
SPG	TW A	105	38	36	34	32	30	28	26	24	22	20	18
SPG	TW A	110	44	42	41	39	37	35	33	31	29	27	25
SPG	TW A	115	57	56	55	55	54	53	52	52	51	50	49
SPG	TW A	125	100	97	95	92	90	88	86	84	82	80	79
SPG	TW A	130	100	97	95	92	90	88	86	84	82	80	79
SPG	TW A1	120	86	84	82	80	79	77	76	75	74	72	71
SPG	TW A2	410	90	88	86	84	82	81	79	78	76	75	74
SPG	TW A3	310	89	87	85	83	81	80	78	77	76	74	73
SPG	TW A4	610	89	87	85	83	81	80	78	77	76	74	73
SPG	TW A4	620	87	85	83	81	80	78	77	75	74	73	72
SPG	TW B	205	60	59	58	58	57	56	56	55	54	53	53
SPG	TW B	210	48	47	45	44	43	41	39	38	36	34	32
SPG	TW B	215	75	73	72	71	70	69	68	67	66	66	65
SPG	TW B1	250	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B1	255	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B2	260	100	97	95	93	90	88	87	85	83	81	80
SPG	TW B2	265	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B3	270	100	97	95	93	90	88	87	85	83	81	80
SPG	TW B3	275	100	97	95	92	90	88	86	84	82	80	79
SPG	TW B4	280	100	97	95	93	90	88	87	85	83	81	80
SPG	TW B4	285	100	97	95	92	90	88	86	84	82	80	79
SPG	TW C	305	94	91	89	87	86	84	82	80	79	77	76
SPG	TW C	307	50	49	48	47	45	44	43	41	39	38	36
SPG	TW C	308	51	50	49	48	47	45	44	43	41	39	38
SPG	TW D	155	100	96	94	91	89	87	85	83	81	80	78
SPG	TW D	157	100	97	95	92	90	88	86	84	82	80	79
SPG	TW D	160	100	97	95	92	90	88	86	84	82	80	79
SPG	TW D	510	64	63	63	62	61	61	60	60	59	59	58
SPG	TW D	515	82	80	79	77	76	74	73	72	71	70	69
SPG	TW D1	450	65	64	63	63	62	62	61	60	60	59	59
SPG	TW D2	740	86	84	82	80	78	77	75	74	72	71	70
SPG	TW D3	470	61	60	60	59	59	58	58	58	57	57	56
SPG	TW D3	475	68	67	66	65	65	64	63	62	62	61	61
SPG	TW D5	150	90	87	85	83	82	80	78	77	75	74	72

Network ID	Branch ID	Section ID	Current PCI	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032
SPG	AP	4110	42	40	38	36	34	32	29	26	23	20	17
SPG	AP	4120	50	47	45	43	41	39	36	34	32	30	28
SPG	AP	4135	64	61	59	57	55	53	50	48	46	44	42
SPG	AP	4145	51	48	46	44	42	40	37	35	33	31	29
SPG	AP	4150	100	96	93	91	89	87	85	82	80	78	76
SPG	AP	4155	100	96	93	91	89	87	85	82	80	78	76
SPG	AP	4160	100	94	91	89	87	85	83	81	79	77	75
SPG	AP	4165	100	96	93	91	89	87	85	82	80	78	76
SPG	AP FUEL	4510	85	82	81	79	77	75	73	71	70	68	67
SPG	AP HELI	4610	63	62	61	60	59	58	57	56	56	55	54
SPG	AP MID	4405	90	87	85	83	81	79	77	76	74	72	70
SPG	AP MID	4410	85	82	81	79	77	75	73	71	70	68	67
SPG	AP NW	4310	68	66	65	64	62	61	60	59	58	58	57
SPG	AP NW	4315	83	81	79	77	75	73	72	70	68	67	66
SPG	AP NW	4320	73	71	69	68	66	65	64	63	62	60	60
SPG	AP NW	4325	90	87	85	83	81	79	76	74	72	70	68

11/17/2022

Work History Report

Page 1 of 11

Pavement Database: FDOT

Network: ALBERT WHITTED Branch: AP FUEL FUEL APRON Section: 4510 Surface: AC
 L.C.D. 1/1/2013 Use: APRON Rank: P Length: 200.00 (Ft) Width: 50.00 (Ft) True Area: 6767.000002 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2013	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403, 4" P-219, 6" P-160, COMP

Network: ALBERT WHITTED Branch: AP HELI HELICOPTER PA Section: 4610 Surface: AC
 L.C.D. 1/1/2006 Use: APRON Rank: P Length: 240.00 (Ft) Width: 92.00 (Ft) True Area: 21255.000000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2006	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED Branch: AP MID APRON MIDFIEL Section: 4405 Surface: AC
 L.C.D. 1/1/2013 Use: APRON Rank: P Length: 450.00 (Ft) Width: 200.00 (Ft) True Area: 85370.000002 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2013	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403, 4" P-219, 6" P-160, COMP

Network: ALBERT WHITTED Branch: AP MID APRON MIDFIEL Section: 4410 Surface: AC
 L.C.D. 1/1/2013 Use: APRON Rank: P Length: 180.00 (Ft) Width: 85.00 (Ft) True Area: 15414.000000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2013	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403, 4" P-219, 6" P-160, COMP

Network: ALBERT WHITTED Branch: AP NW NORTHWEST AP Section: 4310 Surface: AC
 L.C.D. 1/1/2006 Use: APRON Rank: P Length: 365.00 (Ft) Width: 155.00 (Ft) True Area: 76197.000002 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2006	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED Branch: AP NW NORTHWEST AP Section: 4315 Surface: AC
 L.C.D. 1/1/2011 Use: APRON Rank: P Length: 190.00 (Ft) Width: 220.00 (Ft) True Area: 35173.000001 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2011	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED Branch: AP NW NORTHWEST AP Section: 4320 Surface: AC
 L.C.D. 1/1/2002 Use: APRON Rank: P Length: 170.00 (Ft) Width: 28.00 (Ft) True Area: 4732.000001 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2002	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED Branch: AP NW NORTHWEST AP Section: 4325 Surface: AAC
 L.C.D. 1/1/2018 Use: APRON Rank: P Length: 206.00 (Ft) Width: 60.00 (Ft) True Area: 14232.000000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2018	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	
1/1/2006	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

11/17/2022

Work History Report

Page 2 of 11

Pavement Database: FDOT

Network: ALBERT WHITTED		Branch: AP	APRON		Section: 4110	Surface: AC
L.C.D. 1/1/1993	Use: APRON	Rank: P	Length: 485.00 (Ft)	Width: 270.00 (Ft)	True Area: 126574.0000 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/1993	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	1993 AC PAVEMENT. SOIL: SP.

Network: ALBERT WHITTED		Branch: AP	APRON		Section: 4120	Surface: AAC
L.C.D. 1/1/2002	Use: APRON	Rank: P	Length: 300.00 (Ft)	Width: 85.00 (Ft)	True Area: 33335.00001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2018	PA-AC	Patching - AC	0.00	0.00	<input type="checkbox"/>	1965 AC PAVEMENT
1/1/2002	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	
1/1/1965	IMPORT ED	BUILT	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED		Branch: AP	APRON		Section: 4135	Surface: AAC
L.C.D. 1/1/2002	Use: APRON	Rank: P	Length: 1,535.00 (Ft)	Width: 20.00 (Ft)	True Area: 42820.00001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2002	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	
12/25/1999	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED		Branch: AP	APRON		Section: 4145	Surface: AAC
L.C.D. 1/1/2002	Use: APRON	Rank: P	Length: 210.00 (Ft)	Width: 40.00 (Ft)	True Area: 9084.000002 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2002	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	
1/1/1965	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED		Branch: AP	APRON		Section: 4150	Surface: AAC
L.C.D. 7/1/2021	Use: APRON	Rank: P	Length: 40.00 (Ft)	Width: 130.00 (Ft)	True Area: 5101.000001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
7/1/2021	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	Variable depth mill, Variable depth P-
1/1/2002	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	
1/1/1965	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED		Branch: AP	APRON		Section: 4155	Surface: AAC
L.C.D. 7/1/2021	Use: APRON	Rank: P	Length: 330.00 (Ft)	Width: 130.00 (Ft)	True Area: 41633.00001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
7/1/2021	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	Variable depth mill, Variable depth P-
1/1/2018	PA-AC	Patching - AC	0.00	0.00	<input type="checkbox"/>	
1/1/2002	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1965 AC PAVEMENT
1/1/1965	IMPORT ED	BUILT	0.00	0.00	<input checked="" type="checkbox"/>	

11/17/2022

Work History Report

Page 3 of 11

Pavement Database: FDOT

Network: ALBERT WHITTED		Branch: AP	APRON		Section: 4160	Surface: AC
L.C.D. 7/1/2020	Use: APRON	Rank: P	Length: 260.00 (Ft)	Width: 145.00 (Ft)	True Area: 37874.00001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
7/1/2020	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	2" P-402, 5" P-219

Network: ALBERT WHITTED		Branch: AP	APRON		Section: 4165	Surface: AAC
L.C.D. 7/1/2021	Use: APRON	Rank: P	Length: 420.00 (Ft)	Width: 60.00 (Ft)	True Area: 36941.00001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
7/1/2021	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	Variable depth mill, Variable depth P-
1/1/2002	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	
12/25/1999	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED		Branch: RW 18-36	RUNWAY 18-36		Section: 6105	Surface: AAC
L.C.D. 4/1/2022	Use: RUNWAY	Rank: P	Length: 2,864.00 (Ft)	Width: 75.00 (Ft)	True Area: 217732.00000 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O 1992: 1"-2" P-401 1988: 1.5" P-401 ON P-609 ON P-401
1/1/1992	OL-AS	Overlay - AC Structural	0.00	1.00	<input checked="" type="checkbox"/>	
1/1/1950	NC-AC	New Construction - AC	0.00	1.50	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED		Branch: RW 7-25	RUNWAY 7-25		Section: 6205	Surface: AAC
L.C.D. 6/1/2016	Use: RUNWAY	Rank: P	Length: 245.00 (Ft)	Width: 75.00 (Ft)	True Area: 18375.00000 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
6/1/2016	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403 1991: 2.5" P-401 ON 5.5" P-211 ON 6
1/1/1991	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	
1/1/1965	NC-AC	New Construction - AC	0.00	2.50	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED		Branch: RW 7-25	RUNWAY 7-25		Section: 6207	Surface: AAC
L.C.D. 6/1/2016	Use: RUNWAY	Rank: P	Length: 300.00 (Ft)	Width: 75.00 (Ft)	True Area: 22950.00000 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
6/1/2016	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403 1965 AC PAVEMENT
1/1/1965	IMPORT ED	BUILT	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED		Branch: RW 7-25	RUNWAY 7-25		Section: 6208	Surface: AAC
L.C.D. 6/1/2016	Use: RUNWAY	Rank: P	Length: 287.00 (Ft)	Width: 75.00 (Ft)	True Area: 21525.00000 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
6/1/2016	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403 1965 AC Pavement
1/1/2012	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	
1/1/1965	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

11/17/2022

Work History Report

Page 4 of 11

Pavement Database: FDOT

Network: ALBERT WHITTED Branch: RW 7-25 RUNWAY 7-25 Section: 6210 Surface: AAC
 L.C.D. 6/1/2016 Use: RUNWAY Rank: P Length: 1,970.00 (Ft) Width: 75.00 (Ft) True Area: 147650.0000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
6/1/2016	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403
1/1/1965	IMPORT ED	BUILT	0.00	0.00	<input checked="" type="checkbox"/>	1965 AC PAVEMENT
1/1/1965	IMPORT ED	OVERLAY	0.00	0.00	<input checked="" type="checkbox"/>	SOIL: SP

Network: ALBERT WHITTED Branch: RW 7-25 RUNWAY 7-25 Section: 6213 Surface: AC
 L.C.D. 6/1/2016 Use: RUNWAY Rank: P Length: 260.00 (Ft) Width: 75.00 (Ft) True Area: 19590.00000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
6/1/2016	CR-AC	Complete Reconstruction - AC	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403, 5" P-210
1/1/1965	IMPORT ED	BUILT	0.00	0.00	<input checked="" type="checkbox"/>	1965 AC PAVEMENT
1/1/1965	IMPORT ED	OVERLAY	0.00	0.00	<input checked="" type="checkbox"/>	SOIL: SP

Network: ALBERT WHITTED Branch: RW 7-25 RUNWAY 7-25 Section: 6215 Surface: AAC
 L.C.D. 6/1/2016 Use: RUNWAY Rank: P Length: 407.00 (Ft) Width: 75.00 (Ft) True Area: 30125.00000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
6/1/2016	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403
1/1/1991	IMPORT ED	BUILT	0.00	2.00	<input checked="" type="checkbox"/>	1991: 2" P-401 ON 6" P-211 ON 6" P-154
1/1/1991	IMPORT ED	OVERLAY	0.00	0.00	<input checked="" type="checkbox"/>	SOIL: SP

Network: ALBERT WHITTED Branch: RW 7-25 RUNWAY 7-25 Section: 6220 Surface: AAC
 L.C.D. 4/1/2022 Use: RUNWAY Rank: P Length: 40.00 (Ft) Width: 75.00 (Ft) True Area: 2875.000000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O
6/1/2016	CR-AC	Complete Reconstruction - AC	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403, 5" P-210
1/1/1965	IMPORT ED	BUILT	0.00	0.00	<input checked="" type="checkbox"/>	1965 AC PAVEMENT
1/1/1965	IMPORT ED	OVERLAY	0.00	0.00	<input checked="" type="checkbox"/>	SOIL: SP

Network: ALBERT WHITTED Branch: RW 7-25 RUNWAY 7-25 Section: 6225 Surface: AAC
 L.C.D. 4/1/2022 Use: RUNWAY Rank: P Length: 70.00 (Ft) Width: 75.00 (Ft) True Area: 5285.000001 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O
1/1/1992	OL-AS	Overlay - AC Structural	0.00	1.00	<input checked="" type="checkbox"/>	1992: 1"-2" P-401
1/1/1950	NC-AC	New Construction - AC	0.00	1.50	<input checked="" type="checkbox"/>	1988: 1.5" P-401 ON P-609 ON P-401

11/17/2022

Work History Report

Page 5 of 11

Pavement Database: FDOT

Network: ALBERT WHITTED Branch: TW A TAXIWAY A Section: 103 Surface: AC L.C.D. 1/1/1991 Use: TAXIWAY Rank: P Length: 450.00 (Ft) Width: 40.00 (Ft) True Area: 17162.00000 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/1991	NC-AC	New Construction - AC	0.00	2.50	<input checked="" type="checkbox"/>	1991: 2.5" P-401 ON 5.5" P-211 ON 6"

Network: ALBERT WHITTED Branch: TW A TAXIWAY A Section: 105 Surface: AAC L.C.D. 1/1/1987 Use: TAXIWAY Rank: P Length: 500.00 (Ft) Width: 40.00 (Ft) True Area: 15000.00000 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/1987	IMPORT ED	OVERLAY	0.00	0.00	<input checked="" type="checkbox"/>	1987 AC OVERLAY. SOIL: SP.
1/1/1961	IMPORT ED	BUILT	0.00	1.00	<input checked="" type="checkbox"/>	1961: 1" AC ON 6" LIME ROCK BASE

Network: ALBERT WHITTED Branch: TW A TAXIWAY A Section: 110 Surface: AAC L.C.D. 1/1/1987 Use: TAXIWAY Rank: P Length: 400.00 (Ft) Width: 40.00 (Ft) True Area: 21000.00000 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/1987	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1987: AC OVERLAY. SOIL: SP.
1/1/1961	NC-AC	New Construction - AC	0.00	1.00	<input checked="" type="checkbox"/>	ASSUME: 1961 1" AC ON 6" LIME

Network: ALBERT WHITTED Branch: TW A1 TAXIWAY A1 Section: 120 Surface: AC L.C.D. 6/1/2016 Use: TAXIWAY Rank: P Length: 95.00 (Ft) Width: 40.00 (Ft) True Area: 4672.000001 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
6/1/2016	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403, 5" P-210

Network: ALBERT WHITTED Branch: TW A TAXIWAY A Section: 115 Surface: AAC L.C.D. 1/1/1987 Use: TAXIWAY Rank: P Length: 1,615.00 (Ft) Width: 40.00 (Ft) True Area: 65457.00002 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/1987	IMPORT ED	OVERLAY	0.00	0.00	<input checked="" type="checkbox"/>	1987 AC OVERLAY. SOIL: SP.
1/1/1965	IMPORT ED	BUILT	0.00	1.00	<input checked="" type="checkbox"/>	1965: 1" AC ON 6" LIME ROCK BASE

Network: ALBERT WHITTED Branch: TW A TAXIWAY A Section: 125 Surface: AAC L.C.D. 4/1/2022 Use: TAXIWAY Rank: P Length: 40.00 (Ft) Width: 40.00 (Ft) True Area: 1540.000000 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O
1/1/1989	OL-AS	Overlay - AC Structural	0.00	0.00	<input checked="" type="checkbox"/>	1989 C OVERLAY ON EXISTING A
1/1/1950	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	

11/17/2022

Work History Report

Page 6 of 11

Pavement Database: FDOT

Network: ALBERT WHITTED		Branch: TW A		TAXIWAY A		Section: 130	Surface: AAC
L.C.D. 4/1/2022		Use: TAXIWAY	Rank: P	Length: 70.00 (Ft)	Width: 50.00 (Ft)	True Area: 3523.000001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments	
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O	
1/1/1992	OL-AS	Overlay - AC Structural	0.00	1.00	<input checked="" type="checkbox"/>	1992: 1"-2" P-401	
1/1/1950	NC-AC	New Construction - AC	0.00	1.50	<input checked="" type="checkbox"/>	1988: 1.5" P-401 ON P-609 ON P-401	

Network: ALBERT WHITTED		Branch: TW A2		TAXIWAY A2		Section: 410	Surface: AC
L.C.D. 6/1/2016		Use: TAXIWAY	Rank: P	Length: 95.00 (Ft)	Width: 41.00 (Ft)	True Area: 5577.000001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments	
6/1/2016	CR-AC	Complete Reconstruction - AC	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403, 5" P-210	
1/1/1991	IMPORT ED	BUILT	0.00	0.00	<input checked="" type="checkbox"/>	ESTIMATE 1991 AC	

Network: ALBERT WHITTED		Branch: TW A3		TAXIWAY A3		Section: 310	Surface: AC
L.C.D. 6/1/2016		Use: TAXIWAY	Rank: P	Length: 95.00 (Ft)	Width: 41.00 (Ft)	True Area: 5518.000001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments	
6/1/2016	CR-AC	Complete Reconstruction - AC	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403, 5" P-210	
1/1/1987	IMPORT ED	BUILT	0.00	0.00	<input checked="" type="checkbox"/>	1987 AC OVERLAY ON EXISTING AC	
1/1/1950	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>		

Network: ALBERT WHITTED		Branch: TW A4		TAXIWAY A4		Section: 610	Surface: AC
L.C.D. 6/1/2016		Use: TAXIWAY	Rank: P	Length: 95.00 (Ft)	Width: 41.00 (Ft)	True Area: 5518.000001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments	
6/1/2016	CR-AC	Complete Reconstruction - AC	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403, 5" P-210	
1/1/1987	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	1987 AC OVERLAY ON EXISTING	

Network: ALBERT WHITTED		Branch: TW A4		TAXIWAY A4		Section: 620	Surface: AC
L.C.D. 1/1/2013		Use: TAXIWAY	Rank: P	Length: 300.00 (Ft)	Width: 30.00 (Ft)	True Area: 11150.000000 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments	
1/1/2013	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403, 4" P-219, 6" P-160, COMP	

Network: ALBERT WHITTED		Branch: TW B1		TAXIWAY B1		Section: 250	Surface: AAC
L.C.D. 4/1/2022		Use: TAXIWAY	Rank: P	Length: 34.00 (Ft)	Width: 35.00 (Ft)	True Area: 1246.000000 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments	
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O	
1/1/1984	OL-AS	Overlay - AC Structural	0.00	0.00	<input checked="" type="checkbox"/>	1984 AC OVERLAY ON EXISTING	
1/1/1950	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>		

11/17/2022

Work History Report

Page 7 of 11

Pavement Database: FDOT

Network: ALBERT WHITTED		Branch: TW B1	TAXIWAY B1	Section: 255	Surface: AAC	
L.C.D. 4/1/2022	Use: TAXIWAY	Rank: P	Length: 62.00 (Ft)	Width: 35.00 (Ft)	True Area: 2142.000000 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O
1/1/1992	OL-AS	Overlay - AC Structural	0.00	1.00	<input checked="" type="checkbox"/>	1992: 1"-2" P-401
1/1/1950	NC-AC	New Construction - AC	0.00	1.50	<input checked="" type="checkbox"/>	1988: 1.5" P-401 ON P-609 ON P-401

Network: ALBERT WHITTED		Branch: TW B		TAXIWAY B		Section: 205		Surface: AAC			
L.C.D. 1/1/1988		Use: TAXIWAY		Rank: P		Length: 2,150.00 (Ft)		Width: 40.00 (Ft)		True Area: 87871.00002 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments					
1/1/1988	IMPORT ED	OVERLAY	0.00	1.50	<input checked="" type="checkbox"/>	1988: 1.5" P-401 ON P-609					
1/1/1988	IMPORT ED	OVERLAY	0.00	0.00	<input checked="" type="checkbox"/>	SURFACE TREATEMENT ON P-401					
1/1/1961	IMPORT ED	BUILT	0.00	1.00	<input checked="" type="checkbox"/>	SOIL: SP					
						1961: 1" AC ON 6" LIME ROCK BASE					

Network: ALBERT WHITTED		Branch: TW B		TAXIWAY B		Section: 210		Surface: AAC			
L.C.D. 1/1/1988		Use: TAXIWAY		Rank: P		Length: 415.00 (Ft)		Width: 40.00 (Ft)		True Area: 18217.00000 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments					
1/1/1988	IMPORT ED	OVERLAY	0.00	1.50	<input checked="" type="checkbox"/>	1988: 1.5" P-401 ON P-609					
1/1/1988	IMPORT ED	OVERLAY	0.00	0.00	<input checked="" type="checkbox"/>	SURFACE TREATMENT ON P-401					
1/1/1965	IMPORT ED	BUILT	0.00	1.00	<input checked="" type="checkbox"/>	SOIL: SP					
						1965: 1" AC ON 6" LIME ROCK BASE					

Network: ALBERT WHITTED		Branch: TW B	TAXIWAY B		Section: 215	Surface: AC
L.C.D. 6/1/2016	Use: TAXIWAY	Rank: P	Length: 100.00 (Ft)	Width: 50.00 (Ft)	True Area: 6420.000001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
6/1/2016	CR-AC	Complete Reconstruction - AC	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403, 5" P-210
1/1/1965	NC-AC	New Construction - AC	0.00	1.00	<input checked="" type="checkbox"/>	1965: 1" P-401 ON 6" P-211. SOIL: S

Network: ALBERT WHITTED		Branch: TW B2	TAXIWAY B2	Section: 260	Surface: AC	
L.C.D. 4/1/2022	Use: TAXIWAY	Rank: P	Length: 55.00 (Ft)	Width: 50.00 (Ft)	True Area: 3445.000001 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	4" P-403, 6" P-211, 12" P-152

Network: ALBERT WHITTED		Branch: TW B2	TAXIWAY B2		Section: 265	Surface: AAC
L.C.D. 4/1/2022	Use: TAXIWAY	Rank: P	Length: 62.00 (Ft)	Width: 35.00 (Ft)	True Area: 2731.000000 (SqFt)	
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O
1/1/1992	OL-AS	Overlay - AC Structural	0.00	1.00	<input checked="" type="checkbox"/>	1992: 1"-2" P-401
1/1/1950	NC-AC	New Construction - AC	0.00	1.50	<input checked="" type="checkbox"/>	1988: 1.5" P-401 ON P-609 ON P-401

11/17/2022

Work History Report

Page 8 of 11

Pavement Database: FDOT

Network: ALBERT WHITTED Branch: TW B3 TAXIWAY B3 Section: 270 Surface: AC
 L.C.D. 4/1/2022 Use: TAXIWAY Rank: P Length: 55.00 (Ft) Width: 50.00 (Ft) True Area: 3445.000001 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	4" P-403, 6" P-211, 12" P-152

Network: ALBERT WHITTED Branch: TW B3 TAXIWAY B3 Section: 275 Surface: AAC
 L.C.D. 4/1/2022 Use: TAXIWAY Rank: P Length: 62.00 (Ft) Width: 35.00 (Ft) True Area: 2731.000000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O
1/1/1992	OL-AS	Overlay - AC Structural	0.00	1.00	<input checked="" type="checkbox"/>	1992: 1"-2" P-401
1/1/1950	NC-AC	New Construction - AC	0.00	1.50	<input checked="" type="checkbox"/>	1988: 1.5" P-401 ON P-609 ON P-401

Network: ALBERT WHITTED Branch: TW B4 TAXIWAY B4 Section: 280 Surface: AC
 L.C.D. 4/1/2022 Use: TAXIWAY Rank: P Length: 95.00 (Ft) Width: 45.00 (Ft) True Area: 4813.000001 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	4" P-403, 6" P-211, 12" P-152

Network: ALBERT WHITTED Branch: TW B4 TAXIWAY B4 Section: 285 Surface: AAC
 L.C.D. 4/1/2022 Use: TAXIWAY Rank: P Length: 62.00 (Ft) Width: 35.00 (Ft) True Area: 2142.000000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O
1/1/1992	OL-AS	Overlay - AC Structural	0.00	1.00	<input checked="" type="checkbox"/>	1992: 1"-2" P-401
1/1/1950	NC-AC	New Construction - AC	0.00	1.50	<input checked="" type="checkbox"/>	1988: 1.5" P-401 ON P-609 ON P-401

Network: ALBERT WHITTED Branch: TW C TAXIWAY C Section: 305 Surface: AC
 L.C.D. 5/25/2018 Use: TAXIWAY Rank: P Length: 835.00 (Ft) Width: 86.00 (Ft) True Area: 75170.00002 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
5/25/2018	CR-AC	Complete Reconstruction - AC	0.00	0.00	<input checked="" type="checkbox"/>	3" P-403, 6-10" Reclaimed Base
1/1/1950	IMPORT ED	BUILT	0.00	0.00	<input checked="" type="checkbox"/>	1950 AC PAVEMENT

Network: ALBERT WHITTED Branch: TW C TAXIWAY C Section: 307 Surface: AAC
 L.C.D. 1/1/1991 Use: TAXIWAY Rank: P Length: 705.00 (Ft) Width: 36.00 (Ft) True Area: 29730.00000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
7/1/2020	PA-AC	Patching - AC	0.00	0.00	<input type="checkbox"/>	
1/1/1991	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1991 AC OVERLAY ON EXISTING
1/1/1950	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	

11/17/2022

Work History Report

Page 9 of 11

Pavement Database: FDOT

Network: ALBERT WHITTED Branch: TW C TAXIWAY C Section: 308 Surface: AAC L.C.D. 1/1/1991 Use: TAXIWAY Rank: P Length: 635.00 (Ft) Width: 50.00 (Ft) True Area: 33474.00001 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
7/1/2020	PA-AC	Patching - AC	0.00	0.00	<input type="checkbox"/>	1950 AC PAVEMENT
1/1/1991	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	
1/1/1950	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED Branch: TW D1 TAXIWAY D1 Section: 450 Surface: AAC L.C.D. 1/1/2006 Use: TAXIWAY Rank: P Length: 115.00 (Ft) Width: 50.00 (Ft) True Area: 6159.000001 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2006	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED Branch: TW D TAXIWAY D Section: 155 Surface: AAC L.C.D. 11/1/2021 Use: TAXIWAY Rank: P Length: 200.00 (Ft) Width: 62.00 (Ft) True Area: 8835.000002 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
11/1/2021	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1991: 2" P-401 ON 6" P-211 ON 6" P-SOIL: SP
1/1/1991	NC-AC	New Construction - AC	0.00	2.00	<input checked="" type="checkbox"/>	
1/1/1991	IMPORT ED	OVERLAY	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED Branch: TW D TAXIWAY D Section: 157 Surface: AAC L.C.D. 4/1/2022 Use: TAXIWAY Rank: P Length: 75.00 (Ft) Width: 40.00 (Ft) True Area: 3327.000001 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O
1/1/1992	OL-AS	Overlay - AC Structural	0.00	1.00	<input checked="" type="checkbox"/>	1992: 1"-2" P-401
1/1/1950	NC-AC	New Construction - AC	0.00	1.50	<input checked="" type="checkbox"/>	1988: 1.5" P-401 ON P-609 ON P-401

Network: ALBERT WHITTED Branch: TW D TAXIWAY D Section: 160 Surface: AAC L.C.D. 4/1/2022 Use: TAXIWAY Rank: P Length: 40.00 (Ft) Width: 35.00 (Ft) True Area: 1353.000000 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
4/1/2022	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	1.5" Variable cold milling, 2" P-403 O
1/1/1991	NU-IN	New Construction - Initial	0.00	2.00	<input checked="" type="checkbox"/>	1991: 2" P-401 ON 6" P-211 ON 6" P-

Network: ALBERT WHITTED Branch: TW D2 TAXIWAY D2 Section: 740 Surface: AAC L.C.D. 7/1/2019 Use: TAXIWAY Rank: P Length: 405.00 (Ft) Width: 55.00 (Ft) True Area: 29398.00000 (SqFt)						
Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
7/1/2019	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	
1/1/2002	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

11/17/2022

Work History Report

Page 10 of 11

Pavement Database: FDOT

Network: ALBERT WHITTED **Branch:** TW D3 **TAXIWAY D3** **Section:** 470 **Surface:** AC
L.C.D. 1/1/2011 **Use:** TAXIWAY **Rank:** P **Length:** 71.00 (Ft) **Width:** 35.00 (Ft) **True Area:** 3795.000001 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2011	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED **Branch:** TW D3 **TAXIWAY D3** **Section:** 475 **Surface:** AC
L.C.D. 1/1/2006 **Use:** TAXIWAY **Rank:** P **Length:** 55.00 (Ft) **Width:** 25.00 (Ft) **True Area:** 1901.000000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2006	NC-AC	New Construction - AC	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED **Branch:** TW D **TAXIWAY D** **Section:** 510 **Surface:** AC
L.C.D. 1/1/2002 **Use:** TAXIWAY **Rank:** P **Length:** 1,355.00 (Ft) **Width:** 25.00 (Ft) **True Area:** 33920.00001 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2002	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED **Branch:** TW D **TAXIWAY D** **Section:** 515 **Surface:** AC
L.C.D. 1/1/2011 **Use:** TAXIWAY **Rank:** P **Length:** 890.00 (Ft) **Width:** 25.00 (Ft) **True Area:** 23608.00000 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
1/1/2011	NU-IN	New Construction - Initial	0.00	0.00	<input checked="" type="checkbox"/>	

Network: ALBERT WHITTED **Branch:** TW D5 **TAXIWAY D5** **Section:** 150 **Surface:** AAC
L.C.D. 6/1/2016 **Use:** TAXIWAY **Rank:** P **Length:** 92.00 (Ft) **Width:** 62.00 (Ft) **True Area:** 5816.000001 (SqFt)

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major M&R	Comments
6/1/2016	ML-OVL	Mill and Overlay	0.00	0.00	<input checked="" type="checkbox"/>	2" P-403
1/1/1991	NC-AC	New Construction - AC	0.00	2.00	<input checked="" type="checkbox"/>	1991: 2" P-401 ON 6" P-211 ON 6" P-

Summary:

Work Description	Section Count	Area Total (SqFt)	Thickness Avg (in)	Thickness STD (in)
BUILT	14	570,968.00	0.43	0.62
Complete Reconstruction - AC	7	120,668.00	0.00	0.00
Mill and Overlay	34	903,851.00	0.00	0.00
New Construction - AC	28	583,127.00	0.82	0.88
New Construction - Initial	20	496,213.00	0.10	0.44
OVERLAY	11	501,708.00	0.27	0.58
Overlay - AC Structural	10	242,399.00	0.80	0.40
Patching - AC	4	138,172.00	0.00	0.00

11/17/2022

Branch Condition Report

Page 1 of 2

Pavement Database: FDOT

Branch ID	Number of Sections	Sum Section Length (Ft)	Avg Section Width (Ft)	True Area (SqFt)	Use	Average PCI	Standard Deviation PCI	Weighted Average PCI
AP	8	3,580.00	110.00	333,362.00	APRON	75.88	24.76	67.02
AP FUEL	1	200.00	50.00	6,767.00	APRON	85.00	0.00	85.00
AP HELI	1	240.00	92.00	21,255.00	APRON	63.00	0.00	63.00
AP MID	2	630.00	142.50	100,784.00	APRON	87.50	2.50	89.24
AP NW	4	931.00	115.75	130,334.00	APRON	78.50	8.56	74.63
RW 18-36	1	2,864.00	75.00	217,732.00	RUNWAY	100.00	0.00	100.00
RW 7-25	8	3,579.00	75.00	268,375.00	RUNWAY	87.63	8.20	82.05
TW A	6	3,075.00	41.67	123,682.00	TAXIWAY	64.83	25.52	53.28
TW A1	1	95.00	40.00	4,672.00	TAXIWAY	86.00	0.00	86.00
TW A2	1	95.00	41.00	5,577.00	TAXIWAY	90.00	0.00	90.00
TW A3	1	95.00	41.00	5,518.00	TAXIWAY	89.00	0.00	89.00
TW A4	2	395.00	35.50	16,668.00	TAXIWAY	88.00	1.00	87.66
TW B	3	2,665.00	43.33	112,508.00	TAXIWAY	61.00	11.05	58.91
TW B1	2	96.00	35.00	3,388.00	TAXIWAY	100.00	0.00	100.00
TW B2	2	117.00	42.50	6,176.00	TAXIWAY	100.00	0.00	100.00
TW B3	2	117.00	42.50	6,176.00	TAXIWAY	100.00	0.00	100.00
TW B4	2	157.00	40.00	6,955.00	TAXIWAY	100.00	0.00	100.00
TW C	3	2,175.00	57.33	138,374.00	TAXIWAY	65.00	20.51	74.14
TW D	5	2,560.00	37.40	71,043.00	TAXIWAY	89.20	14.40	76.83
TW D1	1	115.00	50.00	6,159.00	TAXIWAY	65.00	0.00	65.00
TW D2	1	405.00	55.00	29,398.00	TAXIWAY	86.00	0.00	86.00
TW D3	2	126.00	30.00	5,696.00	TAXIWAY	64.50	3.50	63.34
TW D5	1	92.00	62.00	5,816.00	TAXIWAY	90.00	0.00	90.00

11/17/2022**Branch Condition Report****Page 2 of 2***Pavement Database: FDOT*

Use Category	Number of Sections	Total Area (SqFt)	Arithmetic Average PCI	Average STD PCI	Weighted Average PCI
APRON	16	592,502.00	77.75	18.88	72.53
RUNWAY	9	486,107.00	89.00	8.65	90.09
TAXIWAY	35	547,806.00	80.69	20.38	69.14
ALL	60	1,626,415.00	81.15	19.00	76.64

Pavement Database: FDOT

NetworkId: SPG

Branch ID	Section ID	Last Const. Date	Surface	Use	Rank	Lanes	True Area (SqFt)	Last Inspection Date	Age At Inspection	PCI
AP	4110	1/1/1993	AC	APRON	P	0	126,574.00	4/6/2022	29	42
AP	4120	1/1/2002	AAC	APRON	P	0	33,335.00	4/6/2022	20	50
AP	4135	1/1/2002	AAC	APRON	P	0	42,820.00	4/6/2022	20	64
AP	4145	1/1/2002	AAC	APRON	P	0	9,084.00	4/6/2022	20	51
AP	4150	7/1/2021	AAC	APRON	P	0	5,101.00	7/1/2021	0	100
AP	4155	7/1/2021	AAC	APRON	P	0	41,633.00	7/1/2021	0	100
AP	4160	7/1/2020	AC	APRON	P	0	37,874.00	7/1/2020	0	100
AP	4165	7/1/2021	AAC	APRON	P	0	36,941.00	7/1/2021	0	100
AP FUEL	4510	1/1/2013	AC	APRON	P	0	6,767.00	4/6/2022	9	85
AP HELI	4610	1/1/2006	AC	APRON	P	0	21,255.00	4/6/2022	16	63
AP MID	4405	1/1/2013	AC	APRON	P	0	85,370.00	4/6/2022	9	90
AP MID	4410	1/1/2013	AC	APRON	P	0	15,414.00	4/6/2022	9	85
AP NW	4310	1/1/2006	AC	APRON	P	0	76,197.00	4/6/2022	16	68
AP NW	4315	1/1/2011	AC	APRON	P	0	35,173.00	4/6/2022	11	83
AP NW	4320	1/1/2002	AC	APRON	P	0	4,732.00	4/6/2022	20	73
AP NW	4325	1/1/2018	AAC	APRON	P	0	14,232.00	4/6/2022	4	90
RW 18-36	6105	4/1/2022	AAC	RUNWAY	P	0	217,732.00	4/1/2022	0	100
RW 7-25	6205	6/1/2016	AAC	RUNWAY	P	0	18,375.00	4/6/2022	6	88
RW 7-25	6207	6/1/2016	AAC	RUNWAY	P	0	22,950.00	4/6/2022	6	79
RW 7-25	6208	6/1/2016	AAC	RUNWAY	P	0	21,525.00	4/6/2022	6	80
RW 7-25	6210	6/1/2016	AAC	RUNWAY	P	0	147,650.00	4/6/2022	6	79
RW 7-25	6213	6/1/2016	AC	RUNWAY	P	0	19,590.00	4/6/2022	6	84
RW 7-25	6215	6/1/2016	AAC	RUNWAY	P	0	30,125.00	4/6/2022	6	91
RW 7-25	6220	4/1/2022	AAC	RUNWAY	P	0	2,875.00	4/1/2022	0	100
RW 7-25	6225	4/1/2022	AAC	RUNWAY	P	0	5,285.00	4/1/2022	0	100
TW A	103	1/1/1991	AC	TAXIWAY	P	0	17,162.00	4/6/2022	31	50
TW A	105	1/1/1987	AAC	TAXIWAY	P	0	15,000.00	4/6/2022	35	38
TW A	110	1/1/1987	AAC	TAXIWAY	P	0	21,000.00	4/6/2022	35	44
TW A	115	1/1/1987	AAC	TAXIWAY	P	0	65,457.00	4/6/2022	35	57
TW A	125	4/1/2022	AAC	TAXIWAY	P	0	1,540.00	4/1/2022	0	100
TW A	130	4/1/2022	AAC	TAXIWAY	P	0	3,523.00	4/1/2022	0	100
TW A1	120	6/1/2016	AC	TAXIWAY	P	0	4,672.00	4/6/2022	6	86
TW A2	410	6/1/2016	AC	TAXIWAY	P	0	5,577.00	4/6/2022	6	90
TW A3	310	6/1/2016	AC	TAXIWAY	P	0	5,518.00	4/6/2022	6	89
TW A4	610	6/1/2016	AC	TAXIWAY	P	0	5,518.00	4/6/2022	6	89
TW A4	620	1/1/2013	AC	TAXIWAY	P	0	11,150.00	4/6/2022	9	87
TW B	205	1/1/1988	AAC	TAXIWAY	P	0	87,871.00	4/6/2022	34	60
TW B	210	1/1/1988	AAC	TAXIWAY	P	0	18,217.00	4/6/2022	34	48
TW B	215	6/1/2016	AC	TAXIWAY	P	0	6,420.00	4/6/2022	6	75
TW B1	250	4/1/2022	AAC	TAXIWAY	P	0	1,246.00	4/1/2022	0	100
TW B1	255	4/1/2022	AAC	TAXIWAY	P	0	2,142.00	4/1/2022	0	100
TW B2	260	4/1/2022	AC	TAXIWAY	P	0	3,445.00	4/1/2022	0	100
TW B2	265	4/1/2022	AAC	TAXIWAY	P	0	2,731.00	4/1/2022	0	100
TW B3	270	4/1/2022	AC	TAXIWAY	P	0	3,445.00	4/1/2022	0	100
TW B3	275	4/1/2022	AAC	TAXIWAY	P	0	2,731.00	4/1/2022	0	100
TW B4	280	4/1/2022	AC	TAXIWAY	P	0	4,813.00	4/1/2022	0	100
TW B4	285	4/1/2022	AAC	TAXIWAY	P	0	2,142.00	4/1/2022	0	100
TW C	305	5/25/2018	AC	TAXIWAY	P	0	75,170.00	4/6/2022	4	94

TW C	307	1/1/1991	AAC	TAXIWAY	P	0	29,730.00	4/6/2022	31	50
TW C	308	1/1/1991	AAC	TAXIWAY	P	0	33,474.00	4/6/2022	31	51
TW D	155	11/1/2021	AAC	TAXIWAY	P	0	8,835.00	11/1/2021	0	100
TW D	157	4/1/2022	AAC	TAXIWAY	P	0	3,327.00	4/1/2022	0	100
TW D	160	4/1/2022	AAC	TAXIWAY	P	0	1,353.00	4/1/2022	0	100
TW D	510	1/1/2002	AC	TAXIWAY	P	0	33,920.00	4/6/2022	20	64
TW D	515	1/1/2011	AC	TAXIWAY	P	0	23,608.00	4/6/2022	11	82
TW D1	450	1/1/2006	AC	TAXIWAY	P	0	6,159.00	4/6/2022	16	65
TW D2	740	7/1/2019	AAC	TAXIWAY	P	0	29,398.00	4/6/2022	3	86
TW D3	470	1/1/2011	AC	TAXIWAY	P	0	3,795.00	4/6/2022	11	61
TW D3	475	1/1/2006	AC	TAXIWAY	P	0	1,901.00	4/6/2022	16	68
TW D5	150	6/1/2016	AAC	TAXIWAY	P	0	5,816.00	4/6/2022	6	90

Pavement Database: FDOT

Age Category	Average Age at Inspection	Total Area (SqFt)	Number of Sections	Arithmetic Average PCI	Standard Deviation PCI	Weighted Average PCI
00-02		388,714.00	20	100.00	0.00	100.00
03-05	4	118,800.00	3	90.00	3.27	91.54
06-10	7	412,437.00	16	85.44	4.69	83.97
11-15	11	62,576.00	3	75.33	10.14	81.29
16-20	18	229,403.00	9	62.89	7.22	62.93
26-30	29	126,574.00	1	42.00	0.00	42.00
31-35	33	287,911.00	8	49.75	6.46	53.57
ALL	10	1,626,415.00	60	81.15	19.00	76.64



Appendix B: Maintenance and Rehabilitation Planning Needs



Table B.1: Localized Maintenance and Repair Needs Based on Current Distresses

Network ID	Branch ID	Section ID	Description	Severity	Distress Qty	Distress Unit	Distress Density	Policy Type	Localized Work Type	Work Qty	Work Unit	Unit Cost	Work Cost
SPG	TW A4	620	WEATHERING	Medium	557	SF	5.0%	Preventive	Surface Seal	558	SF	\$ 0.75	\$ 420
SPG	TW D	515	WEATHERING	Medium	1,180	SF	5.0%	Preventive	Surface Seal	1,181	SF	\$ 0.75	\$ 890
SPG	AP FUEL	4510	WEATHERING	Medium	677	SF	10.0%	Preventive	Surface Seal	677	SF	\$ 0.75	\$ 510
SPG	AP MID	4405	WEATHERING	Medium	4,269	SF	5.0%	Preventive	Surface Seal	4,269	SF	\$ 0.75	\$ 3,210
SPG	AP MID	4410	WEATHERING	Medium	773	SF	5.0%	Preventive	Surface Seal	773	SF	\$ 0.75	\$ 580
SPG	AP NW	4315	WEATHERING	Medium	5,272	SF	15.0%	Preventive	Surface Seal	5,272	SF	\$ 0.75	\$ 3,960
SPG	AP NW	4320	WEATHERING	Medium	4,732	SF	100.0%	Preventive	Surface Seal	4,732	SF	\$ 0.75	\$ 3,550
SPG	TW A	103	RAVELING	High	26	SF	0.2%	Stopgap	AC Partial-Depth Patching	26	SF	\$ 4.75	\$ 130
SPG	TW A	105	L & T CR	High	38	LF	0.3%	Stopgap	AC Full-Depth Patching	123	SF	\$ 11.50	\$ 1,420
SPG	AP	4110	RAVELING	High	47	SF	0.0%	Stopgap	AC Partial-Depth Patching	47	SF	\$ 4.75	\$ 230

Table B.2: Section-Level 10-Year Major Rehabilitation Needs



Program Year	Network ID	Branch ID	Section ID	Surface	Area (SF)	PCI Before	Rehabilitation Type	Planning Cost Estimate
2023	SPG	TW A	103	AC	17,162	49	AC Reconstruction	\$ 318,000
2023	SPG	TW A	105	AAC	15,000	36	AC Reconstruction	\$ 278,000
2023	SPG	TW A	110	AAC	21,000	42	AC Reconstruction	\$ 389,000
2023	SPG	TW A	115	AAC	65,457	56	AC Rehabilitation	\$ 688,000
2023	SPG	TW B	205	AAC	87,871	59	AC Rehabilitation	\$ 923,000
2023	SPG	TW B	210	AAC	18,217	47	AC Reconstruction	\$ 338,000
2023	SPG	TW C	307	AAC	29,730	49	AC Reconstruction	\$ 550,000
2023	SPG	TW C	308	AAC	33,474	50	AC Reconstruction	\$ 620,000
2023	SPG	TW D	510	AC	33,920	63	AC Rehabilitation	\$ 357,000
2023	SPG	TW D1	450	AC	6,159	64	AC Rehabilitation	\$ 65,000
2023	SPG	TW D3	470	AC	3,795	60	AC Rehabilitation	\$ 40,000
2023	SPG	TW D3	475	AC	1,901	67	AC Rehabilitation	\$ 20,000
2023	SPG	AP	4110	AC	126,574	40	AC Reconstruction	\$ 2,342,000
2023	SPG	AP	4120	AAC	33,335	47	AC Reconstruction	\$ 617,000
2023	SPG	AP	4135	AAC	42,820	61	AC Rehabilitation	\$ 450,000
2023	SPG	AP	4145	AAC	9,084	48	AC Reconstruction	\$ 169,000
2023	SPG	AP HELI	4610	AC	21,255	62	AC Rehabilitation	\$ 224,000
2023	SPG	AP NW	4310	AC	76,197	66	AC Rehabilitation	\$ 801,000
2024	SPG	AP NW	4320	AC	4,732	69	AC Rehabilitation	\$ 53,000
2027	SPG	RW 7-25	6207	AAC	22,950	70	AC Rehabilitation	\$ 293,000
2027	SPG	RW 7-25	6210	AAC	147,650	70	AC Rehabilitation	\$ 1,885,000
2027	SPG	TW B	215	AC	6,420	69	AC Rehabilitation	\$ 82,000
2028	SPG	RW 7-25	6208	AAC	21,525	69	AC Rehabilitation	\$ 289,000
2029	SPG	AP NW	4315	AC	35,173	70	AC Rehabilitation	\$ 495,000
2030	SPG	AP FUEL	4510	AC	6,767	70	AC Rehabilitation	\$ 100,000
2030	SPG	AP MID	4410	AC	15,414	70	AC Rehabilitation	\$ 228,000
2031	SPG	TW D	515	AC	23,608	70	AC Rehabilitation	\$ 367,000
2031	SPG	AP NW	4325	AAC	14,232	70	AC Rehabilitation	\$ 221,000
2032	SPG	TW D2	740	AAC	29,398	70	AC Rehabilitation	\$ 479,000

*All planning cost values have been rounded up to the nearest thousand dollars.



Appendix C: Technical Exhibits





AAC RW 7-25 6205 2 5	AAC RW 7-25 6208 2 6	AAC RW 7-25 6210 8 39	AC RW 7-25 6213 2 5	AAC RW 7-25 6220 0 1	AAC RW 7-25 6225 0 1	AC TW A 103 1 4	AAC TW A 105 1 4
AAC TW A 110 2 5	AAC TW A 125 0 1	AAC TW A 130 0 1	AC TW A2 410 1 1	AC TW A3 310 1 1	AC TW A4 610 1 1	AC TW A4 620 1 3	AC TW B2 260 0 1
AAC TW B2 265 0 1	AC TW B3 270 0 1	AAC TW B3 275 0 1	AAC TW C 308 1 7	AAC TW D 157 0 1	AAC TW D 160 0 1	AC AP MID 4405 3 18	AC AP MID 4410 1 4

LEGEND

- RW 13-31 — TYPICAL RUNWAY BRANCH ID
- TW A — TYPICAL TAXIWAY BRANCH ID
- AP S — TYPICAL APRON BRANCH ID
- AAC — PAVEMENT SURFACE TYPE
- AP MAIN — PAVEMENT BRANCH ID
- 4105 — SECTION NUMBER
- 100 — NUMBER OF SAMPLE UNITS IN SECTION
- 100 — NUMBER OF SAMPLE UNITS TO BE INSPECTED
- AAC AP MAIN 4105 100 — SECTION NOT INSPECTED DUE TO RECENT CONSTRUCTION. SEE SYSTEM INVENTORY MAP FOR CONSTRUCTION DATES.
- 100 — INSPECTED SAMPLE UNITS.

TOTAL SAMPLES INSPECTED = 65
AC: 65 PCC: 0

RUNWAY LENGTHS DEPICTED IN THIS DRAWING ARE FOR PAVEMENT MANAGEMENT PURPOSES ONLY AND MAY NOT MATCH PUBLISHED RUNWAY LENGTHS. DRAWING NOT TO SCALE.



RECENT & ANTICIPATED CONSTRUCTION ACTIVITY		
CONSTRUCTION YEAR	LOCATION	WORK TYPE / PAVEMENT SECTION
2018	AP NW	Mill and Overlay
	TW C	Complete Reconstruction - AC 3" P-403, 6-10" Reclaimed Base
2019	TW D2	Mill and Overlay
2020	AP	New Construction - AC 2" P-402, 5" P-219
2021	AP, TW D	Mill and Overlay Variable depth mill, Variable depth P-403 overlay
2022	RW 18-36, RW 7-25, TW A, TW B1, TW B2, TW B3, TW B4, TW D	Mill and Overlay 1.5" Variable cold milling, 2" P-403 Overlay
	TW B2, TW B3, TW B4	New Construction - AC 4" P-403, 6" P-211, 12" P-152

LEGEND

RW 13-31 — TYPICAL RUNWAY BRANCH ID


TW A — TYPICAL TAXIWAY BRANCH ID

AP S — TYPICAL APRON BRANCH ID

PROJECT YEAR

2017	2022
2018	2023
2019	2024
2020	2025
2021	2026

RUNWAY LENGTHS DEPICTED IN THIS DRAWING ARE FOR PAVEMENT MANAGEMENT PURPOSES ONLY AND MAY NOT MATCH PUBLISHED RUNWAY LENGTHS. DRAWING NOT TO SCALE.



LEGEND

TYPICAL RUNWAY BRANCH ID

TYPICAL TAXIWAY BRANCH ID

TYPICAL APRON BRANCH ID

AGE AT INSPECTION

	0-5 Years
	6-10 Years
	11-15 Years
	16-20 Years
	> 20 Years

RUNWAY LENGTHS DEPICTED IN THIS DRAWING ARE FOR PAVEMENT MANAGEMENT PURPOSES ONLY AND MAY NOT MATCH PUBLISHED RUNWAY LENGTHS. DRAWING NOT TO SCALE.



LEGEND


- RW 13-31 — TYPICAL RUNWAY BRANCH ID
- TW A — TYPICAL TAXIWAY BRANCH ID
- AP S — TYPICAL APRON BRANCH ID

2022 PAVEMENT CONDITION INDEX

- PCI 86-100 Good
- PCI 71-85 Satisfactory
- PCI 56-70 Fair
- PCI 41-55 Poor
- PCI 26-40 Very Poor
- PCI 11-25 Serious
- PCI 0-10 Failed

"SECTION ID"
"PCI VALUE"

RUNWAY LENGTHS DEPICTED IN THIS DRAWING ARE FOR PAVEMENT MANAGEMENT PURPOSES ONLY AND MAY NOT MATCH PUBLISHED RUNWAY LENGTHS. DRAWING NOT TO SCALE.



LEGEND

RW 13-31 — TYPICAL RUNWAY BRANCH ID

TW A — TYPICAL TAXIWAY BRANCH ID

AP S — TYPICAL APRON BRANCH ID

PROGRAM YEAR

2023	2028
2024	2029
2025	2030
2026	2031
2027	2032

"BRANCH", "SECTION"
"YEAR", "REHAB ACTIVITY"
"EST. COST"

RUNWAY LENGTHS DEPICTED IN THIS DRAWING ARE FOR PAVEMENT MANAGEMENT PURPOSES ONLY AND MAY NOT MATCH PUBLISHED RUNWAY LENGTHS. DRAWING NOT TO SCALE.



Appendix D: Inspection Photograph Documentation





RW 7-25, Section 6208, Sample Unit 158 – Longitudinal & Transverse Cracking



RW 7-25, Section 6210, Sample Unit 136 – Longitudinal & Transverse Cracking



TW A, Section 105, Sample Unit 103 – Longitudinal & Transverse Cracking, Swelling, and Raveling



TW B, Section 205, Sample Unit 108– Longitudinal & Transverse Cracking



TW C, Section 307, Sample Unit 209 – Block Cracking and Swelling



TW D, Section 510, Sample Unit 232 – Vicinity



AP, Section 4110, Sample Unit 207 – Block Cracking



AP NW, Section 4310, Sample Unit 200 – Longitudinal & Transverse Cracking and Swelling



Appendix E: Inspection Distress Details



Re-Inspection Report

FDOT

Generated Date 11/17/2022

Page 1 of 66

Network:	SPG	Name:	ALBERT WHITTED AIRPORT				
Branch:	AP	Name:	APRON	Use:	APRON	Area:	333,362 SqFt
Section:	4110	of	8	From:	-	To:	-
Surface:	AC	Family:	CA653-RL-AP-AC	Zone:		Category:	
Area:	126,574 SqFt	Length:	485 Ft	Width:	270 Ft	Rank:	P
Slabs:		Slab Length:	Ft	Slab Width:	Ft	Joint Length:	Ft
Shoulder:		Street Type:		Grade:	0	Lanes:	0
Section Comments:							

Work Date:	1/1/1993	Work Type:	New Construction - AC	Code:	NC-AC	Is Major M&R:	True
-------------------	----------	-------------------	-----------------------	--------------	-------	--------------------------	------

Last Insp. Date:	4/6/2022	TotalSamples:	23	Surveyed:	3
-------------------------	----------	----------------------	----	------------------	---

Conditions: PCI: 42

Inspection Comments:

Sample Number:	204	Type:	R	Area:	3746.00 SqFt	PCI:	39
-----------------------	-----	--------------	---	--------------	--------------	-------------	----

Sample Comments:

43	BLOCK CR	L	592.00	SqFt
48	L & T CR	L	180.00	Ft
52	RAVELING	L	1498.00	SqFt
52	RAVELING	M	2248.00	SqFt

Sample Number:	207	Type:	R	Area:	5917.00 SqFt	PCI:	36
-----------------------	-----	--------------	---	--------------	--------------	-------------	----

Sample Comments:

43	BLOCK CR	L	3778.00	SqFt
43	BLOCK CR	M	1259.00	SqFt
50	PATCHING	L	880.00	SqFt
52	RAVELING	L	4528.00	SqFt
52	RAVELING	M	503.00	SqFt
52	RAVELING	H	6.00	SqFt

Sample Number:	309	Type:	R	Area:	6378.00 SqFt	PCI:	49
-----------------------	-----	--------------	---	--------------	--------------	-------------	----

Sample Comments:

43	BLOCK CR	L	750.00	SqFt
48	L & T CR	L	128.00	Ft
48	L & T CR	M	200.00	Ft
52	RAVELING	L	6314.00	SqFt
52	RAVELING	M	64.00	SqFt
54	SHOVING	L	50.00	SqFt

Network:	SPG			Name:	ALBERT WHITTED AIRPORT										
Branch:	AP		Name:	APRON		Use:	APRON		Area:	333,362 SqFt					
Section:	4120		of	8		From:	-		To:	-		Last Const.:	1/1/2002		
Surface:	AAC		Family:	CA653-RL-AP-AAC-APC				Zone:			Category:	Rank: P			
Area:	33,335 SqFt			Length:	300 Ft			Width:	85 Ft						
Slabs:				Slab Length:	Ft			Slab Width:	Ft			Joint Length:	Ft		
Shoulder:				Street Type:				Grade:	0			Lanes:	0		
Section Comments:															
Work Date:	1/1/1965			Work Type:	BUILT				Code:	IMPORTED			Is Major M&R:	True	
Work Date:	1/1/2002			Work Type:	Mill and Overlay				Code:	ML-OVL			Is Major M&R:	True	
Work Date:	1/1/2018			Work Type:	Patching - AC				Code:	PA-AC			Is Major M&R:	False	
Last Insp. Date:	4/6/2022			TotalSamples:	6			Surveyed:	1						
Conditions:	PCI: 50														
Inspection Comments:															
Sample Number:	212		Type:	R		Area:	6950.00 SqFt			PCI:	50				
Sample Comments:															
43	BLOCK CR		L	345.00		SqFt									
45	DEPRESSION		L	45.00		SqFt									
48	L & T CR		L	42.00		Ft									
48	L & T CR		M	289.00		Ft									
52	RAVELING		L	6899.00		SqFt									
52	RAVELING		M	51.00		SqFt									
54	SHOVING		L	28.00		SqFt									

Network:	SPG			Name:	ALBERT WHITTED AIRPORT									
Branch:	AP		Name:	APRON		Use:	APRON		Area:	333,362 SqFt				
Section:	4135		of	8		From:	-		To:	-		Last Const.:	1/1/2002	
Surface:	AAC		Family:	CA653-RL-AP-AAC-APC		Zone:			Category:			Rank:	P	
Area:	42,820 SqFt		Length:	1,535 Ft		Width:	20 Ft							
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:			Ft		
Shoulder:			Street Type:			Grade:	0		Lanes:	0				
Section Comments:														
Work Date:	12/25/1999		Work Type:	New Construction - Initial				Code:	NU-IN		Is Major M&R:	True		
Work Date:	1/1/2002		Work Type:	Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True		
Last Insp. Date:	4/6/2022		TotalSamples:	10		Surveyed:	1							
Conditions:	PCI: 64													
Inspection Comments:														
Sample Number:	405		Type:	R		Area:	4811.00 SqFt		PCI:	64				
Sample Comments:														
48	L & T CR		L	181.00 Ft										
48	L & T CR		M	48.00 Ft										
52	RAVELING		L	4811.00 SqFt										

Network:	SPG		Name:	ALBERT WHITTED AIRPORT						
Branch:	AP		Name:	APRON		Use:	APRON	Area:	333,362 SqFt	
Section:	4145		of	8	From:	-		To:	-	
Surface:	AAC		Family:	CA653-RL-AP-AAC-APC		Zone:			Category:	Rank: P
Area:	9,084 SqFt		Length:	210 Ft		Width:	40 Ft			
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft
Shoulder:			Street Type:			Grade:	0		Lanes:	0
Section Comments:										
Work Date:	1/1/1965		Work Type:	New Construction - Initial				Code:	NU-IN	
Work Date:	1/1/2002		Work Type:	Mill and Overlay				Code:	ML-OVL	
Last Insp. Date:	4/6/2022		TotalSamples:	2		Surveyed:	1			
Conditions:	PCI: 51									
Inspection Comments:										
Sample Number:	352		Type:	R		Area:	4518.00 SqFt		PCI:	51
Sample Comments:										
45	DEPRESSION		L	84.00 SqFt						
48	L & T CR		L	138.00 Ft						
48	L & T CR		M	102.00 Ft						
52	RAVELING		L	3614.00 SqFt						
52	RAVELING		M	904.00 SqFt						

Network:	SPG			Name:	ALBERT WHITTED AIRPORT				
Branch:	AP		Name:	APRON		Use:	APRON	Area:	333,362 SqFt
Section:	4150	of	8	From:	-	To:	-	Last Const.:	7/1/2021
Surface:	AAC	Family:	CA653-RL-AP-AAC-APC		Zone:		Category:		Rank: P
Area:	5,101 SqFt	Length:	40 Ft		Width:	130 Ft			
Slabs:		Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft
Shoulder:		Street Type:			Grade:	0		Lanes:	0
Section Comments:									
Work Date:	1/1/1965		Work Type: New Construction - Initial				Code:	NU-IN	Is Major M&R: True
Work Date:	1/1/2002		Work Type: Mill and Overlay				Code:	ML-OVL	Is Major M&R: True
Work Date:	7/1/2021		Work Type: Mill and Overlay				Code:	ML-OVL	Is Major M&R: True
Last Insp. Date:	12/11/2018		TotalSamples:	3		Surveyed:	1		
Conditions:	PCI: 49		NOTE: *** Pre-Construction PCI ***						
Inspection Comments:									
Sample Number:	352	Type:	R	Area:	4518.00 SqFt		PCI:	49	
Sample Comments:									
43	BLOCK CR	L	375.00	SqFt					
45	DEPRESSION	L	128.00	SqFt					
48	L & T CR	L	176.00	Ft					
52	RAVELING	L	4292.00	SqFt					
52	RAVELING	M	226.00	SqFt					
56	SWELLING	L	250.00	SqFt					

Network:	SPG			Name:	ALBERT WHITTED AIRPORT												
Branch:	AP		Name:	APRON		Use:	APRON		Area:	333,362 SqFt							
Section:	4155		of	8		From:	-		To:	-		Last Const.:	7/1/2021				
Surface:	AAC		Family:	CA653-RL-AP-AAC-APC			Zone:				Category:				Rank:	P	
Area:	41,633 SqFt			Length:	330 Ft			Width:	130 Ft								
Slabs:				Slab Length:	Ft			Slab Width:	Ft			Joint Length:	Ft				
Shoulder:				Street Type:				Grade:	0			Lanes:	0				
Section Comments:																	
Work Date:	1/1/1965			Work Type:	BUILT			Code:	IMPORTED			Is Major M&R:	True				
Work Date:	1/1/2002			Work Type:	Mill and Overlay			Code:	ML-OVL			Is Major M&R:	True				
Work Date:	1/1/2018			Work Type:	Patching - AC			Code:	PA-AC			Is Major M&R:	False				
Work Date:	7/1/2021			Work Type:	Mill and Overlay			Code:	ML-OVL			Is Major M&R:	True				
Last Insp. Date:	12/11/2018			TotalSamples:	15			Surveyed:	3								
Conditions:	PCI: 43			NOTE: *** Pre-Construction PCI ***													
Inspection Comments:																	
Sample Number:	212		Type:	R		Area:	6950.00 SqFt			PCI:	51						
Sample Comments:																	
45	DEPRESSION		L	36.00		SqFt											
48	L & T CR		L	357.00		Ft											
48	L & T CR		M	70.00		Ft											
52	RAVELING		L	6886.00		SqFt											
52	RAVELING		M	64.00		SqFt											
54	SHOVING		L	34.00		SqFt											
Sample Number:	354		Type:	R		Area:	4590.00 SqFt			PCI:	45						
Sample Comments:																	
43	BLOCK CR		L	4338.00		SqFt											
45	DEPRESSION		L	45.00		SqFt											
50	PATCHING		L	252.00		SqFt											
52	RAVELING		L	211.00		SqFt											
52	RAVELING		M	162.00		SqFt											
Sample Number:	455		Type:	R		Area:	5000.00 SqFt			PCI:	30						
Sample Comments:																	
41	ALLIGATOR CR		M	468.00		SqFt											
43	BLOCK CR		L	3943.00		SqFt											
50	PATCHING		L	589.00		SqFt											
52	RAVELING		M	150.00		SqFt											

Network:	SPG			Name:	ALBERT WHITTED AIRPORT							
Branch:	AP		Name:	APRON		Use:	APRON		Area:	333,362 SqFt		
Section:	4165		of	8		From:	-		To:	-		
Surface:	AAC		Family:	CA653-RL-AP-AAC-APC		Zone:			Category:			
Area:	36,941 SqFt		Length:	420 Ft		Width:	60 Ft					
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:			Street Type:			Grade:	0		Lanes:	0		
Section Comments:												
Work Date:	12/25/1999		Work Type:	New Construction - Initial				Code:	NU-IN		Is Major M&R:	True
Work Date:	1/1/2002		Work Type:	Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True
Work Date:	7/1/2021		Work Type:	Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True
Last Insp. Date:	12/11/2018		TotalSamples:	18		Surveyed:	3					
Conditions:	PCI: 63		NOTE: *** Pre-Construction PCI ***									
Inspection Comments:												
Sample Number:	201		Type:	R		Area:	3572.00 SqFt		PCI:	52		
Sample Comments:												
45	DEPRESSION		L	110.00 SqFt								
48	L & T CR		L	115.00 Ft								
48	L & T CR		M	76.00 Ft								
50	PATCHING		L	25.00 SqFt								
50	PATCHING		M	240.00 SqFt								
52	RAVELING		L	3307.00 SqFt								
56	SWELLING		L	10.00 SqFt								
Sample Number:	303		Type:	R		Area:	4172.00 SqFt		PCI:	66		
Sample Comments:												
48	L & T CR		L	96.00 Ft								
52	RAVELING		L	4172.00 SqFt								
56	SWELLING		L	30.00 SqFt								
Sample Number:	405		Type:	R		Area:	5302.00 SqFt		PCI:	69		
Sample Comments:												
48	L & T CR		L	224.00 Ft								
52	RAVELING		L	5302.00 SqFt								

Network:	SPG			Name:	ALBERT WHITTED AIRPORT									
Branch:	AP FUEL		Name:	FUEL APRON		Use:	APRON		Area:	6,767 SqFt				
Section:	4510		of	1		From:	-		To:	-		Last Const.:	1/1/2013	
Surface:	AC		Family:	CA653-RL-AP-AC		Zone:			Category:			Rank:	P	
Area:	6,767 SqFt		Length:	200 Ft		Width:	50 Ft							
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft				
Shoulder:			Street Type:			Grade:	0		Lanes:	0				
Section Comments:														
Work Date:	1/1/2013		Work Type:	New Construction - Initial				Code:	NU-IN		Is Major M&R:	True		
Last Insp. Date:	4/6/2022		TotalSamples:	2		Surveyed:	1							
Conditions:	PCI: 85													
Inspection Comments:														
Sample Number:	306		Type:	R		Area:	3498.00 SqFt		PCI:	85				
Sample Comments:														
48	L & T CR		L	25.00		Ft								
57	WEATHERING		L	3148.00		SqFt								
57	WEATHERING		M	350.00		SqFt								

Network:	SPG		Name:	ALBERT WHITTED AIRPORT							
Branch:	AP HELI		Name:	HELICOPTER PARKING APRON		Use:	APRON	Area:	21,255 SqFt		
Section:	4610	of 1	From:	-			To:	-		Last Const.:	1/1/2006
Surface:	AC	Family:	CA653-RL-AP-AC		Zone:		Category:		Rank:	P	
Area:	21,255 SqFt	Length:	240 Ft		Width:	92 Ft					
Slabs:		Slab Length:	Ft	Slab Width:	Ft	Joint Length:	Ft				
Shoulder:		Street Type:		Grade:	0	Lanes:	0				
Section Comments:											
Work Date:	1/1/2006		Work Type:	New Construction - AC			Code:	NC-AC	Is Major M&R:	True	
Last Insp. Date:	4/6/2022		TotalSamples:	5		Surveyed:	1				
Conditions:	PCI:	63									
Inspection Comments:											
Sample Number:	101	Type:	R	Area:	4530.00 SqFt		PCI:	63			
Sample Comments:											
45	DEPRESSION	L	55.00 SqFt								
48	L & T CR	L	274.00 Ft								
48	L & T CR	M	73.00 Ft								
57	WEATHERING	L	4077.00 SqFt								
57	WEATHERING	M	453.00 SqFt								

Network:	SPG		Name:	ALBERT WHITTED AIRPORT					
Branch:	AP MID		Name:	APRON MIDFIELD		Use:	APRON	Area:	100,784 SqFt
Section:	4405	of 2	From:	-			To:	-	Last Const.: 1/1/2013
Surface:	AC	Family:	CA653-RL-AP-AC		Zone:		Category:		Rank: P
Area:	85,370 SqFt		Length:	450 Ft		Width:	200 Ft		
Slabs:	Slab Length:		Ft		Slab Width:	Ft		Joint Length:	Ft
Shoulder:	Street Type:				Grade:	0		Lanes:	0
Section Comments:									
Work Date:	1/1/2013		Work Type: New Construction - Initial			Code:	NU-IN		Is Major M&R: True
Last Insp. Date:	4/6/2022		TotalSamples:	18		Surveyed:	3		
Conditions:	PCI:	90							
Inspection Comments:									
Sample Number:	101	Type:	R	Area:	5000.00 SqFt		PCI:	89	
Sample Comments:									
49	OIL SPILLAGE	N	2.00 SqFt						
57	WEATHERING	L	4750.00 SqFt						
57	WEATHERING	M	250.00 SqFt						
Sample Number:	106	Type:	R	Area:	5000.00 SqFt		PCI:	91	
Sample Comments:									
57	WEATHERING	L	4750.00 SqFt						
57	WEATHERING	M	250.00 SqFt						
Sample Number:	112	Type:	R	Area:	5000.00 SqFt		PCI:	90	
Sample Comments:									
56	SWELLING	L	2.00 SqFt						
57	WEATHERING	L	4750.00 SqFt						
57	WEATHERING	M	250.00 SqFt						

Network:	SPG			Name:	ALBERT WHITTED AIRPORT									
Branch:	AP MID		Name:	APRON MIDFIELD		Use:	APRON		Area:	100,784 SqFt				
Section:	4410		of	2	From:	-			To:	-		Last Const.:	1/1/2013	
Surface:	AC		Family:	CA653-RL-AP-AC		Zone:				Category:	Rank: P			
Area:	15,414 SqFt		Length:	180 Ft		Width:	85 Ft							
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft				
Shoulder:			Street Type:			Grade:	0		Lanes:	0				
Section Comments:														
Work Date:	1/1/2013		Work Type:	New Construction - Initial				Code:	NU-IN		Is Major M&R:	True		
Last Insp. Date:	4/6/2022		TotalSamples:	4		Surveyed:	1							
Conditions:	PCI: 85													
Inspection Comments:														
Sample Number:	123		Type:	R		Area:	4250.00 SqFt		PCI:	85				
Sample Comments:														
48	L & T CR		L	16.00 Ft										
56	SWELLING		L	15.00 SqFt										
57	WEATHERING		L	4037.00 SqFt										
57	WEATHERING		M	213.00 SqFt										

Network:	SPG		Name:	ALBERT WHITTED AIRPORT								
Branch:	AP NW		Name:	NORTHWEST APRON		Use:	APRON		Area:	130,334 SqFt		
Section:	4310		of	4		From:	-		To:	-		
Surface:	AC		Family:	CA653-RL-AP-AC		Zone:			Category:			
Area:	76,197 SqFt		Length:	365 Ft		Width:	155 Ft					
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:			Street Type:			Grade:	0		Lanes:	0		
Section Comments:												
Work Date:	1/1/2006		Work Type:	New Construction - Initial				Code:	NU-IN		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	16				Surveyed:	3			
Conditions:	PCI: 68											
Inspection Comments:												
Sample Number:	200		Type:	R		Area:	5000.00 SqFt		PCI:	63		
Sample Comments:												
48	L & T CR		L	328.00 Ft								
48	L & T CR		M	50.00 Ft								
56	SWELLING		L	75.00 SqFt								
57	WEATHERING		L	4250.00 SqFt								
57	WEATHERING		M	750.00 SqFt								
Sample Number:	302		Type:	R		Area:	5000.00 SqFt		PCI:	65		
Sample Comments:												
48	L & T CR		L	393.00 Ft								
48	L & T CR		M	50.00 Ft								
57	WEATHERING		L	4250.00 SqFt								
57	WEATHERING		M	750.00 SqFt								
Sample Number:	503		Type:	R		Area:	4996.00 SqFt		PCI:	76		
Sample Comments:												
48	L & T CR		L	239.00 Ft								
56	SWELLING		L	120.00 SqFt								
57	WEATHERING		L	4996.00 SqFt								

Network:	SPG			Name:	ALBERT WHITTED AIRPORT							
Branch:	AP NW		Name:	NORTHWEST APRON		Use:	APRON	Area:	130,334 SqFt			
Section:	4315 of 4		From:	-			To:	-			Last Const.:	1/1/2011
Surface:	AC		Family:	CA653-RL-AP-AC			Zone:				Rank:	P
Area:	35,173 SqFt		Length:	190 Ft			Width:	220 Ft				
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:			Street Type:				Grade:	0		Lanes:	0	
Section Comments:												
Work Date:	1/1/2011		Work Type: New Construction - Initial					Code:	NU-IN		Is Major M&R: True	
Last Insp. Date:	4/6/2022		TotalSamples:	8			Surveyed:	1				
Conditions:	PCI: 83											
Inspection Comments:												
Sample Number:	101		Type:	R		Area:	3316.00 SqFt		PCI:	83		
Sample Comments:												
48	L & T CR		L	49.00 Ft								
57	WEATHERING		L	2819.00 SqFt								
57	WEATHERING		M	497.00 SqFt								

Network:	SPG			Name:	ALBERT WHITTED AIRPORT							
Branch:	AP NW		Name:	NORTHWEST APRON		Use:	APRON	Area:	130,334 SqFt			
Section:	4320		of	4	From:	-		To:	-		Last Const.:	1/1/2002
Surface:	AC		Family:	CA653-RL-AP-AC		Zone:			Category:	Rank: P		
Area:	4,732 SqFt		Length:	170 Ft		Width:	28 Ft					
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:			Street Type:			Grade:	0		Lanes:	0		
Section Comments:												
Work Date:	1/1/2002		Work Type:	New Construction - Initial				Code:	NU-IN		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	1		Surveyed:	1					
Conditions:	PCI: 73											
Inspection Comments:												
Sample Number:	101		Type:	R		Area:	4732.00 SqFt		PCI:	73		
Sample Comments:												
45	DEPRESSION		L	20.00 SqFt								
48	L & T CR		L	15.00 Ft								
57	WEATHERING		M	4732.00 SqFt								

Network:		SPG		Name:		ALBERT WHITTED AIRPORT																	
Branch:		AP NW		Name:		NORTHWEST APRON		Use:		APRON		Area:		130,334 SqFt									
Section:		4325		of		4		From:		-		To:		-		Last Const.:		1/1/2018					
Surface:		AAC		Family:		CA653-RL-AP-AAC-APC		Zone:				Category:				Rank:		P					
Area:		14,232 SqFt		Length:		206 Ft		Width:		60 Ft													
Slabs:				Slab Length:		Ft		Slab Width:		Ft		Joint Length:		Ft									
Shoulder:				Street Type:				Grade:		0		Lanes:		0									
Section Comments:																							
Work Date:				1/1/2006				Work Type:				New Construction - Initial				Code:		NU-IN		Is Major M&R:		True	
Work Date:				1/1/2018				Work Type:				Mill and Overlay				Code:		ML-OVL		Is Major M&R:		True	
Last Insp. Date:				4/6/2022				TotalSamples:				3				Surveyed:				1			
Conditions:				PCI:				90															
Inspection Comments:																							
Sample Number:		101		Type:		R		Area:		5296.00 SqFt		PCI:		90									
Sample Comments:																							
48		L & T CR		L		25.00 Ft																	
57		WEATHERING		L		4560.00 SqFt																	

Network:	SPG		Name:	ALBERT WHITTED AIRPORT							
Branch:	RW 18-36		Name:	RUNWAY 18-36		Use:	RUNWAY	Area:	217,732 SqFt		
Section:	6105 of 1		From:	-		To:	-		Last Const.:	4/1/2022	
Surface:	AAC	Family:	CA653-RL-RW-AAC-APC		Zone:			Category:	Rank: P		
Area:	217,732 SqFt		Length:	2,864 Ft		Width:	75 Ft				
Slabs:	Slab Length:		Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:	Street Type:		Grade:		0		Lanes:	0			
Section Comments:											
Work Date:	1/1/1950		Work Type: New Construction - AC				Code:	NC-AC		Is Major M&R:	True
Work Date:	1/1/1992		Work Type: Overlay - AC Structural				Code:	OL-AS		Is Major M&R:	True
Work Date:	4/1/2022		Work Type: Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True
Last Insp. Date:	12/11/2018		TotalSamples:	57		Surveyed:	17				
Conditions:	PCI: 57		NOTE: *** Pre-Construction PCI ***								
Inspection Comments:											
Sample Number:	120		Type:	R		Area:	5000.00 SqFt		PCI:	59	
Sample Comments:											
43	BLOCK CR		L	5000.00 SqFt							
52	RAVELING		L	5000.00 SqFt							
Sample Number:	148		Type:	R		Area:	5000.00 SqFt		PCI:	55	
Sample Comments:											
43	BLOCK CR		L	2000.00 SqFt							
48	L & T CR		L	356.00 Ft							
52	RAVELING		L	5000.00 SqFt							
56	SWELLING		L	2.00 SqFt							
Sample Number:	301		Type:	R		Area:	5000.00 SqFt		PCI:	55	
Sample Comments:											
43	BLOCK CR		L	110.00 SqFt							
45	DEPRESSION		L	9.00 SqFt							
48	L & T CR		L	208.00 Ft							
48	L & T CR		M	50.00 Ft							
52	RAVELING		L	5000.00 SqFt							
56	SWELLING		L	40.00 SqFt							
Sample Number:	306		Type:	R		Area:	5000.00 SqFt		PCI:	67	
Sample Comments:											
48	L & T CR		L	479.00 Ft							
52	RAVELING		L	5000.00 SqFt							
56	SWELLING		L	5.00 SqFt							
Sample Number:	310		Type:	R		Area:	5000.00 SqFt		PCI:	57	
Sample Comments:											
43	BLOCK CR		L	650.00 SqFt							
48	L & T CR		L	378.00 Ft							
48	L & T CR		M	45.00 Ft							
52	RAVELING		L	5000.00 SqFt							
Sample Number:	315		Type:	R		Area:	5000.00 SqFt		PCI:	67	
Sample Comments:											
48	L & T CR		L	502.00 Ft							
52	RAVELING		L	5000.00 SqFt							
56	SWELLING		L	5.00 SqFt							
Sample Number:	320		Type:	R		Area:	5000.00 SqFt		PCI:	57	
Sample Comments:											
43	BLOCK CR		L	400.00 SqFt							
48	L & T CR		L	385.00 Ft							

48	L & T CR	M	50.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	26.00	SqFt
Sample Number: 325 Type: R Area: 5000.00 SqFt PCI: 59				
Sample Comments:				
43	BLOCK CR	L	400.00	SqFt
48	L & T CR	L	334.00	Ft
48	L & T CR	M	50.00	Ft
52	RAVELING	L	5000.00	SqFt
Sample Number: 330 Type: R Area: 5000.00 SqFt PCI: 64				
Sample Comments:				
43	BLOCK CR	L	850.00	SqFt
48	L & T CR	L	205.00	Ft
52	RAVELING	L	5000.00	SqFt
Sample Number: 335 Type: R Area: 5000.00 SqFt PCI: 61				
Sample Comments:				
43	BLOCK CR	L	1650.00	SqFt
48	L & T CR	L	212.00	Ft
52	RAVELING	L	5000.00	SqFt
Sample Number: 340 Type: R Area: 5000.00 SqFt PCI: 57				
Sample Comments:				
43	BLOCK CR	L	650.00	SqFt
48	L & T CR	L	291.00	Ft
48	L & T CR	M	38.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	15.00	SqFt
Sample Number: 345 Type: R Area: 5000.00 SqFt PCI: 53				
Sample Comments:				
43	BLOCK CR	L	2100.00	SqFt
48	L & T CR	L	324.00	Ft
48	L & T CR	M	100.00	Ft
52	RAVELING	L	5000.00	SqFt
Sample Number: 350 Type: R Area: 5000.00 SqFt PCI: 44				
Sample Comments:				
43	BLOCK CR	L	1100.00	SqFt
43	BLOCK CR	M	300.00	SqFt
48	L & T CR	L	200.00	Ft
48	L & T CR	M	60.00	Ft
52	RAVELING	L	4900.00	SqFt
52	RAVELING	M	100.00	SqFt
56	SWELLING	L	105.00	SqFt
Sample Number: 354 Type: R Area: 5000.00 SqFt PCI: 56				
Sample Comments:				
43	BLOCK CR	L	740.00	SqFt
45	DEPRESSION	L	238.00	SqFt
48	L & T CR	L	254.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	10.00	SqFt
Sample Number: 504 Type: R Area: 5000.00 SqFt PCI: 69				
Sample Comments:				
48	L & T CR	L	398.00	Ft
52	RAVELING	L	5000.00	SqFt
Sample Number: 532 Type: R Area: 5000.00 SqFt PCI: 58				
Sample Comments:				
43	BLOCK CR	L	1150.00	SqFt
48	L & T CR	L	397.00	Ft
52	RAVELING	L	5000.00	SqFt

Sample Number: 552		Type:	R	Area:	6600.00 SqFt	PCI:	45
Sample Comments:							
43	BLOCK CR		L	3100.00	SqFt		
43	BLOCK CR		M	994.00	SqFt		
48	L & T CR		L	263.00	Ft		
52	RAVELING		L	6600.00	SqFt		
56	SWELLING		L	8.00	SqFt		

Network:		SPG		Name:		ALBERT WHITTED AIRPORT																	
Branch:		RW 7-25		Name:		RUNWAY 7-25		Use:		RUNWAY		Area:		268,375 SqFt									
Section:		6205		of 8		From:		-		To:		-		Last Const.:		6/1/2016							
Surface:		AAC		Family:		CA653-RL-RW-AAC-APC		Zone:				Category:				Rank:		P					
Area:		18,375 SqFt		Length:		245 Ft		Width:		75 Ft													
Slabs:				Slab Length:		Ft		Slab Width:		Ft		Joint Length:		Ft									
Shoulder:				Street Type:				Grade:		0		Lanes:		0									
Section Comments:																							
Work Date:				1/1/1965				Work Type:				New Construction - AC				Code:		NC-AC		Is Major M&R:		True	
Work Date:				1/1/1991				Work Type:				New Construction - AC				Code:		NC-AC		Is Major M&R:		True	
Work Date:				6/1/2016				Work Type:				Mill and Overlay				Code:		ML-OVL		Is Major M&R:		True	
Last Insp. Date:				4/6/2022				TotalSamples:				5				Surveyed:				2			
Conditions:				PCI:				88															
Inspection Comments:																							
Sample Number:				170				Type:		R		Area:				3750.00 SqFt				PCI:		88	
Sample Comments:																							
48		L & T CR		L		71.00 Ft																	
57		WEATHERING		L		3750.00 SqFt																	
Sample Number:				173				Type:		R		Area:				3375.00 SqFt				PCI:		87	
Sample Comments:																							
48		L & T CR		L		69.00 Ft																	
57		WEATHERING		L		3375.00 SqFt																	

Network:		SPG		Name:		ALBERT WHITTED AIRPORT																									
Branch:		RW 7-25		Name:		RUNWAY 7-25		Use:		RUNWAY		Area:		268,375 SqFt																	
Section:		6207		of		8		From:		-		To:		-		Last Const.:		6/1/2016													
Surface:		AAC		Family:		CA653-RL-RW-AAC-APC		Zone:				Category:				Rank:		P													
Area:		22,950 SqFt		Length:		300 Ft		Width:		75 Ft																					
Slabs:				Slab Length:		Ft		Slab Width:		Ft		Joint Length:		Ft																	
Shoulder:				Street Type:				Grade:		0		Lanes:		0																	
Section Comments:																															
Work Date:				1/1/1965				Work Type:				BUILT				Code:				IMPORTED				Is Major M&R:				True			
Work Date:				6/1/2016				Work Type:				Mill and Overlay				Code:				ML-OVL				Is Major M&R:				True			
Last Insp. Date:				4/6/2022				TotalSamples:				6				Surveyed:				2											
Conditions:				PCI:				79																							
Inspection Comments:																															
Sample Number:				164				Type:		R		Area:				3750.00 SqFt				PCI:				77							
Sample Comments:																															
48		L & T CR		L		247.00		Ft																							
57		WEATHERING		L		3750.00		SqFt																							
Sample Number:				166				Type:		R		Area:				3750.00 SqFt				PCI:				82							
Sample Comments:																															
48		L & T CR		L		163.00		Ft																							
57		WEATHERING		L		3750.00		SqFt																							

Network:	SPG		Name:	ALBERT WHITTED AIRPORT					
Branch:	RW 7-25		Name:	RUNWAY 7-25		Use:	RUNWAY	Area:	268,375 SqFt
Section:	6208	of 8	From:	-			To:	-	Last Const.: 6/1/2016
Surface:	AAC	Family:	CA653-RL-RW-AAC-APC		Zone:			Category:	Rank: P
Area:	21,525 SqFt		Length:	287 Ft		Width:	75 Ft		
Slabs:	Slab Length:		Ft		Slab Width:	Ft		Joint Length:	Ft
Shoulder:	Street Type:				Grade:	0		Lanes:	0
Section Comments:									
Work Date:	1/1/1965		Work Type: New Construction - Initial				Code:	NU-IN	Is Major M&R: True
Work Date:	1/1/2012		Work Type: Mill and Overlay				Code:	ML-OVL	Is Major M&R: True
Work Date:	6/1/2016		Work Type: Mill and Overlay				Code:	ML-OVL	Is Major M&R: True
Last Insp. Date:	4/6/2022		TotalSamples:	6		Surveyed: 2			
Conditions:	PCI: 80								
Inspection Comments:									
Sample Number:	158	Type:	R	Area:	3750.00 SqFt		PCI:	80	
Sample Comments:									
48	L & T CR		L	184.00 Ft					
57	WEATHERING		L	3750.00 SqFt					
Sample Number:	160	Type:	R	Area:	3750.00 SqFt		PCI:	79	
Sample Comments:									
48	L & T CR		L	208.00 Ft					
57	WEATHERING		L	3750.00 SqFt					

Network:	SPG		Name:	ALBERT WHITTED AIRPORT							
Branch:	RW 7-25		Name:	RUNWAY 7-25		Use:	RUNWAY	Area:	268,375 SqFt		
Section:	6210 of 8		From:	-		To:	-		Last Const.:	6/1/2016	
Surface:	AAC	Family:	CA653-RL-RW-AAC-APC		Zone:			Category:	Rank: P		
Area:	147,650 SqFt		Length:	1,970 Ft		Width:	75 Ft				
Slabs:	Slab Length:		Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:	Street Type:				Grade:	0		Lanes:	0		
Section Comments:											
Work Date:	1/1/1965		Work Type: BUILT				Code:	IMPORTED		Is Major M&R:	True
Work Date:	1/1/1965		Work Type: OVERLAY				Code:	IMPORTED		Is Major M&R:	True
Work Date:	6/1/2016		Work Type: Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	39		Surveyed:	8				
Conditions:	PCI: 79										
Inspection Comments:											
Sample Number:	119		Type:	R		Area:	3750.00 SqFt		PCI:	87	
Sample Comments:											
48	L & T CR		L	90.00 Ft							
57	WEATHERING		L	3750.00 SqFt							
Sample Number:	125		Type:	R		Area:	3750.00 SqFt		PCI:	87	
Sample Comments:											
48	L & T CR		L	86.00 Ft							
57	WEATHERING		L	3750.00 SqFt							
Sample Number:	130		Type:	R		Area:	3750.00 SqFt		PCI:	75	
Sample Comments:											
48	L & T CR		L	274.00 Ft							
56	SWELLING		L	5.00 SqFt							
57	WEATHERING		L	3750.00 SqFt							
Sample Number:	136		Type:	R		Area:	3750.00 SqFt		PCI:	77	
Sample Comments:											
48	L & T CR		L	245.00 Ft							
57	WEATHERING		L	3750.00 SqFt							
Sample Number:	140		Type:	R		Area:	3750.00 SqFt		PCI:	76	
Sample Comments:											
48	L & T CR		L	272.00 Ft							
57	WEATHERING		L	3750.00 SqFt							
Sample Number:	144		Type:	R		Area:	3750.00 SqFt		PCI:	74	
Sample Comments:											
48	L & T CR		L	271.00 Ft							
56	SWELLING		L	10.00 SqFt							
57	WEATHERING		L	3750.00 SqFt							
Sample Number:	151		Type:	R		Area:	3750.00 SqFt		PCI:	77	
Sample Comments:											
48	L & T CR		L	252.00 Ft							
57	WEATHERING		L	3750.00 SqFt							
Sample Number:	155		Type:	R		Area:	3750.00 SqFt		PCI:	79	
Sample Comments:											
48	L & T CR		L	213.00 Ft							
57	WEATHERING		L	3750.00 SqFt							

Network:	SPG		Name:	ALBERT WHITTED AIRPORT							
Branch:	RW 7-25		Name:	RUNWAY 7-25		Use:	RUNWAY		Area:	268,375 SqFt	
Section:	6213 of 8		From:	-		To:	-		Last Const.:	6/1/2016	
Surface:	AC		Family:	CA653-RL-RW-AC		Zone:			Rank:	P	
Area:	19,590 SqFt		Length:	260 Ft		Width:	75 Ft				
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft	
Shoulder:			Street Type:			Grade:	0		Lanes:	0	
Section Comments:											
Work Date:	1/1/1965		Work Type: BUILT				Code:	IMPORTED		Is Major M&R:	True
Work Date:	1/1/1965		Work Type: OVERLAY				Code:	IMPORTED		Is Major M&R:	True
Work Date:	6/1/2016		Work Type: Complete Reconstruction - AC				Code:	CR-AC		Is Major M&R:	True
Last Insp. Date: 4/6/2022											
Conditions:	PCI: 84		TotalSamples:	5		Surveyed: 2					
Inspection Comments:											
Sample Number:	114		Type:	R		Area:	3750.00 SqFt		PCI:	80	
Sample Comments:											
48	L & T CR		L	186.00 Ft							
57	WEATHERING		L	3750.00 SqFt							
Sample Number:	117		Type:	R		Area:	3750.00 SqFt		PCI:	88	
Sample Comments:											
48	L & T CR		L	65.00 Ft							
57	WEATHERING		L	3750.00 SqFt							

Network:		SPG		Name:		ALBERT WHITTED AIRPORT						
Branch:	RW 7-25		Name:	RUNWAY 7-25		Use:	RUNWAY	Area:	268,375 SqFt			
Section:	6215		of	8	From:	-		To:	-		Last Const.:	6/1/2016
Surface:	AAC		Family:	CA653-RL-RW-AAC-APC		Zone:			Category:	Rank: P		
Area:	30,125 SqFt		Length:	407 Ft		Width:	75 Ft					
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:			Street Type:			Grade:	0		Lanes:	0		
Section Comments:												
Work Date:	1/1/1991		Work Type:	BUILT				Code:	IMPORTED		Is Major M&R:	True
Work Date:	1/1/1991		Work Type:	OVERLAY				Code:	IMPORTED		Is Major M&R:	True
Work Date:	6/1/2016		Work Type:	Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	8		Surveyed:	2					
Conditions:	PCI: 91											
Inspection Comments:												
Sample Number:	101		Type:	R		Area:	3000.00 SqFt		PCI:	87		
Sample Comments:												
48	L & T CR		L	66.00 Ft								
57	WEATHERING		L	3000.00 SqFt								
Sample Number:	105		Type:	R		Area:	3750.00 SqFt		PCI:	94		
Sample Comments:												
57	WEATHERING		L	3750.00 SqFt								

Network:	SPG			Name:	ALBERT WHITTED AIRPORT							
Branch:	RW 7-25		Name:	RUNWAY 7-25		Use:	RUNWAY		Area:	268,375 SqFt		
Section:	6220	of	8	From:	-			To:	-		Last Const.:	4/1/2022
Surface:	AAC	Family:	CA653-RL-RW-AAC-APC		Zone:				Category:	Rank: P		
Area:	2,875 SqFt		Length:	40 Ft		Width:	75 Ft					
Slabs:	Slab Length:		Ft		Slab Width:	Ft		Joint Length:	Ft			
Shoulder:	Street Type:				Grade:	0		Lanes:	0			
Section Comments:												
Work Date:	1/1/1965		Work Type: OVERLAY				Code:	IMPORTED		Is Major M&R: True		
Work Date:	1/1/1965		Work Type: BUILT				Code:	IMPORTED		Is Major M&R: True		
Work Date:	6/1/2016		Work Type: Complete Reconstruction - AC				Code:	CR-AC		Is Major M&R: True		
Work Date:	4/1/2022		Work Type: Mill and Overlay				Code:	ML-OVL		Is Major M&R: True		
Last Insp. Date:	10/8/2014		TotalSamples:	45		Surveyed:	9					
Conditions:	PCI: 60		NOTE: *** Pre-Construction PCI ***									
Inspection Comments:												
Sample Number:	114		Type:	R		Area:	3750.00 SqFt		PCI:	57		
Sample Comments:												
43	BLOCK CRACKING		L	2500.00 SqFt								
48	LONGITUDINAL/TRANSVERSE CRACKING		L	141.00 Ft								
52	RAVELING		L	3700.00 SqFt								
52	RAVELING		L	50.00 SqFt								
Sample Number:	119		Type:	R		Area:	3750.00 SqFt		PCI:	67		
Sample Comments:												
48	LONGITUDINAL/TRANSVERSE CRACKING		L	335.00 Ft								
50	PATCHING		L	1.00 SqFt								
50	PATCHING		L	2.00 SqFt								
52	RAVELING		L	3747.00 SqFt								
Sample Number:	125		Type:	R		Area:	3750.00 SqFt		PCI:	62		
Sample Comments:												
48	LONGITUDINAL/TRANSVERSE CRACKING		L	459.00 Ft								
48	LONGITUDINAL/TRANSVERSE CRACKING		M	13.00 Ft								
52	RAVELING		L	3750.00 SqFt								
Sample Number:	130		Type:	R		Area:	3750.00 SqFt		PCI:	62		
Sample Comments:												
48	LONGITUDINAL/TRANSVERSE CRACKING		L	638.00 Ft								
52	RAVELING		L	3750.00 SqFt								
Sample Number:	136		Type:	R		Area:	3750.00 SqFt		PCI:	64		
Sample Comments:												
48	LONGITUDINAL/TRANSVERSE CRACKING		L	544.00 Ft								
52	RAVELING		L	3750.00 SqFt								
Sample Number:	140		Type:	R		Area:	3750.00 SqFt		PCI:	59		
Sample Comments:												
48	LONGITUDINAL/TRANSVERSE CRACKING		L	564.00 Ft								
48	LONGITUDINAL/TRANSVERSE CRACKING		M	14.00 Ft								
52	RAVELING		L	3750.00 SqFt								

56	SWELLING	L	4.00	SqFt		
<hr/>						
Sample Number:	144	Type:	R	Area:	3750.00 SqFt	PCI: 58
Sample Comments:						
48	LONGITUDINAL/TRANSVERSE CRACKING	L	641.00	Ft		
48	LONGITUDINAL/TRANSVERSE CRACKING	M	15.00	Ft		
52	RAVELING	L	3750.00	SqFt		
<hr/>						
Sample Number:	151	Type:	R	Area:	3750.00 SqFt	PCI: 59
Sample Comments:						
48	LONGITUDINAL/TRANSVERSE CRACKING	L	613.00	Ft		
48	LONGITUDINAL/TRANSVERSE CRACKING	M	21.00	Ft		
52	RAVELING	L	3750.00	SqFt		
<hr/>						
Sample Number:	155	Type:	R	Area:	3750.00 SqFt	PCI: 54
Sample Comments:						
43	BLOCK CRACKING	L	210.00	SqFt		
48	LONGITUDINAL/TRANSVERSE CRACKING	L	425.00	Ft		
48	LONGITUDINAL/TRANSVERSE CRACKING	M	50.00	Ft		
52	RAVELING	L	3749.00	SqFt		
52	RAVELING	M	1.00	SqFt		

Network: SPG		Name: ALBERT WHITTED AIRPORT		
Branch: RW 7-25	Name: RUNWAY 7-25	Use: RUNWAY	Area: 268,375 SqFt	
Section: 6225	of 8	From: -	To: -	Last Const.: 4/1/2022
Surface: AAC	Family: CA653-RL-RW-AAC-APC	Zone:	Category:	Rank: P
Area: 5,285 SqFt	Length: 70 Ft	Width: 75 Ft		
Slabs:	Slab Length: Ft	Slab Width: Ft	Joint Length: Ft	
Shoulder:	Street Type:	Grade: 0	Lanes: 0	
Section Comments:				
Work Date: 1/1/1950	Work Type: New Construction - AC		Code: NC-AC	Is Major M&R: True
Work Date: 1/1/1992	Work Type: Overlay - AC Structural		Code: OL-AS	Is Major M&R: True
Work Date: 4/1/2022	Work Type: Mill and Overlay		Code: ML-OVL	Is Major M&R: True
Last Insp. Date: 12/11/2018	TotalSamples: 57	Surveyed: 12		
Conditions: PCI: 58	NOTE: *** Pre-Construction PCI ***			
Inspection Comments:				
Sample Number: 301	Type: R	Area: 5000.00 SqFt	PCI: 55	
Sample Comments:				
43 BLOCK CR	L	110.00 SqFt		
45 DEPRESSION	L	9.00 SqFt		
48 L & T CR	L	208.00 Ft		
48 L & T CR	M	50.00 Ft		
52 RAVELING	L	5000.00 SqFt		
56 SWELLING	L	40.00 SqFt		
Sample Number: 306	Type: R	Area: 5000.00 SqFt	PCI: 67	
Sample Comments:				
48 L & T CR	L	479.00 Ft		
52 RAVELING	L	5000.00 SqFt		
56 SWELLING	L	5.00 SqFt		
Sample Number: 310	Type: R	Area: 5000.00 SqFt	PCI: 57	
Sample Comments:				
43 BLOCK CR	L	650.00 SqFt		
48 L & T CR	L	378.00 Ft		
48 L & T CR	M	45.00 Ft		
52 RAVELING	L	5000.00 SqFt		
Sample Number: 315	Type: R	Area: 5000.00 SqFt	PCI: 67	
Sample Comments:				
48 L & T CR	L	502.00 Ft		
52 RAVELING	L	5000.00 SqFt		
56 SWELLING	L	5.00 SqFt		
Sample Number: 320	Type: R	Area: 5000.00 SqFt	PCI: 57	
Sample Comments:				
43 BLOCK CR	L	400.00 SqFt		
48 L & T CR	L	385.00 Ft		
48 L & T CR	M	50.00 Ft		
52 RAVELING	L	5000.00 SqFt		
56 SWELLING	L	26.00 SqFt		
Sample Number: 325	Type: R	Area: 5000.00 SqFt	PCI: 59	
Sample Comments:				
43 BLOCK CR	L	400.00 SqFt		
48 L & T CR	L	334.00 Ft		
48 L & T CR	M	50.00 Ft		
52 RAVELING	L	5000.00 SqFt		
Sample Number: 330	Type: R	Area: 5000.00 SqFt	PCI: 64	
Sample Comments:				

43	BLOCK CR	L	850.00	SqFt
48	L & T CR	L	205.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 335		Type: R	Area: 5000.00 SqFt	PCI: 61
Sample Comments:				
43	BLOCK CR	L	1650.00	SqFt
48	L & T CR	L	212.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 340		Type: R	Area: 5000.00 SqFt	PCI: 57
Sample Comments:				
43	BLOCK CR	L	650.00	SqFt
48	L & T CR	L	291.00	Ft
48	L & T CR	M	38.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	15.00	SqFt
<hr/>				
Sample Number: 345		Type: R	Area: 5000.00 SqFt	PCI: 53
Sample Comments:				
43	BLOCK CR	L	2100.00	SqFt
48	L & T CR	L	324.00	Ft
48	L & T CR	M	100.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 350		Type: R	Area: 5000.00 SqFt	PCI: 44
Sample Comments:				
43	BLOCK CR	L	1100.00	SqFt
43	BLOCK CR	M	300.00	SqFt
48	L & T CR	L	200.00	Ft
48	L & T CR	M	60.00	Ft
52	RAVELING	L	4900.00	SqFt
52	RAVELING	M	100.00	SqFt
56	SWELLING	L	105.00	SqFt
<hr/>				
Sample Number: 354		Type: R	Area: 5000.00 SqFt	PCI: 56
Sample Comments:				
43	BLOCK CR	L	740.00	SqFt
45	DEPRESSION	L	238.00	SqFt
48	L & T CR	L	254.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	10.00	SqFt

Network:	SPG			Name:	ALBERT WHITTED AIRPORT						
Branch:	TW A		Name:	TAXIWAY A		Use:	TAXIWAY	Area:	123,682 SqFt		
Section:	103	of 6	From:	-			To:	-	Last Const.:	1/1/1991	
Surface:	AC	Family:	CA653-RL-TW-AC		Zone:		Category:		Rank:	P	
Area:	17,162 SqFt		Length:	450 Ft		Width:	40 Ft				
Slabs:		Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:		Street Type:		Grade:	0		Lanes:	0			
Section Comments:											
Work Date:	1/1/1991		Work Type:	New Construction - AC			Code:	NC-AC		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	4		Surveyed:	1				
Conditions:	PCI:	50									
Inspection Comments:											
Sample Number:	301	Type:	R	Area:	4000.00 SqFt		PCI:	50			
Sample Comments:											
48	L & T CR	L	391.00	Ft							
48	L & T CR	M	50.00	Ft							
50	PATCHING	M	10.00	SqFt							
52	RAVELING	L	3934.00	SqFt							
52	RAVELING	M	50.00	SqFt							
52	RAVELING	H	6.00	SqFt							

Network:	SPG			Name:	ALBERT WHITTED AIRPORT						
Branch:	TW A		Name:	TAXIWAY A		Use:	TAXIWAY	Area:	123,682 SqFt		
Section:	105 of 6		From:	-		To:	-		Last Const.:	1/1/1987	
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:			Rank:	P	
Area:	15,000 SqFt		Length:	500 Ft		Width:	40 Ft				
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft	
Shoulder:			Street Type:			Grade:	0		Lanes:	0	
Section Comments:											
Work Date:	1/1/1961		Work Type: BUILT				Code:	IMPORTED		Is Major M&R:	True
Work Date:	1/1/1987		Work Type: OVERLAY				Code:	IMPORTED		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	4		Surveyed: 1					
Conditions:	PCI: 38										
Inspection Comments:											
Sample Number:	103		Type:	R		Area:	4000.00 SqFt		PCI:	38	
Sample Comments:											
43	BLOCK CR		M	615.00 SqFt							
48	L & T CR		L	84.00 Ft							
48	L & T CR		M	200.00 Ft							
48	L & T CR		H	10.00 Ft							
52	RAVELING		L	3960.00 SqFt							
52	RAVELING		M	40.00 SqFt							
56	SWELLING		L	250.00 SqFt							

Network:	SPG		Name:	ALBERT WHITTED AIRPORT							
Branch:	TW A		Name:	TAXIWAY A		Use:	TAXIWAY		Area:	123,682 SqFt	
Section:	110 of 6		From:	-		To:	-		Last Const.:	1/1/1987	
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:			Category:	Rank: P	
Area:	21,000 SqFt		Length:	400 Ft		Width:	40 Ft				
Slabs:	Slab Length:		Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:	Street Type:		Grade:		0		Lanes:	0			
Section Comments:											
Work Date:	1/1/1961		Work Type: New Construction - AC				Code:	NC-AC		Is Major M&R:	True
Work Date:	1/1/1987		Work Type: Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True
Last Insp. Date: 4/6/2022											
Conditions:	PCI: 44										
Inspection Comments:											
Sample Number:	106		Type:	R		Area:	4000.00 SqFt		PCI:	38	
Sample Comments:											
43	BLOCK CR		L	3600.00 SqFt							
43	BLOCK CR		M	400.00 SqFt							
45	DEPRESSION		L	63.00 SqFt							
52	RAVELING		L	3916.00 SqFt							
52	RAVELING		M	84.00 SqFt							
56	SWELLING		L	150.00 SqFt							
Sample Number:	108		Type:	R		Area:	4000.00 SqFt		PCI:	50	
Sample Comments:											
48	L & T CR		L	106.00 Ft							
48	L & T CR		M	300.00 Ft							
52	RAVELING		L	3920.00 SqFt							
52	RAVELING		M	80.00 SqFt							
56	SWELLING		L	50.00 SqFt							

Network:	SPG			Name:	ALBERT WHITTED AIRPORT				
Branch:	TW A		Name:	TAXIWAY A		Use:	TAXIWAY	Area:	123,682 SqFt
Section:	115	of	6	From:	-	To:	-	Last Const.:	1/1/1987
Surface:	AAC	Family:	CA653-RL-TW-AAC-APC	Zone:		Category:		Rank:	P
Area:	65,457 SqFt		Length:	1,615 Ft		Width:	40 Ft		
Slabs:	Slab Length:		Ft	Slab Width:		Ft	Joint Length:		Ft
Shoulder:	Street Type:			Grade:	0	Lanes:		0	
Section Comments:									
Work Date:	1/1/1965		Work Type: BUILT			Code:	IMPORTED	Is Major M&R:	True
Work Date:	1/1/1987		Work Type: OVERLAY			Code:	IMPORTED	Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	16		Surveyed:	3		
Conditions:	PCI:	57							
Inspection Comments:									
Sample Number:	111	Type:	R	Area:	4000.00 SqFt		PCI:	50	
Sample Comments:									
48	L & T CR		L	127.00 Ft					
48	L & T CR		M	250.00 Ft					
50	PATCHING		M	3.00 SqFt					
52	RAVELING		L	3797.00 SqFt					
52	RAVELING		M	200.00 SqFt					
Sample Number:	117	Type:	R	Area:	4000.00 SqFt		PCI:	60	
Sample Comments:									
48	L & T CR		L	92.00 Ft					
48	L & T CR		M	185.00 Ft					
50	PATCHING		M	120.00 SqFt					
52	RAVELING		M	194.00 SqFt					
Sample Number:	121	Type:	R	Area:	4000.00 SqFt		PCI:	59	
Sample Comments:									
48	L & T CR		L	62.00 Ft					
48	L & T CR		M	100.00 Ft					
52	RAVELING		L	3720.00 SqFt					
52	RAVELING		M	280.00 SqFt					

Network:		SPG		Name:		ALBERT WHITTED AIRPORT								
Branch:	TW A		Name:	TAXIWAY A		Use:	TAXIWAY	Area:	123,682 SqFt					
Section:	125		of	6		From:	-		To:	-		Last Const.:	4/1/2022	
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:			Category:			Rank:	P	
Area:	1,540 SqFt		Length:	40 Ft		Width:	40 Ft							
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:			Ft		
Shoulder:			Street Type:			Grade:	0		Lanes:	0				
Section Comments:														
Work Date:	1/1/1950		Work Type:	New Construction - AC				Code:	NC-AC		Is Major M&R:	True		
Work Date:	1/1/1989		Work Type:	Overlay - AC Structural				Code:	OL-AS		Is Major M&R:	True		
Work Date:	4/1/2022		Work Type:	Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True		
Last Insp. Date:	12/11/2018		TotalSamples:	1		Surveyed:	1							
Conditions:	PCI: 44		NOTE: *** Pre-Construction PCI ***											
Inspection Comments:														
Sample Number:	100		Type:	R		Area:	6613.00 SqFt		PCI:	44				
Sample Comments:														
48	L & T CR		L	157.00 Ft										
52	RAVELING		L	2645.00 SqFt										
52	RAVELING		M	3968.00 SqFt										

Network:	SPG	Name:	ALBERT WHITTED AIRPORT						
Branch:	TW A	Name:	TAXIWAY A		Use:	TAXIWAY	Area:	123,682 SqFt	
Section:	130	of	6	From:	-	To:	-	Last Const.:	4/1/2022
Surface:	AAC	Family:	CA653-RL-TW-AAC-APC	Zone:		Category:		Rank:	P
Area:	3,523 SqFt	Length:	70 Ft	Width:	50 Ft				
Slabs:	Slab Length:	Ft	Slab Width:	Ft	Joint Length:	Ft			
Shoulder:	Street Type:	Grade:	0	Lanes:	0				
Section Comments:									
Work Date:	1/1/1950	Work Type:	New Construction - AC			Code:	NC-AC	Is Major M&R:	True
Work Date:	1/1/1992	Work Type:	Overlay - AC Structural			Code:	OL-AS	Is Major M&R:	True
Work Date:	4/1/2022	Work Type:	Mill and Overlay			Code:	ML-OVL	Is Major M&R:	True
Last Insp. Date:	12/11/2018	TotalSamples:	57	Surveyed:	12				
Conditions:	PCI: 58	NOTE: *** Pre-Construction PCI ***							
Inspection Comments:									
Sample Number:	301	Type:	R	Area:	5000.00 SqFt	PCI:	55		
Sample Comments:									
43	BLOCK CR	L	110.00	SqFt					
45	DEPRESSION	L	9.00	SqFt					
48	L & T CR	L	208.00	Ft					
48	L & T CR	M	50.00	Ft					
52	RAVELING	L	5000.00	SqFt					
56	SWELLING	L	40.00	SqFt					
Sample Number:	306	Type:	R	Area:	5000.00 SqFt	PCI:	67		
Sample Comments:									
48	L & T CR	L	479.00	Ft					
52	RAVELING	L	5000.00	SqFt					
56	SWELLING	L	5.00	SqFt					
Sample Number:	310	Type:	R	Area:	5000.00 SqFt	PCI:	57		
Sample Comments:									
43	BLOCK CR	L	650.00	SqFt					
48	L & T CR	L	378.00	Ft					
48	L & T CR	M	45.00	Ft					
52	RAVELING	L	5000.00	SqFt					
Sample Number:	315	Type:	R	Area:	5000.00 SqFt	PCI:	67		
Sample Comments:									
48	L & T CR	L	502.00	Ft					
52	RAVELING	L	5000.00	SqFt					
56	SWELLING	L	5.00	SqFt					
Sample Number:	320	Type:	R	Area:	5000.00 SqFt	PCI:	57		
Sample Comments:									
43	BLOCK CR	L	400.00	SqFt					
48	L & T CR	L	385.00	Ft					
48	L & T CR	M	50.00	Ft					
52	RAVELING	L	5000.00	SqFt					
56	SWELLING	L	26.00	SqFt					
Sample Number:	325	Type:	R	Area:	5000.00 SqFt	PCI:	59		
Sample Comments:									
43	BLOCK CR	L	400.00	SqFt					
48	L & T CR	L	334.00	Ft					
48	L & T CR	M	50.00	Ft					
52	RAVELING	L	5000.00	SqFt					
Sample Number:	330	Type:	R	Area:	5000.00 SqFt	PCI:	64		
Sample Comments:									

43	BLOCK CR	L	850.00	SqFt
48	L & T CR	L	205.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 335		Type: R	Area: 5000.00 SqFt	PCI: 61
Sample Comments:				
43	BLOCK CR	L	1650.00	SqFt
48	L & T CR	L	212.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 340		Type: R	Area: 5000.00 SqFt	PCI: 57
Sample Comments:				
43	BLOCK CR	L	650.00	SqFt
48	L & T CR	L	291.00	Ft
48	L & T CR	M	38.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	15.00	SqFt
<hr/>				
Sample Number: 345		Type: R	Area: 5000.00 SqFt	PCI: 53
Sample Comments:				
43	BLOCK CR	L	2100.00	SqFt
48	L & T CR	L	324.00	Ft
48	L & T CR	M	100.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 350		Type: R	Area: 5000.00 SqFt	PCI: 44
Sample Comments:				
43	BLOCK CR	L	1100.00	SqFt
43	BLOCK CR	M	300.00	SqFt
48	L & T CR	L	200.00	Ft
48	L & T CR	M	60.00	Ft
52	RAVELING	L	4900.00	SqFt
52	RAVELING	M	100.00	SqFt
56	SWELLING	L	105.00	SqFt
<hr/>				
Sample Number: 354		Type: R	Area: 5000.00 SqFt	PCI: 56
Sample Comments:				
43	BLOCK CR	L	740.00	SqFt
45	DEPRESSION	L	238.00	SqFt
48	L & T CR	L	254.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	10.00	SqFt

Network:	SPG		Name:	ALBERT WHITTED AIRPORT					
Branch:	TW A1		Name:	TAXIWAY A1		Use:	TAXIWAY	Area:	4,672 SqFt
Section:	120	of	1	From:	-	To:	-	Last Const.:	6/1/2016
Surface:	AC	Family:	CA653-RL-TW-AC	Zone:		Category:		Rank:	P
Area:	4,672 SqFt	Length:	95 Ft	Width:	40 Ft				
Slabs:		Slab Length:	Ft	Slab Width:	Ft	Joint Length:	Ft		
Shoulder:		Street Type:		Grade:	0	Lanes:	0		
Section Comments:									
Work Date:	6/1/2016	Work Type:	New Construction - AC			Code:	NC-AC	Is Major M&R:	True
Last Insp. Date:	4/6/2022	TotalSamples:	1	Surveyed:	1				
Conditions:	PCI:	86							
Inspection Comments:									
Sample Number:	100	Type:	R	Area:	4672.00 SqFt	PCI:	86		
Sample Comments:									
48	L & T CR	L	8.00 Ft						
50	PATCHING	L	90.00 SqFt						
57	WEATHERING	L	4582.00 SqFt						

Network:	SPG			Name:	ALBERT WHITTED AIRPORT							
Branch:	TW A2		Name:	TAXIWAY A2		Use:	TAXIWAY	Area:	5,577 SqFt			
Section:	410		of	1	From:	-		To:	-		Last Const.:	6/1/2016
Surface:	AC		Family:	CA653-RL-TW-AC		Zone:			Category:	Rank: P		
Area:	5,577 SqFt		Length:	95 Ft		Width:	41 Ft					
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:			Street Type:			Grade:	0		Lanes:	0		
Section Comments:												
Work Date:	1/1/1991		Work Type:	BUILT				Code:	IMPORTED		Is Major M&R:	True
Work Date:	6/1/2016		Work Type:	Complete Reconstruction - AC				Code:	CR-AC		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	1		Surveyed:	1					
Conditions:	PCI: 90											
Inspection Comments:												
Sample Number:	100		Type:	R		Area:	5577.00 SqFt		PCI:	90		
Sample Comments:												
48	L & T CR		L	18.00 Ft								
57	WEATHERING		L	5577.00 SqFt								

Network:		SPG		Name:		ALBERT WHITTED AIRPORT						
Branch:	TW A3		Name:	TAXIWAY A3		Use:	TAXIWAY	Area:	5,518 SqFt			
Section:	310		of	1	From:	-		To:	-		Last Const.:	6/1/2016
Surface:	AC		Family:	CA653-RL-TW-AC		Zone:			Category:	Rank: P		
Area:	5,518 SqFt		Length:	95 Ft		Width:	41 Ft					
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:			Street Type:			Grade:	0		Lanes:	0		
Section Comments:												
Work Date:	1/1/1950		Work Type:	New Construction - AC				Code:	NC-AC		Is Major M&R:	True
Work Date:	1/1/1987		Work Type:	BUILT				Code:	IMPORTED		Is Major M&R:	True
Work Date:	6/1/2016		Work Type:	Complete Reconstruction - AC				Code:	CR-AC		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	1		Surveyed:	1					
Conditions:	PCI: 89											
Inspection Comments:												
Sample Number:	100		Type:	R		Area:	5518.00 SqFt		PCI:	89		
Sample Comments:												
48	L & T CR		L	50.00 Ft								
57	WEATHERING		L	5518.00 SqFt								

Network:		SPG		Name:		ALBERT WHITTED AIRPORT					
Branch:	TW A4		Name:	TAXIWAY A4		Use:	TAXIWAY	Area:	16,668 SqFt		
Section:	610 of 2		From:	-		To:	-		Last Const.:	6/1/2016	
Surface:	AC		Family:	CA653-RL-TW-AC		Zone:			Rank:	P	
Area:	5,518 SqFt		Length:	95 Ft		Width:	41 Ft				
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft	
Shoulder:			Street Type:			Grade:	0		Lanes:	0	
Section Comments:											
Work Date:	1/1/1987		Work Type: New Construction - AC				Code:	NC-AC		Is Major M&R:	True
Work Date:	6/1/2016		Work Type: Complete Reconstruction - AC				Code:	CR-AC		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	1		Surveyed:	1				
Conditions:	PCI: 89										
Inspection Comments:											
Sample Number:	100		Type:	R		Area:	5518.00 SqFt		PCI:	89	
Sample Comments:											
48	L & T CR		L	69.00 Ft							
57	WEATHERING		L	5518.00 SqFt							

Network:	SPG		Name:	ALBERT WHITTED AIRPORT							
Branch:	TW A4		Name:	TAXIWAY A4		Use:	TAXIWAY	Area:	16,668 SqFt		
Section:	620	of	2	From:	-			To:	-		
Surface:	AC	Family:	CA653-RL-TW-AC		Zone:				Category:		
Area:	11,150 SqFt		Length:	300 Ft		Width:	30 Ft				
Slabs:	Slab Length:		Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:	Street Type:		Grade:		0		Lanes:	0			
Section Comments:											
Work Date:	1/1/2013		Work Type:	New Construction - Initial			Code:	NU-IN		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	3		Surveyed:	1				
Conditions:	PCI:	87									
Inspection Comments:											
Sample Number:	119	Type:	R	Area:	3000.00 SqFt		PCI:	87			
Sample Comments:											
48	L & T CR		L	15.00 Ft							
57	WEATHERING		L	2850.00 SqFt							
57	WEATHERING		M	150.00 SqFt							

Network:		SPG		Name:		ALBERT WHITTED AIRPORT									
Branch:		TW B		Name:		TAXIWAY B		Use:		TAXIWAY		Area:		112,508 SqFt	
Section:		205		of 3		From:		-		To:		-		Last Const.: 1/1/1988	
Surface:		AAC		Family:		CA653-RL-TW-AAC-APC		Zone:		Category:		Rank:		P	
Area:		87,871 SqFt		Length:		2,150 Ft		Width:		40 Ft					
Slabs:		Slab Length:		Ft		Slab Width:		Ft		Joint Length:		Ft			
Shoulder:		Street Type:		Grade:		0		Lanes:		0					
Section Comments:															
Work Date:		1/1/1961		Work Type:		BUILT		Code:		IMPORTED		Is Major M&R:		True	
Work Date:		1/1/1988		Work Type:		OVERLAY		Code:		IMPORTED		Is Major M&R:		True	
Work Date:		1/1/1988		Work Type:		OVERLAY		Code:		IMPORTED		Is Major M&R:		True	
Last Insp. Date:		4/6/2022		TotalSamples:		21		Surveyed:		3					
Conditions:		PCI: 60													
Inspection Comments:															
Sample Number:		101		Type:		R		Area:		4000.00 SqFt		PCI:		56	
Sample Comments:															
48	L & T CR			L		110.00 Ft									
48	L & T CR			M		25.00 Ft									
50	PATCHING			L		880.00 SqFt									
52	RAVELING			L		3089.00 SqFt									
52	RAVELING			M		31.00 SqFt									
Sample Number:		108		Type:		R		Area:		4000.00 SqFt		PCI:		59	
Sample Comments:															
48	L & T CR			L		106.00 Ft									
48	L & T CR			M		50.00 Ft									
52	RAVELING			L		3960.00 SqFt									
52	RAVELING			M		40.00 SqFt									
Sample Number:		119		Type:		R		Area:		4000.00 SqFt		PCI:		66	
Sample Comments:															
48	L & T CR			L		12.00 Ft									
52	RAVELING			L		3800.00 SqFt									
52	RAVELING			M		200.00 SqFt									

Network:	SPG		Name:	ALBERT WHITTED AIRPORT							
Branch:	TW B		Name:	TAXIWAY B		Use:	TAXIWAY	Area:	112,508 SqFt		
Section:	210 of 3		From:	-			To:	-		Last Const.:	1/1/1988
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:				Category:	Rank: P
Area:	18,217 SqFt		Length:	415 Ft		Width:	40 Ft				
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft	
Shoulder:			Street Type:			Grade:	0		Lanes:	0	
Section Comments:											
Work Date:	1/1/1965		Work Type: BUILT				Code:	IMPORTED		Is Major M&R:	True
Work Date:	1/1/1988		Work Type: OVERLAY				Code:	IMPORTED		Is Major M&R:	True
Work Date:	1/1/1988		Work Type: OVERLAY				Code:	IMPORTED		Is Major M&R:	True
Last Insp. Date: 4/6/2022											
Conditions: PCI: 48			TotalSamples:	4		Surveyed: 1					
Inspection Comments:											
Sample Number:	126		Type:	R		Area:	4018.00 SqFt		PCI:	48	
Sample Comments:											
48	L & T CR		M	29.00 Ft							
50	PATCHING		L	300.00 SqFt							
52	RAVELING		L	2231.00 SqFt							
52	RAVELING		M	1487.00 SqFt							

Network:	SPG		Name:	ALBERT WHITTED AIRPORT							
Branch:	TW B		Name:	TAXIWAY B		Use:	TAXIWAY	Area:	112,508 SqFt		
Section:	215 of 3		From:	-		To:	-		Last Const.:	6/1/2016	
Surface:	AC		Family:	CA653-RL-TW-AC		Zone:			Category:	Rank: P	
Area:	6,420 SqFt		Length:	100 Ft		Width:	50 Ft				
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft	
Shoulder:			Street Type:			Grade:	0		Lanes:	0	
Section Comments:											
Work Date:	1/1/1965		Work Type: New Construction - AC				Code:	NC-AC		Is Major M&R:	True
Work Date:	6/1/2016		Work Type: Complete Reconstruction - AC				Code:	CR-AC		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	1		Surveyed:	1				
Conditions:	PCI: 75										
Inspection Comments:											
Sample Number:	100		Type:	R		Area:	6420.00 SqFt		PCI:	75	
Sample Comments:											
48	L & T CR		L	6.00 Ft							
50	PATCHING		L	900.00 SqFt							
57	WEATHERING		L	5520.00 SqFt							

Network:		SPG		Name:		ALBERT WHITTED AIRPORT				
Branch:	TW B1		Name:		TAXIWAY B1		Use:	TAXIWAY	Area:	3,388 SqFt
Section:	250		of	2	From:	-		To:	-	
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:			Category:	Rank: P
Area:	1,246 SqFt		Length:	34 Ft		Width:	35 Ft			
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft
Shoulder:			Street Type:			Grade:	0		Lanes:	0
Section Comments:										
Work Date:	1/1/1950		Work Type:	New Construction - AC				Code:	NC-AC	Is Major M&R: True
Work Date:	1/1/1984		Work Type:	Overlay - AC Structural				Code:	OL-AS	Is Major M&R: True
Work Date:	4/1/2022		Work Type:	Mill and Overlay				Code:	ML-OVL	Is Major M&R: True
Last Insp. Date:	12/11/2018		TotalSamples:	1		Surveyed:	1			
Conditions:	PCI: 55		NOTE: *** Pre-Construction PCI ***							
Inspection Comments:										
Sample Number:	100		Type:	R		Area:	2578.00 SqFt		PCI:	55
Sample Comments:										
48	L & T CR		L	57.00		Ft				
48	L & T CR		M	3.00		Ft				
52	RAVELING		L	1928.00		SqFt				
52	RAVELING		M	650.00		SqFt				

Network:	SPG		Name:	ALBERT WHITTED AIRPORT										
Branch:	TW B1		Name:	TAXIWAY B1		Use:	TAXIWAY		Area:	3,388 SqFt				
Section:	255		of	2		From:	-		To:	-		Last Const.:	4/1/2022	
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:			Category:			Rank:	P	
Area:	2,142 SqFt		Length:	62 Ft		Width:			35 Ft					
Slabs:			Slab Length:	Ft		Slab Width:			Ft	Joint Length:			Ft	
Shoulder:			Street Type:			Grade:	0		Lanes:	0				
Section Comments:														
Work Date:	1/1/1950		Work Type:	New Construction - AC					Code:	NC-AC		Is Major M&R:	True	
Work Date:	1/1/1992		Work Type:	Overlay - AC Structural					Code:	OL-AS		Is Major M&R:	True	
Work Date:	4/1/2022		Work Type:	Mill and Overlay					Code:	ML-OVL		Is Major M&R:	True	
Last Insp. Date:	12/11/2018		TotalSamples:	57		Surveyed:	12							
Conditions:	PCI:	58		NOTE: *** Pre-Construction PCI ***										
Inspection Comments:														
Sample Number:	301		Type:	R		Area:	5000.00 SqFt		PCI:	55				
Sample Comments:														
43	BLOCK CR		L	110.00		SqFt								
45	DEPRESSION		L	9.00		SqFt								
48	L & T CR		L	208.00		Ft								
48	L & T CR		M	50.00		Ft								
52	RAVELING		L	5000.00		SqFt								
56	SWELLING		L	40.00		SqFt								
Sample Number:	306		Type:	R		Area:	5000.00 SqFt		PCI:	67				
Sample Comments:														
48	L & T CR		L	479.00		Ft								
52	RAVELING		L	5000.00		SqFt								
56	SWELLING		L	5.00		SqFt								
Sample Number:	310		Type:	R		Area:	5000.00 SqFt		PCI:	57				
Sample Comments:														
43	BLOCK CR		L	650.00		SqFt								
48	L & T CR		L	378.00		Ft								
48	L & T CR		M	45.00		Ft								
52	RAVELING		L	5000.00		SqFt								
Sample Number:	315		Type:	R		Area:	5000.00 SqFt		PCI:	67				
Sample Comments:														
48	L & T CR		L	502.00		Ft								
52	RAVELING		L	5000.00		SqFt								
56	SWELLING		L	5.00		SqFt								
Sample Number:	320		Type:	R		Area:	5000.00 SqFt		PCI:	57				
Sample Comments:														
43	BLOCK CR		L	400.00		SqFt								
48	L & T CR		L	385.00		Ft								
48	L & T CR		M	50.00		Ft								
52	RAVELING		L	5000.00		SqFt								
56	SWELLING		L	26.00		SqFt								
Sample Number:	325		Type:	R		Area:	5000.00 SqFt		PCI:	59				
Sample Comments:														
43	BLOCK CR		L	400.00		SqFt								
48	L & T CR		L	334.00		Ft								
48	L & T CR		M	50.00		Ft								
52	RAVELING		L	5000.00		SqFt								
Sample Number:	330		Type:	R		Area:	5000.00 SqFt		PCI:	64				
Sample Comments:														

43	BLOCK CR	L	850.00	SqFt
48	L & T CR	L	205.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 335		Type: R	Area: 5000.00 SqFt	PCI: 61
Sample Comments:				
43	BLOCK CR	L	1650.00	SqFt
48	L & T CR	L	212.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 340		Type: R	Area: 5000.00 SqFt	PCI: 57
Sample Comments:				
43	BLOCK CR	L	650.00	SqFt
48	L & T CR	L	291.00	Ft
48	L & T CR	M	38.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	15.00	SqFt
<hr/>				
Sample Number: 345		Type: R	Area: 5000.00 SqFt	PCI: 53
Sample Comments:				
43	BLOCK CR	L	2100.00	SqFt
48	L & T CR	L	324.00	Ft
48	L & T CR	M	100.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 350		Type: R	Area: 5000.00 SqFt	PCI: 44
Sample Comments:				
43	BLOCK CR	L	1100.00	SqFt
43	BLOCK CR	M	300.00	SqFt
48	L & T CR	L	200.00	Ft
48	L & T CR	M	60.00	Ft
52	RAVELING	L	4900.00	SqFt
52	RAVELING	M	100.00	SqFt
56	SWELLING	L	105.00	SqFt
<hr/>				
Sample Number: 354		Type: R	Area: 5000.00 SqFt	PCI: 56
Sample Comments:				
43	BLOCK CR	L	740.00	SqFt
45	DEPRESSION	L	238.00	SqFt
48	L & T CR	L	254.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	10.00	SqFt

Network:	SPG		Name:	ALBERT WHITTED AIRPORT										
Branch:	TW B2		Name:	TAXIWAY B2		Use:	TAXIWAY	Area:	6,176 SqFt					
Section:	265		of	2		From:	-		To:	-		Last Const.:	4/1/2022	
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:			Category:			Rank:	P	
Area:	2,731 SqFt		Length:	62 Ft		Width:	35 Ft							
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:			Ft		
Shoulder:			Street Type:			Grade:	0		Lanes:	0				
Section Comments:														
Work Date:	1/1/1950		Work Type:	New Construction - AC				Code:	NC-AC		Is Major M&R:	True		
Work Date:	1/1/1992		Work Type:	Overlay - AC Structural				Code:	OL-AS		Is Major M&R:	True		
Work Date:	4/1/2022		Work Type:	Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True		
Last Insp. Date:	12/11/2018		TotalSamples:	57		Surveyed:	12							
Conditions:	PCI: 58		NOTE: *** Pre-Construction PCI ***											
Inspection Comments:														
Sample Number:	301		Type:	R		Area:	5000.00 SqFt		PCI:	55				
Sample Comments:														
43	BLOCK CR		L	110.00 SqFt										
45	DEPRESSION		L	9.00 SqFt										
48	L & T CR		L	208.00 Ft										
48	L & T CR		M	50.00 Ft										
52	RAVELING		L	5000.00 SqFt										
56	SWELLING		L	40.00 SqFt										
Sample Number:	306		Type:	R		Area:	5000.00 SqFt		PCI:	67				
Sample Comments:														
48	L & T CR		L	479.00 Ft										
52	RAVELING		L	5000.00 SqFt										
56	SWELLING		L	5.00 SqFt										
Sample Number:	310		Type:	R		Area:	5000.00 SqFt		PCI:	57				
Sample Comments:														
43	BLOCK CR		L	650.00 SqFt										
48	L & T CR		L	378.00 Ft										
48	L & T CR		M	45.00 Ft										
52	RAVELING		L	5000.00 SqFt										
Sample Number:	315		Type:	R		Area:	5000.00 SqFt		PCI:	67				
Sample Comments:														
48	L & T CR		L	502.00 Ft										
52	RAVELING		L	5000.00 SqFt										
56	SWELLING		L	5.00 SqFt										
Sample Number:	320		Type:	R		Area:	5000.00 SqFt		PCI:	57				
Sample Comments:														
43	BLOCK CR		L	400.00 SqFt										
48	L & T CR		L	385.00 Ft										
48	L & T CR		M	50.00 Ft										
52	RAVELING		L	5000.00 SqFt										
56	SWELLING		L	26.00 SqFt										
Sample Number:	325		Type:	R		Area:	5000.00 SqFt		PCI:	59				
Sample Comments:														
43	BLOCK CR		L	400.00 SqFt										
48	L & T CR		L	334.00 Ft										
48	L & T CR		M	50.00 Ft										
52	RAVELING		L	5000.00 SqFt										
Sample Number:	330		Type:	R		Area:	5000.00 SqFt		PCI:	64				
Sample Comments:														

43	BLOCK CR	L	850.00	SqFt
48	L & T CR	L	205.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 335		Type: R	Area: 5000.00 SqFt	PCI: 61
Sample Comments:				
43	BLOCK CR	L	1650.00	SqFt
48	L & T CR	L	212.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 340		Type: R	Area: 5000.00 SqFt	PCI: 57
Sample Comments:				
43	BLOCK CR	L	650.00	SqFt
48	L & T CR	L	291.00	Ft
48	L & T CR	M	38.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	15.00	SqFt
<hr/>				
Sample Number: 345		Type: R	Area: 5000.00 SqFt	PCI: 53
Sample Comments:				
43	BLOCK CR	L	2100.00	SqFt
48	L & T CR	L	324.00	Ft
48	L & T CR	M	100.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 350		Type: R	Area: 5000.00 SqFt	PCI: 44
Sample Comments:				
43	BLOCK CR	L	1100.00	SqFt
43	BLOCK CR	M	300.00	SqFt
48	L & T CR	L	200.00	Ft
48	L & T CR	M	60.00	Ft
52	RAVELING	L	4900.00	SqFt
52	RAVELING	M	100.00	SqFt
56	SWELLING	L	105.00	SqFt
<hr/>				
Sample Number: 354		Type: R	Area: 5000.00 SqFt	PCI: 56
Sample Comments:				
43	BLOCK CR	L	740.00	SqFt
45	DEPRESSION	L	238.00	SqFt
48	L & T CR	L	254.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	10.00	SqFt

Network:		SPG		Name:		ALBERT WHITTED AIRPORT								
Branch:	TW B3		Name:	TAXIWAY B3		Use:	TAXIWAY	Area:	6,176 SqFt					
Section:	275		of	2		From:	-		To:	-		Last Const.:	4/1/2022	
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:			Category:			Rank:	P	
Area:	2,731 SqFt		Length:	62 Ft		Width:	35 Ft							
Slabs:	Slab Length:		Ft		Slab Width:	Ft		Joint Length:	Ft					
Shoulder:	Street Type:				Grade:	0		Lanes:	0					
Section Comments:														
Work Date:	1/1/1950		Work Type:	New Construction - AC				Code:	NC-AC		Is Major M&R:	True		
Work Date:	1/1/1992		Work Type:	Overlay - AC Structural				Code:	OL-AS		Is Major M&R:	True		
Work Date:	4/1/2022		Work Type:	Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True		
Last Insp. Date:	12/11/2018		TotalSamples:	57		Surveyed:	12							
Conditions:	PCI: 58		NOTE: *** Pre-Construction PCI ***											
Inspection Comments:														
Sample Number:	301		Type:	R		Area:	5000.00 SqFt		PCI:	55				
Sample Comments:														
43	BLOCK CR		L	110.00 SqFt										
45	DEPRESSION		L	9.00 SqFt										
48	L & T CR		L	208.00 Ft										
48	L & T CR		M	50.00 Ft										
52	RAVELING		L	5000.00 SqFt										
56	SWELLING		L	40.00 SqFt										
Sample Number:	306		Type:	R		Area:	5000.00 SqFt		PCI:	67				
Sample Comments:														
48	L & T CR		L	479.00 Ft										
52	RAVELING		L	5000.00 SqFt										
56	SWELLING		L	5.00 SqFt										
Sample Number:	310		Type:	R		Area:	5000.00 SqFt		PCI:	57				
Sample Comments:														
43	BLOCK CR		L	650.00 SqFt										
48	L & T CR		L	378.00 Ft										
48	L & T CR		M	45.00 Ft										
52	RAVELING		L	5000.00 SqFt										
Sample Number:	315		Type:	R		Area:	5000.00 SqFt		PCI:	67				
Sample Comments:														
48	L & T CR		L	502.00 Ft										
52	RAVELING		L	5000.00 SqFt										
56	SWELLING		L	5.00 SqFt										
Sample Number:	320		Type:	R		Area:	5000.00 SqFt		PCI:	57				
Sample Comments:														
43	BLOCK CR		L	400.00 SqFt										
48	L & T CR		L	385.00 Ft										
48	L & T CR		M	50.00 Ft										
52	RAVELING		L	5000.00 SqFt										
56	SWELLING		L	26.00 SqFt										
Sample Number:	325		Type:	R		Area:	5000.00 SqFt		PCI:	59				
Sample Comments:														
43	BLOCK CR		L	400.00 SqFt										
48	L & T CR		L	334.00 Ft										
48	L & T CR		M	50.00 Ft										
52	RAVELING		L	5000.00 SqFt										
Sample Number:	330		Type:	R		Area:	5000.00 SqFt		PCI:	64				
Sample Comments:														

43	BLOCK CR	L	850.00	SqFt
48	L & T CR	L	205.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 335		Type: R	Area: 5000.00	PCI: 61
Sample Comments:				
43	BLOCK CR	L	1650.00	SqFt
48	L & T CR	L	212.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 340		Type: R	Area: 5000.00	PCI: 57
Sample Comments:				
43	BLOCK CR	L	650.00	SqFt
48	L & T CR	L	291.00	Ft
48	L & T CR	M	38.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	15.00	SqFt
<hr/>				
Sample Number: 345		Type: R	Area: 5000.00	PCI: 53
Sample Comments:				
43	BLOCK CR	L	2100.00	SqFt
48	L & T CR	L	324.00	Ft
48	L & T CR	M	100.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 350		Type: R	Area: 5000.00	PCI: 44
Sample Comments:				
43	BLOCK CR	L	1100.00	SqFt
43	BLOCK CR	M	300.00	SqFt
48	L & T CR	L	200.00	Ft
48	L & T CR	M	60.00	Ft
52	RAVELING	L	4900.00	SqFt
52	RAVELING	M	100.00	SqFt
56	SWELLING	L	105.00	SqFt
<hr/>				
Sample Number: 354		Type: R	Area: 5000.00	PCI: 56
Sample Comments:				
43	BLOCK CR	L	740.00	SqFt
45	DEPRESSION	L	238.00	SqFt
48	L & T CR	L	254.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	10.00	SqFt

Network:		SPG		Name:		ALBERT WHITTED AIRPORT						
Branch:	TW B4			Name:	TAXIWAY B4		Use:	TAXIWAY	Area:	6,955 SqFt		
Section:	285		of	2	From:	-			To:	-		
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:				Category:	Rank: P	
Area:	2,142 SqFt		Length:	62 Ft		Width:	35 Ft					
Slabs:			Slab Length:	Ft		Slab Width:	Ft			Joint Length:	Ft	
Shoulder:			Street Type:			Grade:	0			Lanes:	0	
Section Comments:												
Work Date:	1/1/1950			Work Type:	New Construction - AC			Code:	NC-AC		Is Major M&R:	True
Work Date:	1/1/1992			Work Type:	Overlay - AC Structural			Code:	OL-AS		Is Major M&R:	True
Work Date:	4/1/2022			Work Type:	Mill and Overlay			Code:	ML-OVL		Is Major M&R:	True
Last Insp. Date:	12/11/2018			TotalSamples:	57		Surveyed:	12				
Conditions:	PCI: 58		NOTE: *** Pre-Construction PCI ***									
Inspection Comments:												
Sample Number:	301		Type:	R		Area:	5000.00 SqFt		PCI:	55		
Sample Comments:												
43	BLOCK CR		L	110.00 SqFt								
45	DEPRESSION		L	9.00 SqFt								
48	L & T CR		L	208.00 Ft								
48	L & T CR		M	50.00 Ft								
52	RAVELING		L	5000.00 SqFt								
56	SWELLING		L	40.00 SqFt								
Sample Number:	306		Type:	R		Area:	5000.00 SqFt		PCI:	67		
Sample Comments:												
48	L & T CR		L	479.00 Ft								
52	RAVELING		L	5000.00 SqFt								
56	SWELLING		L	5.00 SqFt								
Sample Number:	310		Type:	R		Area:	5000.00 SqFt		PCI:	57		
Sample Comments:												
43	BLOCK CR		L	650.00 SqFt								
48	L & T CR		L	378.00 Ft								
48	L & T CR		M	45.00 Ft								
52	RAVELING		L	5000.00 SqFt								
Sample Number:	315		Type:	R		Area:	5000.00 SqFt		PCI:	67		
Sample Comments:												
48	L & T CR		L	502.00 Ft								
52	RAVELING		L	5000.00 SqFt								
56	SWELLING		L	5.00 SqFt								
Sample Number:	320		Type:	R		Area:	5000.00 SqFt		PCI:	57		
Sample Comments:												
43	BLOCK CR		L	400.00 SqFt								
48	L & T CR		L	385.00 Ft								
48	L & T CR		M	50.00 Ft								
52	RAVELING		L	5000.00 SqFt								
56	SWELLING		L	26.00 SqFt								
Sample Number:	325		Type:	R		Area:	5000.00 SqFt		PCI:	59		
Sample Comments:												
43	BLOCK CR		L	400.00 SqFt								
48	L & T CR		L	334.00 Ft								
48	L & T CR		M	50.00 Ft								
52	RAVELING		L	5000.00 SqFt								
Sample Number:	330		Type:	R		Area:	5000.00 SqFt		PCI:	64		
Sample Comments:												

43	BLOCK CR	L	850.00	SqFt
48	L & T CR	L	205.00	Ft
52	RAVELING	L	5000.00	SqFt
Sample Number: 335 Type: R Area: 5000.00 SqFt PCI: 61				
Sample Comments:				
43	BLOCK CR	L	1650.00	SqFt
48	L & T CR	L	212.00	Ft
52	RAVELING	L	5000.00	SqFt
Sample Number: 340 Type: R Area: 5000.00 SqFt PCI: 57				
Sample Comments:				
43	BLOCK CR	L	650.00	SqFt
48	L & T CR	L	291.00	Ft
48	L & T CR	M	38.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	15.00	SqFt
Sample Number: 345 Type: R Area: 5000.00 SqFt PCI: 53				
Sample Comments:				
43	BLOCK CR	L	2100.00	SqFt
48	L & T CR	L	324.00	Ft
48	L & T CR	M	100.00	Ft
52	RAVELING	L	5000.00	SqFt
Sample Number: 350 Type: R Area: 5000.00 SqFt PCI: 44				
Sample Comments:				
43	BLOCK CR	L	1100.00	SqFt
43	BLOCK CR	M	300.00	SqFt
48	L & T CR	L	200.00	Ft
48	L & T CR	M	60.00	Ft
52	RAVELING	L	4900.00	SqFt
52	RAVELING	M	100.00	SqFt
56	SWELLING	L	105.00	SqFt
Sample Number: 354 Type: R Area: 5000.00 SqFt PCI: 56				
Sample Comments:				
43	BLOCK CR	L	740.00	SqFt
45	DEPRESSION	L	238.00	SqFt
48	L & T CR	L	254.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	10.00	SqFt

Network:	SPG			Name:	ALBERT WHITTED AIRPORT						
Branch:	TW C		Name:	TAXIWAY C		Use:	TAXIWAY		Area:	138,374 SqFt	
Section:	305 of 3		From:	-			To:	-		Last Const.:	5/25/2018
Surface:	AC		Family:	CA653-RL-TW-AC		Zone:			Category:	Rank: P	
Area:	75,170 SqFt		Length:	835 Ft		Width:	86 Ft				
Slabs:	Slab Length:		Ft		Slab Width:		Ft		Joint Length:	Ft	
Shoulder:	Street Type:				Grade:	0		Lanes:	0		
Section Comments:											
Work Date:	1/1/1950		Work Type: BUILT				Code:	IMPORTED		Is Major M&R: True	
Work Date:	5/25/2018		Work Type: Complete Reconstruction - AC				Code:	CR-AC		Is Major M&R: True	
Last Insp. Date:	4/6/2022		TotalSamples:	17		Surveyed:		3			
Conditions:	PCI: 94										
Inspection Comments:											
Sample Number:	100		Type:	R		Area:	3886.00 SqFt		PCI:	94	
Sample Comments:											
57	WEATHERING		L	3886.00 SqFt							
Sample Number:	107		Type:	R		Area:	5350.00 SqFt		PCI:	94	
Sample Comments:											
57	WEATHERING		L	5350.00 SqFt							
Sample Number:	204		Type:	R		Area:	4200.00 SqFt		PCI:	94	
Sample Comments:											
57	WEATHERING		L	4200.00 SqFt							

Network:	SPG		Name:	ALBERT WHITTED AIRPORT							
Branch:	TW C		Name:	TAXIWAY C		Use:	TAXIWAY	Area:	138,374 SqFt		
Section:	307 of 3		From:	-			To:	-		Last Const.:	1/1/1991
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:				Rank:	P
Area:	29,730 SqFt		Length:	705 Ft		Width:	36 Ft				
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft	
Shoulder:			Street Type:			Grade:	0		Lanes:	0	
Section Comments:											
Work Date:	1/1/1950		Work Type: New Construction - AC				Code:	NC-AC		Is Major M&R:	True
Work Date:	1/1/1991		Work Type: Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True
Work Date:	7/1/2020		Work Type: Patching - AC				Code:	PA-AC		Is Major M&R:	False
Last Insp. Date:	4/6/2022		TotalSamples:	7		Surveyed:		1			
Conditions:	PCI: 50										
Inspection Comments:											
Sample Number:	209		Type:	R		Area:	3600.00 SqFt		PCI:	50	
Sample Comments:											
43	BLOCK CR		L	1440.00		SqFt					
48	L & T CR		L	83.00		Ft					
48	L & T CR		M	10.00		Ft					
52	RAVELING		L	3600.00		SqFt					
56	SWELLING		L	400.00		SqFt					

Network:	SPG			Name:	ALBERT WHITTET AIRPORT				
Branch:	TW C		Name:	TAXIWAY C		Use:	TAXIWAY	Area:	138,374 SqFt
Section:	308	of 3	From:	-			To:	-	Last Const.: 1/1/1991
Surface:	AAC	Family:	CA653-RL-TW-AAC-APC	Zone:				Category:	Rank: P
Area:	33,474 SqFt	Length:	635 Ft	Width:	50 Ft				
Slabs:	Slab Length:		Ft	Slab Width:		Ft	Joint Length:		Ft
Shoulder:	Street Type:		Grade:		0	Lanes:		0	
Section Comments:									
Work Date:	1/1/1950	Work Type: New Construction - Initial				Code:	NU-IN	Is Major M&R:	True
Work Date:	1/1/1991	Work Type: Mill and Overlay				Code:	ML-OVL	Is Major M&R:	True
Work Date:	7/1/2020	Work Type: Patching - AC				Code:	PA-AC	Is Major M&R:	False
Last Insp. Date: 4/6/2022									
		TotalSamples:	7	Surveyed:		1			
Conditions:	PCI:	51							
Inspection Comments:									
Sample Number:	110	Type:	R	Area:	5000.00 SqFt	PCI:	51		
Sample Comments:									
45	DEPRESSION		L	28.00	SqFt				
48	L & T CR		L	560.00	Ft				
48	L & T CR		M	137.00	Ft				
52	RAVELING		L	5000.00	SqFt				
56	SWELLING		L	99.00	SqFt				

Network:	SPG	Name:	ALBERT WHITTED AIRPORT						
Branch:	TW D	Name:	TAXIWAY D		Use:	TAXIWAY	Area:	71,043 SqFt	
Section:	155	of	5	From:	-	To:	-	Last Const.:	11/1/2021
Surface:	AAC	Family:	CA653-RL-TW-AAC-APC	Zone:		Category:		Rank:	P
Area:	8,835 SqFt		Length:	200 Ft		Width:	62 Ft		
Slabs:	Slab Length:		Ft	Slab Width:		Ft	Joint Length:		Ft
Shoulder:	Street Type:			Grade:	0	Lanes:		0	
Section Comments:									
Work Date:	1/1/1991		Work Type: New Construction - AC			Code:	NC-AC	Is Major M&R:	True
Work Date:	1/1/1991		Work Type: OVERLAY			Code:	IMPORTED	Is Major M&R:	True
Work Date:	11/1/2021		Work Type: Mill and Overlay			Code:	ML-OVL	Is Major M&R:	True
Last Insp. Date:	12/11/2018		TotalSamples:	2		Surveyed:	2		
Conditions:	PCI:	61	NOTE: *** Pre-Construction PCI ***						
Inspection Comments:									
Sample Number:	100	Type:	R	Area:	3133.00 SqFt		PCI:	69	
Sample Comments:									
48	L & T CR	L	96.00 Ft						
52	RAVELING	L	3133.00 SqFt						
Sample Number:	101	Type:	R	Area:	5703.00 SqFt		PCI:	57	
Sample Comments:									
45	DEPRESSION	H	16.00 SqFt						
48	L & T CR	L	65.00 Ft						
50	PATCHING	M	352.00 SqFt						
52	RAVELING	L	5351.00 SqFt						

Network:	SPG		Name:	ALBERT WHITTED AIRPORT					
Branch:	TW D		Name:	TAXIWAY D		Use:	TAXIWAY	Area:	71,043 SqFt
Section:	157	of 5	From:	-			To:	-	
Surface:	AAC	Family:	CA653-RL-TW-AAC-APC		Zone:	Category:			Rank: P
Area:	3,327 SqFt		Length:	75 Ft		Width:	40 Ft		
Slabs:	Slab Length:		Ft		Slab Width:	Ft		Joint Length:	Ft
Shoulder:	Street Type:		Grade:		0		Lanes:	0	
Section Comments:									
Work Date:	1/1/1950		Work Type: New Construction - AC				Code:	NC-AC	
Work Date:	1/1/1992		Work Type: Overlay - AC Structural				Code:	OL-AS	
Work Date:	4/1/2022		Work Type: Mill and Overlay				Code:	ML-OVL	
Last Insp. Date:	12/11/2018		TotalSamples:	57		Surveyed:	12		
Conditions:	PCI:	58	NOTE: *** Pre-Construction PCI ***						
Inspection Comments:									
Sample Number:	301	Type:	R	Area:	5000.00 SqFt		PCI:	55	
Sample Comments:									
43	BLOCK CR	L	110.00	SqFt					
45	DEPRESSION	L	9.00	SqFt					
48	L & T CR	L	208.00	Ft					
48	L & T CR	M	50.00	Ft					
52	RAVELING	L	5000.00	SqFt					
56	SWELLING	L	40.00	SqFt					
Sample Number:	306	Type:	R	Area:	5000.00 SqFt		PCI:	67	
Sample Comments:									
48	L & T CR	L	479.00	Ft					
52	RAVELING	L	5000.00	SqFt					
56	SWELLING	L	5.00	SqFt					
Sample Number:	310	Type:	R	Area:	5000.00 SqFt		PCI:	57	
Sample Comments:									
43	BLOCK CR	L	650.00	SqFt					
48	L & T CR	L	378.00	Ft					
48	L & T CR	M	45.00	Ft					
52	RAVELING	L	5000.00	SqFt					
Sample Number:	315	Type:	R	Area:	5000.00 SqFt		PCI:	67	
Sample Comments:									
48	L & T CR	L	502.00	Ft					
52	RAVELING	L	5000.00	SqFt					
56	SWELLING	L	5.00	SqFt					
Sample Number:	320	Type:	R	Area:	5000.00 SqFt		PCI:	57	
Sample Comments:									
43	BLOCK CR	L	400.00	SqFt					
48	L & T CR	L	385.00	Ft					
48	L & T CR	M	50.00	Ft					
52	RAVELING	L	5000.00	SqFt					
56	SWELLING	L	26.00	SqFt					
Sample Number:	325	Type:	R	Area:	5000.00 SqFt		PCI:	59	
Sample Comments:									
43	BLOCK CR	L	400.00	SqFt					
48	L & T CR	L	334.00	Ft					
48	L & T CR	M	50.00	Ft					
52	RAVELING	L	5000.00	SqFt					
Sample Number:	330	Type:	R	Area:	5000.00 SqFt		PCI:	64	
Sample Comments:									

43	BLOCK CR	L	850.00	SqFt
48	L & T CR	L	205.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 335		Type: R	Area: 5000.00 SqFt	PCI: 61
Sample Comments:				
43	BLOCK CR	L	1650.00	SqFt
48	L & T CR	L	212.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 340		Type: R	Area: 5000.00 SqFt	PCI: 57
Sample Comments:				
43	BLOCK CR	L	650.00	SqFt
48	L & T CR	L	291.00	Ft
48	L & T CR	M	38.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	15.00	SqFt
<hr/>				
Sample Number: 345		Type: R	Area: 5000.00 SqFt	PCI: 53
Sample Comments:				
43	BLOCK CR	L	2100.00	SqFt
48	L & T CR	L	324.00	Ft
48	L & T CR	M	100.00	Ft
52	RAVELING	L	5000.00	SqFt
<hr/>				
Sample Number: 350		Type: R	Area: 5000.00 SqFt	PCI: 44
Sample Comments:				
43	BLOCK CR	L	1100.00	SqFt
43	BLOCK CR	M	300.00	SqFt
48	L & T CR	L	200.00	Ft
48	L & T CR	M	60.00	Ft
52	RAVELING	L	4900.00	SqFt
52	RAVELING	M	100.00	SqFt
56	SWELLING	L	105.00	SqFt
<hr/>				
Sample Number: 354		Type: R	Area: 5000.00 SqFt	PCI: 56
Sample Comments:				
43	BLOCK CR	L	740.00	SqFt
45	DEPRESSION	L	238.00	SqFt
48	L & T CR	L	254.00	Ft
52	RAVELING	L	5000.00	SqFt
56	SWELLING	L	10.00	SqFt

Network:	SPG			Name:	ALBERT WHITTED AIRPORT				
Branch:	TW D		Name:	TAXIWAY D		Use:	TAXIWAY	Area:	71,043 SqFt
Section:	160	of	5	From:	-		To:	-	Last Const.: 4/1/2022
Surface:	AAC	Family:	CA653-RL-TW-AAC-APC	Zone:				Category:	Rank: P
Area:	1,353 SqFt		Length:	40 Ft		Width:	35 Ft		
Slabs:	Slab Length:		Ft		Slab Width:		Ft		Joint Length: Ft
Shoulder:	Street Type:				Grade:	0		Lanes:	0
Section Comments:									
Work Date:	1/1/1991		Work Type: New Construction - Initial				Code:	NU-IN	Is Major M&R: True
Work Date:	4/1/2022		Work Type: Mill and Overlay				Code:	ML-OVL	Is Major M&R: True
Last Insp. Date:	12/11/2018		TotalSamples:	1		Surveyed: 1			
Conditions:	PCI:	65	NOTE: *** Pre-Construction PCI ***						
Inspection Comments:									
Sample Number:	100	Type:	R	Area:	2171.00 SqFt		PCI:	65	
Sample Comments:									
48	L & T CR		L	55.00 Ft					
52	RAVELING		L	2170.00 SqFt					
52	RAVELING		M	1.00 SqFt					

Network:	SPG			Name:	ALBERT WHITTED AIRPORT							
Branch:	TW D		Name:	TAXIWAY D		Use:	TAXIWAY	Area:	71,043 SqFt			
Section:	510	of	5	From:	-			To:	-		Last Const.:	1/1/2002
Surface:	AC		Family:	CA653-RL-TW-AC		Zone:		Category:	Rank: P			
Area:	33,920 SqFt		Length:	1,355 Ft		Width:	25 Ft					
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:			Street Type:			Grade:	0		Lanes:	0		
Section Comments:												
Work Date:	1/1/2002			Work Type:	New Construction - Initial			Code:	NU-IN		Is Major M&R:	True
Last Insp. Date:	4/6/2022			TotalSamples:	7			Surveyed:	1			
Conditions:	PCI:	64										
Inspection Comments:												
Sample Number:	232	Type:	R	Area:	5000.00 SqFt			PCI:	64			
Sample Comments:												
48	L & T CR		L	148.00 Ft								
48	L & T CR		M	25.00 Ft								
52	RAVELING		L	5000.00 SqFt								

Network:	SPG		Name:	ALBERT WHITTED AIRPORT							
Branch:	TW D		Name:	TAXIWAY D		Use:	TAXIWAY	Area:	71,043 SqFt		
Section:	515	of 5	From:	-			To:	-		Last Const.:	1/1/2011
Surface:	AC	Family:	CA653-RL-TW-AC		Zone:		Category:		Rank:	P	
Area:	23,608 SqFt		Length:	890 Ft		Width:	25 Ft				
Slabs:	Slab Length:		Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:	Street Type:		Grade:		0		Lanes:	0			
Section Comments:											
Work Date:	1/1/2011		Work Type:	New Construction - Initial			Code:	NU-IN		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	5		Surveyed:	1				
Conditions:	PCI:	82									
Inspection Comments:											
Sample Number:	212	Type:	R	Area:	5000.00 SqFt		PCI:	82			
Sample Comments:											
48	L & T CR		L	149.00 Ft							
57	WEATHERING		L	4750.00 SqFt							
57	WEATHERING		M	250.00 SqFt							

Network:	SPG			Name:	ALBERT WHITTED AIRPORT				
Branch:	TW D1		Name:	TAXIWAY D1		Use:	TAXIWAY	Area:	6,159 SqFt
Section:	450	of	1	From:	-	To:	-	Last Const.:	1/1/2006
Surface:	AC	Family:	CA653-RL-TW-AC	Zone:		Category:		Rank:	P
Area:	6,159 SqFt	Length:	115 Ft	Width:	50 Ft				
Slabs:		Slab Length:	Ft	Slab Width:	Ft	Joint Length:	Ft		
Shoulder:		Street Type:		Grade:	0	Lanes:	0		
Section Comments:									
Work Date:	1/1/2006	Work Type:	New Construction - Initial			Code:	NU-IN	Is Major M&R:	True
Last Insp. Date:	4/6/2022	TotalSamples:	1	Surveyed:	1				
Conditions:	PCI:	65							
Inspection Comments:									
Sample Number:	100	Type:	R	Area:	6159.00 SqFt	PCI:	65		
Sample Comments:									
48	L & T CR	L	312.00	Ft					
50	PATCHING	L	661.00	SqFt					
56	SWELLING	L	312.00	SqFt					
57	WEATHERING	L	4948.00	SqFt					
57	WEATHERING	M	550.00	SqFt					

Network:	SPG			Name:	ALBERT WHITTED AIRPORT						
Branch:	TW D2		Name:	TAXIWAY D2		Use:	TAXIWAY	Area:	29,398 SqFt		
Section:	740		of	1		From:	-		To:	-	
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:			Category:		
Area:	29,398 SqFt		Length:	405 Ft		Width:	55 Ft				
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft	
Shoulder:			Street Type:			Grade:	0		Lanes:	0	
Section Comments:											
Work Date:	1/1/2002		Work Type: New Construction - Initial				Code:	NU-IN		Is Major M&R: True	
Work Date:	7/1/2019		Work Type: Mill and Overlay				Code:	ML-OVL		Is Major M&R: True	
Last Insp. Date:	4/6/2022		TotalSamples:	6		Surveyed:	1				
Conditions:	PCI: 86										
Inspection Comments:											
Sample Number:	102		Type:	R		Area:	4848.00 SqFt		PCI:	86	
Sample Comments:											
48	L & T CR		L	118.00 Ft							
57	WEATHERING		L	4848.00 SqFt							

Network:	SPG			Name:	ALBERT WHITTED AIRPORT						
Branch:	TW D3		Name:	TAXIWAY D3		Use:	TAXIWAY	Area:	5,696 SqFt		
Section:	470	of 2	From:	-			To:	-	Last Const.:	1/1/2011	
Surface:	AC	Family:	CA653-RL-TW-AC		Zone:		Category:		Rank:	P	
Area:	3,795 SqFt		Length:	71 Ft		Width:	35 Ft				
Slabs:		Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:		Street Type:		Grade:	0		Lanes:	0			
Section Comments:											
Work Date:	1/1/2011		Work Type:	New Construction - Initial			Code:	NU-IN		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	1		Surveyed:	1				
Conditions:	PCI:	61									
Inspection Comments:											
Sample Number:	100	Type:	R	Area:	3796.00 SqFt		PCI:	61			
Sample Comments:											
45	DEPRESSION	L	15.00 SqFt								
48	L & T CR	L	98.00 Ft								
50	PATCHING	L	840.00 SqFt								
57	WEATHERING	L	2365.00 SqFt								
57	WEATHERING	M	591.00 SqFt								

Network:	SPG			Name:	ALBERT WHITTED AIRPORT						
Branch:	TW D3		Name:	TAXIWAY D3		Use:	TAXIWAY	Area:	5,696 SqFt		
Section:	475 of 2		From:	-		To:	-		Last Const.:	1/1/2006	
Surface:	AC		Family:	CA653-RL-TW-AC		Zone:			Rank:	P	
Area:	1,901 SqFt		Length:	55 Ft		Width:	25 Ft				
Slabs:	Slab Length:		Ft		Slab Width:	Ft		Joint Length:	Ft		
Shoulder:	Street Type:				Grade:	0		Lanes:	0		
Section Comments:											
Work Date:	1/1/2006		Work Type: New Construction - AC				Code:	NC-AC		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	1		Surveyed:	1				
Conditions:	PCI: 68										
Inspection Comments:											
Sample Number:	101		Type:	R		Area:	1901.00 SqFt		PCI:	68	
Sample Comments:											
48	L & T CR		L	112.00 Ft							
48	L & T CR		M	30.00 Ft							
57	WEATHERING		L	1426.00 SqFt							
57	WEATHERING		M	475.00 SqFt							

Network:	SPG			Name:	ALBERT WHITTED AIRPORT						
Branch:	TW D5		Name:	TAXIWAY D5		Use:	TAXIWAY	Area:	5,816 SqFt		
Section:	150 of 1		From:	-		To:	-		Last Const.:	6/1/2016	
Surface:	AAC		Family:	CA653-RL-TW-AAC-APC		Zone:			Rank:	P	
Area:	5,816 SqFt		Length:	92 Ft		Width:	62 Ft				
Slabs:			Slab Length:	Ft		Slab Width:	Ft		Joint Length:	Ft	
Shoulder:			Street Type:			Grade:	0		Lanes:	0	
Section Comments:											
Work Date:	1/1/1991		Work Type: New Construction - AC				Code:	NC-AC		Is Major M&R:	True
Work Date:	6/1/2016		Work Type: Mill and Overlay				Code:	ML-OVL		Is Major M&R:	True
Last Insp. Date:	4/6/2022		TotalSamples:	1		Surveyed:	1				
Conditions:	PCI: 90										
Inspection Comments:											
Sample Number:	100		Type:	R		Area:	5816.00 SqFt		PCI:	90	
Sample Comments:											
48	L & T CR		L	22.00 Ft							
57	WEATHERING		L	5816.00 SqFt							



FLORIDA DEPARTMENT OF TRANSPORTATION | AVIATION OFFICE



AVIATION